CARPENTER ROAD WIDENING
STP00-0003-00 (430) PI No. 0003430
CITY OF TIFTON / TIFT COUNTY

TYPICAL SECTION



REQUIRED FULL DEPTH PAVEMENT SECTION:
① RECYCLED ASPH CONC 9.5 MM SUPERPAVE, GP 2 ONLY. (MIX) BITUM MAT'L & W CONC. (135 LB/SY)
② RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2. (MIX) BITUM MAT'L & W CONC. (550 LB/SY)
③ RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2. (MIX) BITUM MAT'L & W CONC. (550 LB/SY)
④ GRADED AGG BASE CRSE. (GA) MATL. 1" TYP
⑤ 8" X 30" CONC. CURB & GUTTER, IA. STD. 9032 B, TYPE 2
⑥ 4" CONC. SIDEWALK

PROPERTY LINE		PROPOSED CURB & GUTTER	
EXISTING R/W		PROPOSED SIDEWALK	
REQUIRED R/W		14' FLUSH MEDIAN	
DRIVEWAY EASEMENT		WETLANDS	
		JURISDICTIONAL STREAM	