

## **PROJECT DESCRIPTION**

The proposed project would consist of the replacement of the existing bridge on SR 37/1st Avenue over Okapilco creek in the City of Moultrie. The existing 120-foot x 44-foot concrete bridge with 5-foot sidewalks on each side will be replaced with a 240-foot x 86.5-foot concrete bridge with 5-foot sidewalks on each side on the existing alignment. There is 139 to 200-feet of existing variable right-of-way. Proposed variable right-of-way will be between 150 and 200-feet.

Existing typical section consists of two, 12-foot lanes in each direction with 5-foot sidewalks, and curb and gutter on each side. The proposed typical section consists of two 12-foot lanes in each direction, 14-foot flush median, 5-foot sidewalks and curb and gutter on each side.

Traffic will be maintained via off-site detour.