

**DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA
SPECIAL PROVISION**

SECTION 682 – ELECTRICAL WIRE, CABLE, AND CONDUIT

**P. I. No. 0010782
District 7**

Section 682 - Electrical Wire, Cable, And Conduit

Add the following:

Delete Subsection 682.1 General Description and substitute the following:

682.1 General Description

This work includes furnishing and installing wire, cable, and conduit for roadway and structure lighting systems, complete or as indicated on the Plans. This work also consists of furnishing and installing a Multi-cell or Continuous Flexible Conduit System for Fiber Optic Cable, complete or as indicated on the Plans. The installation of conduit for fiber optic cable shall not require the presence of a qualified electrician on the job site.

Add the following to Subsection 682.2:

All multi-cell and continuous flexible conduit products shall meet the General Specifications as set out in these Special Provisions. Those products shall be installed, applied, inspected, and/or utilized in accordance with the Construction Section of these Special Provisions. Prior to any conduit work and within 60 days after Notice to Proceed, submit catalog sheets, engineering drawings, and maintenance procedures for review by the Engineer for all products and procedures in these Special Provisions to be used on the Project. If the products to be used are not specified within these Special Provisions or not listed separately and/or completely on the details of the Plans, submit catalog sheets, engineering drawings, factory specifications, a set of installation procedures, and a set of operation and maintenance procedures (for multi-cell conduit) for review by the Engineer. No work shall be done using these products until after submittals have been approved by the Engineer.

A summary of the products, their Sections, and each product's specification included in these Special Provisions are listed below:

A. MARKING TAPE.....Section 682.2.03

Visible marking tape, location and warning system.

B. CONDUIT, NONMETAL, TYPE 2 - POWER SERVICE.....Section 682.2.04

All conduit shall be Schedule 40 polyvinyl chloride.

C.	MULTI-CELL FACTORY INSTALLED DUCT SYSTEM.....	Section 682.2.05
----	---	------------------

The multi-cell innerducts shall be colored red, white, yellow, and orange, and utilized as noted: red = hybrid fiber optic cable; white = open spare/interconnect/control circuit; yellow = single mode fiber optic cable; and orange = multi-mode fiber optic cable.

D.	CONDUIT DUCT BANK.....	Section 682.2.06
----	------------------------	------------------

Conduit duct bank shall be a configuration of high density polyethylene conduits.

E.	CONDUIT, NONMETAL, TYPE 3	Section 682.2.07
----	---------------------------------	------------------

F.	CONDUIT, FIBERGLASS	Section 682.2.08
----	---------------------------	------------------

G.	PULL TAPE	Section 682.2.09
----	-----------------	------------------

H.	DUCT PLUGS	Section 682.2.10
----	------------------	------------------

I.	CONDUIT DETECTION WIRE	Section 682.2.11
----	------------------------------	------------------

J.	ELECTRICAL COMMUNICATION BOX.....	Section 682.2.13
----	-----------------------------------	------------------

K.	ELECTRICAL COMMUNICATION BOX REHABILITATION.....	Section 682.2.14
----	--	------------------

Add the following Subsections: 682.2.02 – 682.2.14

682.2.02 MATERIAL CERTIFICATION

The following chart provides an outline of the submittal requirements for the equipment and components for this pay item. This chart shall be used as a guide and does not relieve the Contractor from submitting additional information to form a complete submittal package.

Submit submittal data for all equipment, materials, test procedures, and routine maintenance procedures required for these items within 60 calendar days after the Notice To Proceed and prior to any installation, unless noted otherwise in the Contract Documents.

Submit to the Engineer for approval, six (6) copies of the manufacturer’s descriptive literature (catalog cuts), technical data, operational documentation, service and maintenance documentation, and all other materials required within these Special Provisions.

Provide submittal data that is neat, legible, and orderly. Neatly organize each package of submittal data and separate by hardware item. Use the “Materials Certification Package Index and Transmittal Form”, contained in Section 105.02 of the Special Provisions, for each pay item to document and list all material and components that are included in the submittal package. Any submittal data submitted without the index/transmittal form or that is incomplete will be rejected.

Item	Specification Section	Catalog Cuts	Installation Procedure	Installation Equipment	Maintenance Procedures
Marking Tape	682.2.03	X			
Conduit, Nonmetal, Type 2 - Power Service	682.2.04	X			
Multi-Cell Factory Installed Duct System	682.2.05	X	X		X
HDPE Conduit in Duct Banks	682.2.06	X			
Couplings	682.2.06	X	X	X	
Conduit, Nonmetal, Type 3	682.2.07	X			
Couplings	682.2.07	X	X	X	
Conduit, Fiberglass	682.2.08	X			
Pull Tape	682.2.09	X			
Duct Plugs	682.2.10	X			
Conduit Detection Wire	682.2.11	X			
Electrical Communication Box, Type	682.2.13	X			
Electrical Communication Box Rehabilitation	682.2.14	X			

Submittal data shall include complete technical and performance specifications on all elements of the conduit system. Below is a sample listing of submittal data requirements by 682.X.X subsection.

For *Subsection 682.2.03 Marking Tape* submit materials submittal data for the marking tape.

For *Subsection 682.2.04 Conduit, Nonmetal, Type 2 - Power Service* submit materials submittal data for the conduit, fittings, pull boxes, and electrical service wire.

For *Subsection 682.2.05 Multi-Cell Factory Installed Conduit System* submit materials data for the conduit system, innerduct, outerduct, coupling body, fittings, accessories, bends and sweeps, installation procedures, and maintenance procedures.

For *Subsection 682.2.06 Conduit Duct Bank* submit materials submittal data for conduit, couplings, and coupling procedures.

For *Subsection 682.2.07 Conduit, Nonmetal, Type 3* submit materials submittal data for conduit, couplings, and coupling procedures.

For *Subsection 682.2.08 Conduit, Fiberglass* submit materials submittal data for conduit, couplings and fittings, and coupling and fittings procedures.

For *Subsection 682.2.09 Pull Tape* submit materials submittal data for pull tape and installation procedure.

For *Subsection 682.2.10 Duct Plugs* submit materials submittal data for duct plugs for empty conduit and duct plugs with cable installed.

For *Subsection 682.2.11 Conduit Detection Wire* submit materials submittal data for conduit detection wire and testing procedure.

For *Subsection 682.2.13 Electrical Communication Box, Type ____* submit materials submittal data for electrical communication box, ring and cover, conduit terminators, cable racks and hardware, sealant, and conduit alignment jigs or spacers.

For *Subsection 682.2.14 Electrical Communication Box, Rehabilitation* submit materials submittal data for cable racks and hardware.

682.2.03 MARKING TAPE SPECIFICATIONS

A. Requirement For Use

When fiber optic cable is installed underground in conduit or directly buried or when empty conduit is installed, install a dielectric marking tape directly over the conduit or cable below finished grade. The tape shall be installed for the full length of the cable or conduit run. When the conduit or cable is in a trench backfilled with full depth concrete, no marking tape shall be installed.

B. Printing

The color of the tape shall be orange with "GEORGIA DOT FIBER OPTIC CABLE-CALL 1-404-624-2661" printed every 6.5 ft (2.0 m).

C. Physical Properties

The tape shall be a dielectric, polyolefin film tape, 0.004 in. (0.1 mm) thick, 3 in. (76 mm) wide. The tape shall be constructed using material and ink colors which will not change when exposed to acids and other destructive substances commonly found in the soil.

The physical test methods along with typical properties and values are specified below:

PROPERTY	METHOD	VALUE
Standard Weight	ASTM-D2103	0.02 lb/ft ² (0.1 kg/m ²)
Thickness-Overall	ASTM-D2103	0.004 in. (0.1 mm)
3" Tensile Break-MD	ASTM-D882	35 lbf (160 N)
3" Tensile Strength-MD	ASTM-D882	2900 psi (20000 kPa)
3" Tensile Break-TD	ASTM-D882	38 lbf (170 N)
3" Tensile Strength-TD	ASTM-D882	3160 psi (21790 kPa)
Elongation-MD	ASTM-D882	530%
Elongation-TD	ASTM-D822	660%
PPT Resistance-MD	ASTM-D2582	12 lbf (53 N)
PPT Resistance-TD	ASTM-D2582	14 lbf (62 N)
Tear Strength-3" x 8"-MD	ASTM-D2261	24 lbf (110 N)
Tear Strength-3" x 8"-TD	ASTM-D2261	32 lbf (140 N)

PPT – Puncture Propagation Tear

MD/TD – Machine Direction/ Transverse Direction

682.2.04 POWER SERVICE, NONMETAL, TYPE 2 - POWER SERVICE

Install conduit as indicated in the Plans. Conduit and fittings shall be Schedule 40 unplasticized PolyVinyl Chloride (PVC) that meets Federal Specification WC-1904-A. If the conduit is shown in the plans crossing pavement, install the conduit under the pavement via the directional bore method in accordance with Section 615 and Details. If using the directional bore method of installation, install a Schedule 40, UL-listed conduit suitable for being installed via the directional bore method that does not require solvent welds. Install Type 2 pull boxes if in unpaved shoulder or concrete ground mounted electrical junction boxes if in pavement along the conduit route between the electrical service pole and the equipment cabinet requiring power. Install the pull boxes as described in Section 647 and in Details that meet requirements in Section 925 except that the covers should be furnished with the logo "ELECTRICAL". Make any repairs to pavement required as a result of the installation of electrical junction boxes in accordance with Department standards. Within the conduit and pull boxes, install

electrical service wire that meets requirements in Section 922. Install any transformers as may be required because of voltage drops between the electrical service pole and the equipment cabinet requiring power.

682.2.05 MULTI-CELL “FACTORY INSTALLED” CONDUIT SYSTEM

A. DESCRIPTION

The multi-cell conduit system shall be a pre-assembled conduit manufactured from a 4 in. (102 mm) round outerduct containing either 3 or 4 factory installed round innerducts. The innerducts shall be held together in a square (4 conduit system) or triangular (3 conduit system) configuration by a system of spacers, bands, or other mechanism. The coupling system shall be resistant to water infiltration, air loss during cable installation and shall be capable of locking the system tightly together in order to not allow free twisting of the innerducts.

B. OUTERDUCT

All outerduct shall be 4 in. (102 mm) trade size and shall have a nominal 20 ft (6 m) lay length except for the steel conduit which shall have a minimum lay length of 10 ft (3 m). Types to be used shall be designated on the plans or in the proposal. All outerduct shall conform to the following requirements.

1. The outerduct shall have the following identification information:



Line text height shall be at least ½ in. (10 mm). Text labeling shall occur a maximum of every 2 ft (0.6 m). The text shall be indelibly printed in high contrast to the conduit. The text shall be oriented to face up for underground installation; the text shall be oriented to face down for under bridge installation.

2. The duct shall be marked with data which will provide traceability of the manufacturer, plant location, date, shift, and machine of manufacturer.
3. Any additional wording on the conduit, such as “this side up” or “this side down”, shall be consistent with the installation orientation.
4. The spigot end of the duct shall have a circumferential insertion depth mark to insure that proper insertion depth is achieved. This mark is not required for spigots with threaded fittings.

C. INNERDUCT

Innerduct shall be manufactured from Poly-vinyl Chloride (PVC) or High Density Polyethylene (HDPE).

D. COUPLING BODY

The multi-cell conduit shall be joined by use of a coupling system which effectively seals the outerducts and innerducts but allows for expansion or contraction in the system.

E. ACCESSORIES AND FITTINGS

The multi-cell conduit system shall be furnished with all necessary fittings and accessories. These shall include, but shall not be limited to, coupling kits, lubrication fittings, repair kits, manhole terminator kits w/plugs, installation accessories, deflection fittings, and epoxy adhesive kits. Each multi-cell system shall offer a complete line of fixed, rigid bends and sweeps. For applications in which the multi-cell conduit system is specified on the Plans and/or by the Engineer to be attached to a bridge or other structure, bridge hanger assemblies, expansion joints, and conduit support devices shall be required. These hanger assemblies, expansion joints, and support devices shall be designed for application to the specific bridge or structure for which they will be used, and their materials and design shall be approved by the Department prior to their use.

F. MATERIALS

Provide the Engineer with Manufacturer's test results for the required testing and certification in accordance with Subsection 106.05 of the Georgia Standard Specifications.

1. OUTERDUCT

- a. Schedule 40, Polyvinyl Chloride (PVC) Conduit - Schedule 40, polyvinyl chloride (PVC) conduit shall conform to the requirements of the National Electrical Manufacturers Association (NEMA) Standards Publication No. TC-6 and 8-2003, Type DB-120, except that the conduit shall be white in color and shall have a minimum 5 in. (127 mm) long integral bell to accommodate the coupling body.
- b. Type "C", Polyvinyl Chloride (PVC) Conduit - Type "C," polyvinyl chloride (PVC) conduit shall conform to the requirements of the National Electrical Manufacturers Association (NEMA) Standards Publication No. TC-6 and 8-2003, Type DB-120, except that the conduit shall be white in color and shall have a minimum 5 in. (127 mm) long integral bell to accommodate the coupling body.
- c. Steel Conduit - Rigid steel conduit shall meet the requirements of Sub-Section 923.2 of The Georgia Standard Specifications. All metal accessories and fitting used with the conduit shall be compatible and shall meet the galvanization requirements of Sub-Section 923. 2.
- d. "Bullet Resistant" Fiberglass Conduit - Bullet resistant fiberglass conduit shall have a minimum wall thickness of 0.250 in. (6.35 mm). The conduit shall prevent the penetration of a 0.45 caliber slug fired from a distance of 20 ft (6 m). The conduit shall conform to the following requirements when tested in accordance with the referenced specification. All accessories and fittings, including outerduct couplings and expansion joints, shall meet all the same "bullet resistant" requirements as the conduit. All conduit and fittings shall be black.

<u>PHYSICAL AND MECHANICAL PROPERTIES</u>	<u>TEST METHODS</u>
Ultimate Tensile Strength - 11,000 PSI (75800 kPa) Min.	ASTM D 2105
Dielectric Strength - 500 Volts/Mil.	ASTM D 149
Water Absorption - 1% Max.	ASTM D 570
Specific Gravity - 1.9 - 2.0	ASTM D 792
Glass Content - 68 +/- 2%	API SPEC 15 LR
Barcol Hardness - 58-52	ASTM D 2583

2. INNERDUCT (WITHIN MULTI-CELL)

Innerducts shall be manufactured from polyvinyl chloride (PVC) or high density polyethylene (HDPE). Innerducts shall be factory treated with an atomized silicone or manufactured in a manner to reduce friction during pulling of fiber optic cable. Innerduct to be used in bends and sweeps shall have a minimum burn through time of 30 minutes when tested in accordance with Generic Requirement GR-356-CORE, Issue 1, October 1995. The dimensions of innerduct shall meet the requirements of the manufacturer's catalog cuts approved by the Department.

a. PVC INNERDUCT

PVC innerduct shall be factory treated with an atomized silicone to reduce friction. The innerduct shall conform to the following requirements:

<u>COLOR OF INNERDUCTS</u>	<u>NOMINAL SIZE</u>
3-way (2 gray & 1 white)	1 1/2" (38 mm)
4-way (3 gray & 1 white)	1 1/4" (32 mm)

Note: The white innerduct shall be located directly under the print line on the outerduct.

Alternate innerduct colors shall be permitted only when requested in writing and upon receiving written approval from the Engineer.

b. HDPE INNERDUCT

HDPE innerduct shall have a permanent dry lubricant extruded within the inner wall and shall incorporate longitudinal ribs within the inner wall. HDPE innerduct shall conform to the following requirements:

<u>COLOR OF INNERDUCTS</u>	<u>NOMINAL SIZE</u>
3-way (yellow, orange, red)	1 1/2" (38 mm)

4-way (red, white, yellow, orange)

1 1/4" (32 mm)

Innerduct colors shall be oriented in a clockwise direction as shown above, looking at the spigot end of the multi-cell conduit system. The white innerduct for 4-way and yellow innerduct for 3-way shall be located directly under the print line on the outerduct.

Alternate innerduct colors shall be permitted only when requested in writing and upon receiving written approval from the Engineer.

3. COUPLING BODY

The coupling body shall be designed with either 3 or 4 bores as required. The coupling body shall be designed so that when the conduit is joined, the outer walls of the innerducts and the inner walls of the outerduct shall be sealed, providing an airtight seal from within the innerduct system and a watertight seal from the outside of the outerduct. The coupling body shall be tested for water tightness and air tightness per Bellcore TA-NWT-000356 and shall conform to the following specifications.

Water infiltration: minimum 11-foot head or more for 7 days

Air Tightness: minimum 100 PSI (690kPa)

4. BENDS AND SWEEPS

Each multi-cell system shall offer a complete line of fixed bends and sweeps. No flexible bends will be permitted. HDPE, PVC, and bullet resistant fiberglass bends and sweeps shall have compatible bell and spigot ends. Steel conduit bends and sweeps shall have compatible threads and reversing couplings for connection to the conduit. PVC innerducts shall not be allowed in bends and sweeps. In no case shall bends and sweeps exceed a 90 degree direction change. Bends and sweeps shall be available as follows:

Fixed Bends: Fixed bends for steel conduit shall be available in no less than 4 ft (1.22 m) radii in 11 1/4 degrees, 22 1/2 degrees, 45 degrees, and 90 degree bends. Fixed bends for PVC and bullet resistant fiberglass multicell conduit shall be available in radii no less than the following:

RADIUS DEGREE BEND

4 ft. (1.22 m)	11 1/4 degrees
6 ft. (1.83 m)	22 1/2 degrees
9 ft. (2.74 m)	45 and 90 degrees

682.2.06 CONDUIT DUCT BANK

A. MATERIAL

Install Conduit Duct Banks by configuring individual conduits into a continuous duct bank from termination point to termination point as shown in the Standard Details and other Contract Documents. Conduit Duct Bank, Type 1 shall include six 1-1/4" (32 mm) conduits and three 2" (51 mm) conduits. Conduit Duct Bank, Type 2 shall include eight 1-1/4" (32 mm) conduits and three 2" (51 mm) conduits. Conduit Duct Bank, Type 3 shall include four 2" (51 mm) conduits. Conduit Duct Bank, Type Special shall be as shown in the Plans.

Conduit shall be manufactured from virgin high-density polyethylene. Conduit shall be extruded from colored material for uniform full-thickness coloring. Where striping is required, a minimum of three colored longitudinal stripes of HDPE material shall be co-extruded on the conduit outer wall. The three stripes shall be equally spaced around the circumference and continuous for the entire length of conduit. Printed or embossed striping is not permitted.

All conduit shall be labeled with durable identification giving the name of the manufacturer, conduit size (inner diameter trade size and wall thickness/rating), manufacture/date codes, and sequential foot marking. Labeling shall occur at a maximum of every 2 ft (0.6 m).

Where required in the Contract Documents, conduits shall be located and secured in the conduit duct bank by conduit spacers configured into an assembly that is appropriate for the duct bank type.

1. 1-1/4 in. (32 mm) Conduit

1-1/4 in. (32 mm) Conduit shall conform to ASTM D-3035 and meet the following requirements:

- Smoothwall SDR 11
- Nominal outer diameter: 1.660 in. (42.16 mm)
- Minimum inner diameter: 1.313 in. (33.35 mm)
- Minimum wall thickness: 0.151 in. (3.84 mm)

2. 2 in. (51 mm) Conduit

2 in. (51 mm) Conduit shall conform to ASTM D-3035 and meet the following requirements:

- Smoothwall SDR 11
- Nominal outer diameter: 2.375 in. (60.32 mm)
- Minimum inner diameter: 1.885 in. (47.88 mm)
- Minimum wall thickness: 0.216 in. (5.49 mm)

3. Conduit Spacer

Conduit spacers shall be steel or molded high impact polystyrene that is resistant to rot and moisture absorption.

Spacers shall be manufactured to have an interlocking design such that spacers for different conduits can be assembled for the appropriate duct bank configuration. All spacers on the bottom of an assembly shall be “base” that includes a flat base with a minimum of 6 in² (3900 mm²) of bearing area for each bottom conduit.

B. COUPLING

Make every effort to minimize coupling. Coupling shall only be permitted with the advance permission of the Engineer.

Couplings shall be airtight and watertight. All couplings shall be installed in accordance with the conduit and the coupling manufacturer’s recommendations. Only couplings of the type specified below and approved by the conduit manufacturer are permitted.

Couplings shall be accomplished only by hydraulic press-on or electro-fusion coupling methods. Use hydraulic press-on couplings of seamless tool-grade tubular aluminum with sealing barbs and center stop. Use hydraulic compression duct coupling tools and follow all manufacturer’s installation procedures, fully inserting both conduit sections to the coupling center stop. Use pre-fabricated electro-fusion couplings that are field-installed using the coupling manufacturer’s recommended automatic self-monitoring fusing machine and installation procedures. Do not use any other coupling methods.

C. TERMINATION

Conduit duct banks shall be terminated in electrical communications boxes (ECBs) and pull boxes as shown in the Standard Details of the Contract Documents and in accordance with Section 647. Duct banks terminated in ECBs shall be installed into factory-installed knockout windows only, which shall be fully grouted and sealed around all conduits and to the full thickness of the box wall. Duct banks terminated in pull boxes shall be installed into factory-installed conduit terminators; conduit adhesive sealants recommended by the terminator and conduit manufacturers shall be used.

682.2.07 CONDUIT, NONMETAL, TYPE 3

A. MATERIAL

Conduit shall be manufactured from virgin high-density polyethylene (HDPE). Conduit shall be extruded from colored material for uniform full-thickness coloring. Where striping is required, a minimum of three colored longitudinal stripes of HDPE material shall be co-extruded on the conduit outer wall. The three stripes shall be equally spaced around the circumference and continuous for the entire length of conduit. Printed or embossed striping is not permitted. Unless otherwise noted in the Contract Documents, color code for conduit used for Type 3 installation shall comply with the Conduit Duct Bank Color Code schedule listed on the plan detail sheet. .

All conduit shall be labeled with durable identification giving the name of the manufacturer, conduit size (inner diameter trade size and wall thickness/rating), manufacture/date codes, and sequential foot marking. The conduit shall also be labeled with the following: "Georgia DOT Cable – For Assistance Call 404-624-2661". Labeling shall occur a maximum of every 4 ft. (1.2 m).

1. 1 in. (25 mm) Conduit

1 in. (25 mm) Conduit shall conform to ASTM D-3035 and shall meet the following requirements:

- Smoothwall SDR 11
- Nominal outer diameter: 1.315 in. (33.40 mm)
- Minimum inner diameter: 1.030 in. (26.16 mm)
- Minimum wall thickness: 0.120 in. (3.05 mm)

2. 1¼ in. (32 mm) Conduit

1¼ in. (32 mm) Conduit shall conform to ASTM D-3035 and shall meet the following requirements:

- Smoothwall SDR 11
- Nominal outer diameter: 1.660 in. (42.16 mm)
- Minimum inner diameter: 1.313 in. (33.35 mm)
- Minimum wall thickness: 0.151 in. (3.84 mm)

3. 1½ in. (38 mm) Conduit

1½ in. (38 mm) Conduit shall conform to ASTM D-3035 and shall meet the following requirements:

- Smoothwall SDR 11
- Nominal outer diameter: 1.900 in. (48.26 mm)
- Minimum inner diameter: 1.506 in. (38.25 mm)
- Minimum wall thickness: 0.173 in. (4.39 mm)

4. 2 in. (51 mm) Conduit

2 in. (51 mm) Conduit shall conform to ASTM D-3035 and shall meet the following requirements:

- Smoothwall SDR 11
- Nominal outer diameter: 2.375 in. (60.32 mm)
- Minimum inner diameter: 1.885 in. (47.88 mm)
- Minimum wall thickness: 0.216 in. (5.49 mm)

B. COUPLING

Make every effort to minimize coupling. Coupling shall only be permitted with the advance permission of the Engineer.

Couplings shall be airtight and watertight. All couplings shall be installed in accordance with the conduit and the coupling manufacturer's recommendations. Only couplings of the type specified below and approved by the conduit manufacturer are permitted.

Couplings shall be accomplished only by hydraulic press-on or electro-fusion coupling methods. Use hydraulic press-on couplings of seamless tool-grade tubular aluminum with sealing barbs and center stop. Use hydraulic compression duct coupling tools and follow all manufacturer's installation procedures, fully inserting both conduit sections to the coupling center stop. Use pre-fabricated electro-fusion couplings that are field-installed using the coupling manufacturer's recommended automatic self-monitoring fusing machine and installation procedures. Do not use any other coupling methods.

C. TERMINATION

Install Type 3 conduits in pull boxes in accordance with Section 647 and the Standard Details of the Contract Documents. Unless otherwise shown in the Plans, install Type 3 conduits in different types of underground spaces as follows. Type 3 conduits shall be terminated in electrical communications boxes (ECBs) and Types 6 and 7 pull boxes using factory-installed terminators in the ECB or pull box; conduit adhesive sealants recommended by the terminator and conduit manufacturers shall be used. Type 3 conduits shall be terminated in Types 1, 2, 3, 4S and 5S pull boxes bonded to a PVC sweep through the open bottom. Type 3 conduits shall be terminated in Types 4 and 5 pull boxes directly through cored holes in the side walls in accordance with Section 647.

682.2.08 CONDUIT, FIBERGLASS

A. MATERIAL

Conduit shall be manufactured from fiberglass reinforced epoxy. The conduit shall be “bullet resistant”, capable of preventing the penetration of a 0.45 caliber slug fired from a distance of 20 ft. (6 m). The conduit shall conform to the following physical and mechanical properties when tested in accordance with the referenced specification. All accessories and fittings, including outerduct couplings and expansion joints, shall meet all the same “bullet resistant” requirements as the conduit. All conduit and fittings shall be black.

PHYSICAL AND MECHANICAL PROPERTIES	TEST METHODS
Ultimate Tensile Strength - 11,000 PSI (75800 kPa) Min.	ASTM D 2105
Dielectric Strength - 500 Volts/Mil.	ASTM D 149
Water Absorption - 1% Max.	ASTM D 570
Specific Gravity - 1.9 - 2.0	ASTM D 792
Glass Content - 68 +/- 2%	API SPEC 15 LR
Barcol Hardness - 58-52	ASTM D 2583

All conduit shall conform to the following requirements:

- a. The conduit shall have the following identification information:



Line text height shall be at least ½ in. (10 mm). Text labeling shall occur a maximum of every 2 ft. (0.6 m). The text shall be indelibly printed in high contrast to the conduit. The text shall be oriented to face up for underground installation; the text shall be oriented to face down for under bridge installation.

- b. The duct shall be marked with data which will provide traceability of the manufacturer, plant location, date, shift, and machine of manufacturer.
 - c. Any additional wording on the conduit, such as “this side up” or “this side down”, shall be consistent with the installation orientation.
 - d. The spigot end of the duct shall have a circumferential insertion depth mark to insure that proper insertion depth is achieved. This mark is not required for spigots with threaded fittings.
1. 2 in. (51 mm) Conduit
 - 2 in. (51 mm) Conduit shall meet the following requirements:
 - Nominal outer diameter: 2.500 in. (tolerance +0.028”/-0.018”)
 - [63.50 mm (tolerance +0.71/-0.46)]
 - Minimum inner diameter: 2.000 in. (50.80 mm)
 - Minimum wall thickness: 0.250 in. (6.35 mm)
 2. 4 in. (102 mm) Conduit

4 in. (102 mm) Conduit shall meet the following requirements:

- Nominal outer diameter: 4.500 in. (tolerance +0.034"/-0.028")
- [114.3 mm (tolerance +0.86/-0.71)]
- Minimum inner diameter: 4.000 in. (101.6 mm)
- Minimum wall thickness: 0.250 in. (6.35 mm)

B. COUPLINGS AND FITTINGS

Coupling shall be by epoxy adhesive interference joint with bell and spigot or stop coupling fittings only. Couplings shall be airtight and watertight. All couplings shall be installed in accordance with the conduit and the coupling manufacturer's recommendations. Only couplings of the same type of fiberglass as specified above are permitted.

Fixed bends and sweeps shall be used; no flexible bends are permitted. Bends and sweeps shall be compatible with the coupling requirements above. Bends and sweeps shall be of consistent radius and inner diameter, with a minimum radius of 10 times the inner diameter. In no case shall bends exceed a 90 degree direction change.

Where the fiberglass conduit is specified in the Plans and/or by the Engineer to be attached to a bridge or other structure, bridge hanger assemblies, expansion joints, deflection fittings, and conduit support devices are required and shall be designed for application to the specific bridge or structure for which they will be used. The Department shall approve all materials and design of bridge-attached conduit systems prior to any field installation. All bridge hanger assembly components that are in contact with the conduit's outer surface shall be manufactured of the same fiberglass reinforced epoxy material or shall employ low-friction roller bushings.

C. TERMINATION

Fiberglass conduits shall be terminated in ECBs using factory-installed terminators in the ECB or by grouting and setting in a knockout window as shown in the Standard Details of the Contract Documents. Adhesive sealants recommended by the terminator and conduit manufacturers shall be used.

682.2.09 PULL TAPE

A. MATERIAL

Non-detectable pull tape shall be a polyester tape (Fibertek Part No. WP1250, NEPTCO Part No. WP1250P, or approved equal). The tape shall have the following properties:

- 1250 lb (567 kg) tensile strength
- flat, not round, construction
- printed foot markings
- pre-lubricated for reduced pulling tension at start of cable pull
- low susceptibility to absorption of moisture; moisture resistant

Detectable pull tape shall consist of a single 24 AWG copper wire with polyethylene or PVC jacket woven into a polyester tape (Fibertek Part No. WPT1250, NEPTCO Part No. DP1250P, or approved equal). The tape shall have the following properties:

- 1250 lbs. (567 kg) tensile strength
- flat, not round, construction
- printed foot markings
- pre-lubricated for reduced pulling tension at start of cable pull
- low susceptibility to absorption of moisture; moisture resistant
- corrosion resistant embedded conductor

B. INSTALLATION

Install pull tape, by hand pulling, blowing, or via vacuum method, into each empty conduit and innerduct and empty cell within a multi-cell conduit during conduit installation. Install the pull tape after conduit testing has been completed.

Install and secure 5 ft (1.5 m) of slacked pull tape in each empty conduit or cell at each vault. Secure the pull tape by tying it to the duct plug for the conduit in which it is installed.

682.2.10 DUCT PLUGS

Install blank duct plugs in each empty conduit that enters an ECB, pull box, hub, or building entrance. The plug shall be sized to fit the conduit in which it is used and shall provide a watertight and airtight seal by use of mechanical expansion. No sealants or caulks shall be used. The duct plug shall have inner rings to which pull tape can be tied. All metallic components shall be stainless steel.

Install a fiber optic innerduct plug in each conduit that enters an ECB, pull box, hub, or building entrance and has a cable installed in it. The plug shall be sized to fit the conduit and cable with which it is used and shall be a split plug with a bushing assembly for sealing around the cable by mechanical compression. All metallic components shall be stainless steel.

Install a multi-conduit duct plug in each conduit that enters an ECB, pullbox, hub, or building entrance and has one or more innerducts installed in it. The plug shall be sized to fit the outer conduit and the innerducts with which it is used and shall have split holes for each innerduct with a bushing assembly for sealing around the innerducts by mechanical compression. Seal unused innerduct holes with the appropriate plug or solid bushing. All metallic components shall be stainless steel.

Install a multi-cable duct plug in each conduit that enters an ECB, pullbox, hub, or building entrance and has two or more cables installed in it. The plug shall be sized to fit the outer conduit and the cables (with appropriately-sized split bushings) with which it is used and shall have split holes for each cable with an overall bushing assembly for sealing around the cable bushings by mechanical compression. Where the conduit is 4-inch I.D. or greater, use a multi-cable duct plug with a minimum of four cable holes. Seal unused cable holes with the appropriate plug or solid bushing. All metallic components shall be stainless steel.

682.2.11 CONDUIT DETECTION WIRE

A. MATERIAL

Conduit detection wire shall be #10 AWG stranded green-insulated THWN or THHN-THWN conductor.

B. INSTALLATION

Install one conduit detection wire in the trench during conduit installation, directly below the conduit or at the same level as the conduit. All conduit installed by use of directional boring shall include the installation of a conduit detection wire. The conduit detection wire shall be pulled with, but not in, the bored conduit. If more than one conduit is being installed in a single bore, only one conduit detection wire shall be required.

When conduit detection wire installation is required in existing conduit, install one conduit detection wire in the existing conduit or in one of the existing innerducts.

The conduit detection wire shall be continuous and unspliced between pull boxes or vaults and shall enter the pull boxes or vaults at the same location as the conduit with which it is installed. Coil and secure 5 ft (1.5 m) of conduit detection wire in each pull box or vault.

C. TESTING

Perform a continuity or tone test after installation to confirm that a continuous run of conduit detection wire was installed between pull boxes or vaults. For conduit detection wire installed in a trench, test the conduit detection wire after backfilling, compaction, and ECB installation is complete. For conduit detection wire installed in a trench with full-depth conduit backfill, test the conduit detection wire before and after backfilling. The purpose of this test is to document that no damage or separation of the conduit detection wire has occurred during the installation of wire, backfilling of the trench, or ECB installation.

Prepare a test plan, supplying equipment, conducting the test and documenting the results. Submit a test plan at least 15 working days prior to the desired testing date. Testing shall not begin until the Engineer has approved the test plan, and all tests shall be conducted in the presence of the Engineer.

682.2.12 CONDUIT TESTING

Test every conduit after the conduit is installed and before cable or pull tape is installed. Perform testing on all conduit types in this Specification, including but not limited to each cell of multi-cell conduit, each conduit in duct banks, and each innerduct. All testing shall be performed using the procedures and mandrel size recommended by the conduit

manufacturer. Testing shall be performed in the presence of the Engineer. Payment for all testing is included in the cost of the conduit.

682.2.13 ELECTRICAL COMMUNICATION BOX

Design electrical communication box and cover in accordance with ASTM C-857-95. Ensure that the walls, floor, and roof be minimum 6 in. thicknesses. Form electrical communication box from 4500 psi concrete in accordance with Section 830. Manufacture and install the electrical communication box in accordance with Details which include the dimensions associated with each type of electrical communication box. Seal all joints and seams in the electrical communication boxes created from manufacture or final assembly with manufacturer-approved sealant.

Form electrical communication box with one (1) knockout window and three (3) conduit terminators for conduit, nonmetal, type 3, 2 in. on each wall of the electrical communication box as shown in the Details. The knockout window shall remain sealed unless used for conduit duct bank termination. Provide 1 in. to 1.5 in. separation between conduit terminators. Install conduit into terminators as shown in Plans and seal with manufacturer-approved sealant.

Install two (2) cable racks, minimum 54 in. in length, on each wall of the electrical communication box as shown in the Details. Install cable racks directly to the wall or use the shortest standoff bracket possible. Include cable support arms, 7 in. to 9 in. in length, with plastic or ceramic insulators with each rack. Install one (1) cable support arm per rack for each cable installed plus one (1) cable support arm per rack as spare. Manufacture all cable racks, cable support arms, and mounting/fastening hardware of hot-dipped galvanized steel.

Install electrical communication box on a 12 in. layer of compacted coarse aggregate. Terminate conduit duct banks as shown in the Details. Prior to grouting, compact backfill for the entire length of trench to within 10 ft. of the electrical communication box. Bundle conduit, as shown on conduit duct bank installation Details, with cable ties, wire, or duct tape. Secure and align individual conduits of conduit duct bank with conduit alignment jigs, ensuring that the conduits enter the electrical communication box level, straight, and perpendicular to the wall. Construct conduit alignment jigs of plywood or use conduit spacers in accordance with Section 682. Allow grout around individual conduits of conduit duct bank to set prior to final backfilling and paving around the electrical communication box. Do not use concrete for any backfill around the electrical communication box or the conduit approaches to the electrical communication box within 10 ft.

Install electrical communication boxes in the shoulder lane whenever possible, unless shown otherwise in the Plans. In the case of narrow shoulder lanes where the electrical communication box extends beyond the edge of pavement, backfill to the top of the electrical communication box. Never install any portion of the electrical communication box in the travel lane.

Electrical communication box covers shall be imprinted with "GEORGIA DOT COMMUNICATIONS".

682.2.14 ELECTRICAL COMMUNICATION BOX REHABILITATION

Establish the location of the electrical communication box, recognizing that pavement may have been placed over the cover of the electrical communication box.

Open the cover of the electrical communication box which may include the use of power tools to accomplish and the removal of pavement.

Remove existing fiber optic cable coils temporarily ensuring no kinks or abrasions are made to the fiber optic cable.

Clean the interior of the electrical communication box and remove any debris, trash, mud, silt, and water.

Reseal all joints and seams in the electrical communication box with silicone sealant, type A as specified in Section 833.2.06.

Install two (2) cable racks per wall for inside wall widths greater than or equal to 36 in. Install one (1) rack per wall for inside wall widths less than 36 in. but greater or equal to 24 in. Install no racks for inside wall widths less than 24 in. Cable rack height shall be equal to inside height of the electrical communication box minus 6 in. Install cable racks such that the bottom of the cable rack is no greater than 3 in. from the bottom of the electrical communication box. Install cable

racks such that the distance between successive racks and the electrical communication box corners is equal to the extent permitted by the presence of knockout windows and/or conduit terminators. Install cable racks directly to the wall or use the shortest standoff bracket possible. Include cable support arms, 7 in. to 9 in. in length, with plastic or ceramic insulators with each rack. Install one (1) cable support arm per rack for each cable previously installed or being installed as part of the project plus one (1) cable support arm per rack as spare. Manufacture all cable racks, cable support arms, and mounting/fastening hardware of hot-dipped galvanized steel.

Re-set the electrical communication box and cover assembly such that the cover is at the elevation of the paved shoulder lane. Install class A concrete HES and 2 in. of 12.5 mm superpave or concrete surface to match existing paved shoulder.

Label any unlabeled fiber optic cables in accordance with labeling requirements set forth in Section 935.

If a suitable unused conduit terminator does not exist and a conduit is being terminated into an existing electrical communication box, neatly core conduit entry hole in electrical communication box wall and seal around conduit with silicone sealant or grout as necessary to prevent soil and/or water intrusion into the electrical communication box.

Add the following to Subsection 682.3.05:

A. Multi-Cell Conduit System

Secure from the manufacturer or supplier of the multi-cell system and provide to the Department complete and comprehensive written installation manuals for the complete system. At the start of the multi-cell installation, have the manufacturer or supplier provide technical assistance, as needed. At any time during the construction process, ensure that the manufacturer or supplier provides technical assistance to the Contractor and/or the Department.

For multi-cell conduit system installation under bridges, only fiberglass or steel multi-cell conduit systems shall be used. Install expansion and deflection joints according to the multi-cell conduit system manufacturer's and support hanger manufacturer's recommendations. Steel couplings shall be securely tightened; fiberglass coupling shall be epoxied. Ensure that during the construction process and at the request of the Department, the multi-cell conduit system or support hanger manufacturer provides on-site technical assistance at no additional cost to the Department.

B. Continuous Flexible Conduit

Whenever possible, conduits shall be placed in continuous manufactured lengths without coupling.

Conduit shall be placed in the straightest orientation possible, reducing bends, rises, and waves. Conduits shall be held in place during backfilling when necessary to keep straight. Where field conditions require the trench to change direction and bends are necessary, the bends shall be formed in the with the trench and should be smooth and gentle and shall not have less than a 4 foot radius (as measured to the inside surface of the conduit)

Delete Subsection 682.4 and substitute the following:

No items shall be measured separately

Multi-cell conduit system, innerduct, conduit duct bank, fiberglass conduit, and conduit nonmetal type 3 will not be measured separately for payment. Work shall include, but not limited to cutting asphalt or concrete, trenching, installing, backfilling trench, restoring asphalt or concrete, drilling existing concrete shoulder, installing #4 rebar, replacement of existing transverse joint material, directional boring, and testing of multi-cell conduit system, innerduct, conduit duct bank, conduit nonmetal type 3, fiberglass conduit, marking tape, pull tape, duct plugs, and conduit detection wire shall be included in the overall cost of the multi-cell conduit system, innerduct, conduit duct bank, fiberglass conduit, and conduit nonmetal type 3.

Conduit detection wire installed in existing conduit will not be measured separately for payment.

Conduit, nonmetal, type 2 – power service will be not be measured separately for payment. No separate measurement will be made for type 2 pull boxes, electrical junction boxes, electrical wire, directional bores, transformers, pavement repair, or any other required materials.

Electrical communication box, type ____ will not be measured separately for payment. No separate measurement will be made for, cable racks, cable support arms, compacted backfill material, compacted coarse aggregate, pavement removal, or pavement installation.

Electrical communication box rehabilitation will not be measured separately for payment by the electrical communication box that was rehabilitated as previously defined. No separate measurement will be made for cable racks, cable support arms, pavement removal, or pavement installation.

Delete Subsection 682.5 and substitute the following:

Payment for all items shall be made under CONSTRUCTION COMPLETE.