

**DEPARTMENT OF TRANSPORTATION  
STATE OF GEORGIA**

**SPECIAL PROVISION**

**Section 163—Miscellaneous Erosion Control Items**

---

*Delete Subsection 163.2 and substitute the following:*

**163.2 Materials**

Provide materials shown on the Plans, such as pipe, spillways, wood baffles, and other accessories including an anti-seep collar, when necessary. The materials shall remain the Contractor's property after removal, unless otherwise shown on the Plans.

Materials may be new or used; however, the Engineer shall approve previously used materials before use.

Materials shall meet the requirements of the following Specifications:

<b>Material</b>	<b>Section</b>
Mulch	<a href="#">893.2.02</a>
Temporary Silt Fence	<a href="#">171</a>
Concrete Aprons and Footings shall be Class A	<a href="#">500</a>
Riprap	<a href="#">603</a>
Temporary Grass	<a href="#">700</a>
Triangular Silt Barrier	<a href="#">715</a>
Lumber and Timber	<a href="#">860.2.01</a>
Preservative Treatment of Timber Products	<a href="#">863.1</a>
Corrugated Polyethylene Temporary Slope Drain Pipe	AASHTO M252 or M294

**163.2.01 Delivery, Storage, and Handling**

General Provisions 101 through 150.

*Delete Subsection 163.4.M. and substitute the following:*

**M. Stone Filter Berms**

Stone filter berms are measured for payment per linear foot (meter) required. This includes the entire structure at each location and all the work necessary for construction.

*Delete Subsection 163.5.M. and substitute the following:*

**M. Stone Filter Berms**

Stone filter berms are paid for per linear foot (meter). Payment is full compensation for all materials, construction, and removal for each. Clean stone Type 3 riprap and #3 stone are paid for on the same basis as new items. Plastic woven filter fabric is required under rock filter berms and is included in the price bid for linear foot (meter).