

PROJECT NOTES

1. THIS PROJECT DOES REQUIRE A NOI.
2. ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL OR IN AN ENGINEERED FILL.
3. EXISTING TREES THAT ARE WITHIN THE SR400 RAMP AREAS AND ARE OUTSIDE OF THE CONSTRUCTION LIMITS SHOULD NOT BE DISTURBED.
4. THERE IS NO SUITABLE PLACE TO BURY EXISTING BRIDGE/CONSTRUCTION DEBRIS WITHIN THE PROJECT'S LIMITS. THE CONTRACTOR SHALL PROVIDE AN ENVIRONMENTALLY APPROVED SITE TO DISPOSE OF EXISTING BRIDGE/CONSTRUCTION DEBRIS AT NO ADDITIONAL COST TO THE DEPARTMENT.
5. ALL EXISTING CMP WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED OR REPLACED WITH RCP.

UTILITY PROVIDERS

- ELECTRICAL: GEORGIA POWER  
 GAS: ATLANTA GAS LIGHT COMPANY  
 SEWER: FULTON COUNTY  
 WATER: CITY OF ATLANTA WATERSHED MANAGEMENT  
 TELEPHONE: AT&T FORMERLY BELLSOUTH  
 RAILROAD: NONE  
 CABLE TV: COMCAST  
 OTHER: FULTON COUNTY PUBLIC WORKS  
 CITY OF SANDY SPRINGS  
 GDOT

|          |  |      |
|----------|--|------|
| 999-2010 | DESIGN COMPLETE                          | LUMP |
| 999-2015 | CONSTRUCTION COMPLETE                    | LUMP |
| 150-9011 | TRAFFIC CONTROL WORKZONE LAW ENFORCEMENT | LUMP |

| ENVIRONMENTAL RESOURCES IMPACT TABLE |               |               |      |                               |  |                                   |                    |  |
|--------------------------------------|---------------|---------------|------|-------------------------------|--|-----------------------------------|--------------------|--|
| RESOURCE NAME/TYPE                   | LOCATION      |               | SIDE | CONSTRUCTION ACTIVITY         | PERMITTED ACTIVITY   | CONTROLLING CRITERIA              | SPECIAL PROVISIONS | COMMENTS INCLUDING ANY PERMIT EXPIRATION DATES   |
|                                      | BEGINNING STA | ENDING STA    |      |                               |  |                                   |                    |  |
| Water: Non-Buffered State Water 1    | 702+50 Ramp D | 704+50 Ramp D | RT   | No Impact                     | No Impact  | NPDES                             | None               |  |
| Water: Non-Buffered State Water 2    | N/A           | N/A           | N/A  | See Comments                  | 157 feet of piping to a non-buffered drainage ditch        | NPDES                             | None               | Construction limits changed and this is no longer with the project area  |
| Water: IS 3                          | N/A           | N/A           | N/A  | See Comments                  | 62 linear feet of piping, 30 linear feet of rip rap impact | NPDES                             | None               | Construction limits changed and this is no longer with the project area  |
| Buffer: IS 3                         | N/A           | N/A           | N/A  | See Comments                  | No Impact  | NPDES                             | None               | Construction limits changed and this is no longer with the project area  |
| Migratory Birds                      | N/A           | N/A           | N/A  | Demolition Of Existing Bridge | See Special Provision 107.236                              | Migratory Bird Treaty Act Of 1918 | 107.236            | Survey for migratory birds will be conducted prior to construction. If exclusionary devices are to be used, the Office of Environmental Services shall be contacted prior to installation. Contractor shall direct questions to the Engineer, and the Engineer shall contact Environmental Services if necessary for resolution. |



**Know what's below.  
Call before you dig.**



| REVISION DATES |  |  |
|----------------|--|--|
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |
|                |  |  |

STATE OF GEORGIA  
 DEPARTMENT OF TRANSPORTATION  
 OFFICE: INNOVATIVE PROGRAM DELIVERY  
**GENERAL NOTES**

DRAWING No. **4-001**