GUARDRAIL QUANTITIES

GA. STDS. 4000W, 4380, 4383, 4384, 4388

GUARDRAIL "W" BEAM		ANCHORAGES	
LOCATION & SIDE	LIN FT	TYPE 1	TYPE 12
29+50 - 38+05.87 LT	900	1	1
34+05.87 - 37+65.44 RT	375	1	1
TOTALS	1275	2	2

NOTE: THE ACTUAL BEGINNING AND ENDING OF GUARDRAIL MAY BE ADJUSTED TO MEET FIELD CONDITION, AS DIRECTED BY THE ENGINEER.

FIELD FENCE WOVEN WIRE	
TOTAL	145 LF

BARRIER FENCE (ORANGE) 4 FT	
TOTAL	265 LF

CONCRETE RIGHT- OF- WAY MARKERS GA. STD. 9003		
EACH	68	TOTAL

DRAINAGE ITEMS

STRUCTURE NUMBER	LOCATION	STORM DRAIN PIPE, 18 IN. H 1-10	JACK OR BORE PIPE-CONCRETE, TP IV, 18"	STORM DRAIN PIPE, 24 IN. H 1-10	JACK OR BORE PIPE-CONCRETE, TP IV, 24"	STORM DRAIN PIPE, 30 IN. H 1-10	SIDE DRAIN PIPE, 18 IN. H 1-10	GA. STD. 1122 SAFETY END SECTION, STORM DRAIN, 4:1 SLOPE	GA. STD. 1122 SAFETY END SECTION, SIDE DRAIN, 6:1 SLOPE	GA. STD. 1120 FLARED END SECTION STORM DRAIN	GA. STD. 1011A STORM SEWER MANHOLE, TP 1
		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	SIZE (IN)	SIZE (IN)	SIZE (IN)	DEPTH (FT)
A1	20+67.89 54.19' LT									18	
A2	20+75.00 36.50' RT	87						18			
A3	23+78.00 41.78' RT								18		
A4	24+28.00 48.72' RT						47		18		
A5	25+24.00 49.00' RT								18		
A6	25+71.00 49.00' RT						43		18		
A7	26+81.00 49.00' LT								18		
A8	27+29.00 44.00' LT						44		18		
A9	110+62.00 40.00' LT								18		
A10	110+16.00 40.00' LT						42		18		
A11	108+22.00 38.27' LT								18		
A12	107+67.00 37.05' LT						49		18		
B1	22+81.00 39.29' LT								18		
B2	23+39.00 40.34' LT						54		18		
B3	23+74.00 40.98' LT								18		
B4	24+32.00 42.00' LT						53		18		
B5	25+07.00 42.00' LT								18		
B6	25+53.00 42.00' LT						42		18		
B7	25+64.00 42.00' LT								18		
B8	26+29.00 40.00' LT						61		18		
C1	34+85.00 70.64' LT									18	
C2	35+00.00 65.03' RT		133							18	
D1	35+50.00 64.64' LT									24	
D2	36+10.00 62.70' RT				137					24	
E1	104+50.00 35.93' LT	84						18			
E2	105+00.00 36.00' RT							18			
E3	105+24.00 36.00' LT								18		
E4	105+70.00 34.00' LT						42		18		
F1	116+50.00 44.23' LT					61		30			
F2	116+50.00 21.22' RT										6.00
F3	116+65.00 36.89' RT	18						18			
F4	115+37.00 39.73' RT					61		30			
F4.1	116+00.00 22.33' RT					46					6.00
F5	112+70.00 41.97' RT							24			
F6	111+15.00 50.76' RT			151				24			
G1	120+28.00 34.29' RT								18		
G2	119+83.00 32.61' RT						42		18		
G3	119+11.00 34.00' RT								18		
G4	118+63.00 34.00' RT						45		18		
	TOTAL	189	133	151	137	168	564				

VOID

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY OF QUANTITIES

P. I. NO. 0000408
SPALDING COUNTY

DRAWING NO. 6-002

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	STP00-0000-00(408)	12	187

9/24/2012 3:17:42 PM \\GDOT-DSN\GDPLOT\OCE\OGC\gcf_qsvp.dgn \\gdot-dsn\geofg\resources\Gdot-2012.tbl M:\0000408\DGN\10-29-08\gdot DGN\CONSTRUCTION PRES\0000408002.prf