GUARDRAIL QUANTITIES

GA. STDS. 4000W, 4380, 4383, 4384, 4388

GUARDRAIL "W" BEAM		ANCHORAGES	
LOCATION & SIDE	LIN FT	TYPE 1	TYPE 12
29+50 - 38+05.87 LT	900	1	1
34+05.87 - 37+65.44 RT	375	1	1
TOTALS	1275	2	2

NOTE: THE ACTUAL BEGINNING AND ENDING OF GUARDRAIL MAY BE ADJUSTED TO MEET FIELD CONDITION, AS DIRECTED BY THE ENGINEER.

FIELD FENCE WOVEN WIRE	
TOTAL	145 LF

BARRIER FENCE (ORANGE) 4 FT	
TOTAL	265 LF

CONCRETE RIGHT- OF- WAY MARKERS GA. STD. 9003		
EACH	68	TOTAL

DRAINAGE ITEMS

STRUCTURE NUMBER	LOCATION	STORM DRAIN PIPE, 18 IN. H 1-10	STORM DRAIN PIPE, 18 IN. H 15-20	JACK OR BORE PIPE-18 IN. A36 STEEL, 0.375 IN CASING TK	STORM DRAIN PIPE, 24 IN. H 1-10	STORM DRIAN PIPE, 24 IN. H 15-20	JACK OR BORE PIPE-24 IN. A36 STEEL, 0.375 IN CASING TK	STORM DRAIN PIPE, 30 IN. H 1-10	SIDE DRAIN PIPE, 18 IN. H 1-10	GA. STD. 1122 SAFTEY END SECTION, STORM DRAIN, 4:1 SLOPE	GA. STD. 1122 SAFETY END SECTION, SIDE DRAIN, 6:1 SLOPE	GA. STD. 1120 FLARED END SECTION STORM DRAIN	GA. STD. 1011A STORM SEWER MANHOLE, TP 1
		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	SIZE (IN)	SIZE (IN)	SIZE (IN)	DEPTH (FT)
A1	20+67.89 54.19' LT											18	
A2	20+75.00 36.50' RT	87								18			
A3	23+78.00 41.78' RT										18		
A4	24+28.00 48.72' RT								47		18		
A5	25+24.00 49.00' RT										18		
A6	25+71.00 49.00' RT								43		18		
A7	26+81.00 49.00' LT										18		
A8	27+29.00 44.00' LT								44		18		
A9	110+62.00 40.00' LT										18		
A10	110+16.00 40.00' LT								42		18		
A11	108+22.00 38.27' LT										18		
A12	107+67.00 37.05' LT								49		18		
B1	22+81.00 39.29' LT										18		
B2	23+39.00 40.34' LT								54		18		
B3	23+74.00 40.98' LT										18		
B4	24+32.00 42.00' LT								53		18		
B5	25+07.00 42.00' LT										18		
B6	25+53.00 42.00' LT								42		18		
B7	25+64.00 42.00' LT										18		
B8	26+29.00 40.00' LT								61		18		
C1	34+85.00 70.64' LT											18	
C2	35+00.00 65.03' RT		133	133								18	
D1	35+50.00 64.64' LT											24	
D2	36+10.00 62.70' RT					137	137					24	
E1	104+50.00 35.93' LT	84								18			
E2	105+00.00 36.00' RT									18			
E3	105+24.00 36.00' LT										18		
E4	105+70.00 34.00' LT								42		18		
F1	116+50.00 44.23' LT							61		30			
F2	116+50.00 21.22' RT												6.00
F3	116+65.00 36.89' RT	18								18			
F4	115+37.00 39.73' RT							61		30			
F4.1	116+00.00 22.33' RT							46					6.00
F5	112+70.00 41.97' RT									24			
F6	111+15.00 50.76' RT				151					24			
G1	120+28.00 34.29' RT										18		
G2	119+83.00 32.61' RT								42		18		
G3	119+11.00 34.00' RT										18		
G4	118+63.00 34.00' RT								45		18		
	TOTAL	189	133	133	151	137	137	168	564				

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES
11/28/2012

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY OF QUANTITIES

P.I. NO. 0000408
SPALDING COUNTY

DRAWING NO. 6-002

STATE GA | PROJECT NUMBER STP00-0000-00(408) | SHEET NO. 12 | TOTAL SHEETS 187

11/29/2012 8:10:49 AM \\GDOT-DSN\IGOPLOT\OCF\OEC_gcf asava M:\0000408\DGN\10-29-08\gdot DGN\CONSTRUCTION PRFS\0000408DN02.prf

11/29/2012 asava Thu Nov 29 08:10:59 2012 \\gdot-dsn\geofgxresources\Gdot-2012.tbl M:\0000408.DGN 10-29-08\gdot DGN\0000408DN01.dgn