











CODE	PRACTICE STD :SPC's :SECTION	DETAIL	DESCRIPTION
St	STORM DRAIN OUTLET PROTECTION GA. STD. 1125 & 2332		A PIPE OR BOX CULVERT OUTLET HEADWALL WITH AN APRON AND DISSIPATOR BLOCKS IS USED TO PREVENT EROSION AND TO SLOW WATER. IT IS USED ON THE OUTLET OF ALL BOX CULVERTS AND ON 48" AND LARGER PIPES. MAY BE USED ON INLET FOR FLOWING STREAMS. USE ON SMALL PIPES WHEN OUTLET VELOCITY IS 12 fps AND GREATER.
	LINE CODE		
St-Rp	STORM DRAIN OUTLET PROTECTION SECTION 603		THIS ITEM IS ADDED TO 'St' WHEN ADDITIONAL PROTECTION IS NEEDED. TYPE 1 RIP RAP PLACED ON FILTER FABRIC SHOULD BE USED AT A 24" THICKNESS. MAY BE USED ON INLETS FOR FLOWING STREAMS. REFER TO CHARTS IN 'MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA' FOR QUANTITY DETERMINATION.
	PATTERN		
Su	SURFACE ROUGHENING SERRATED SLOPES CONSTRUCTION DETAIL SECTION 205		PROVIDING A ROUGH SOIL SURFACE WITH HORIZONTAL DEPRESSIONS, BY OPERATING A CLEATED DOZER ON THE SLOPE IN A VERTICAL DIRECTION. CREATING SERRATED SLOPES IN THE GRADING PROCESS TO CONSTRUCT BENCHES WILL REDUCE RUNOFF VELOCITY AND INCREASE INFILTRATION OF WATER. IN MOST CASES THIS ITEM IS NOT REQUIRED TO BE SHOWN ON THE PLANS, BUT REQUIRED TO BE COMPLETED BY THE CONTRACTOR UNDER ALL PROJECTS. IF SERRATED SLOPES ARE USED ON THE PROJECT, THEN THIS ITEM SHALL BE SHOWN WHERE SERRATED SLOPES ARE TO BE USED.
	LINE CODE		
	(LINE CODE Su IS SHOWN ON THE PLANS FOR SERRATED SLOPES WHERE SPECIFIED IN THE SOIL SURVEY.)		
Trm-1	TURF REINFORCEMENT MAT CONSTRUCTION DETAIL SECTION 711		THIS THREE DIMENSIONAL EROSION CONTROL MAT IS USED IN DITCHES TO STABILIZE THE SOIL BY REINFORCING THE GRASS ROOTS TO PROVIDE LONG-TERM PROTECTION FOR SHEAR STRESSES 0-2 psf. (THIS IS ALSO CALLED 'Mb' IN THE MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.)
	LINE CODE		
Trm-2	TURF REINFORCEMENT MAT CONSTRUCTION DETAIL SECTION 711		THIS THREE DIMENSIONAL EROSION CONTROL MAT IS USED IN DITCHES TO STABILIZE THE SOIL BY REINFORCING THE GRASS ROOTS TO PROVIDE LONG-TERM PROTECTION FOR SHEAR STRESSES 0-4 psf. (THIS IS ALSO CALLED 'Mb' IN THE MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.)
	LINE CODE		

Trm-3	TURF REINFORCEMENT MAT CONSTRUCTION DETAIL SECTION 711		THIS THREE DIMENSIONAL EROSION CONTROL MAT IS USED IN DITCHES TO STABILIZE THE SOIL BY REINFORCING THE GRASS ROOTS TO PROVIDE LONG TERM PROTECTION FOR SHEAR STRESSES 0-6 psf. (THIS IS ALSO CALLED 'Mb' IN THE MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.)
	LINE CODE		
Trm-4	TURF REINFORCEMENT MAT CONSTRUCTION DETAIL SECTION 711		THIS THREE DIMENSIONAL EROSION CONTROL MAT IS USED IN DITCHES TO STABILIZE THE SOIL BY REINFORCING THE GRASS ROOTS TO PROVIDE LONG-TERM PROTECTION FOR SHEAR STRESSES 0-8 psf. (THIS IS ALSO CALLED 'Mb' IN THE MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.)
	LINE CODE		
Trm-5	TURF REINFORCEMENT MAT CONSTRUCTION DETAIL SECTION 711		THIS THREE DIMENSIONAL EROSION CONTROL MAT IS USED IN DITCHES TO STABILIZE THE SOIL BY REINFORCING THE GRASS ROOTS TO PROVIDE LONG-TERM PROTECTION FOR SHEAR STRESSES 0-10 psf. (THIS IS ALSO CALLED 'Mb' IN THE MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.)
	LINE CODE		
Trm-6	TURF REINFORCEMENT MAT CONSTRUCTION DETAIL SECTION 711		THIS THREE DIMENSIONAL EROSION CONTROL MAT IS USED IN DITCHES TO STABILIZE THE SOIL BY REINFORCING THE GRASS ROOTS TO PROVIDE LONG-TERM PROTECTION FOR SHEAR STRESSES 0-12 psf. (THIS IS ALSO CALLED 'Mb' IN THE MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.)
	LINE CODE		

NOTE:
 1. DO NOT USE EROSION CONTROL ITEMS IN A FLOWING STREAM OR IN A TIDAL AREA BELOW HIGH TIDE.
 2. FOR ADDITIONAL INFORMATION ON THE DESIGN AND APPLICATION OF EROSION CONTROL MEASURES, SEE THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION, "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA".

DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA	
EROSION CONTROL LEGEND AND UNIFORM CODE SHEET SHEET 6 OF 6	
NO SCALE	NOV., 2007
NUMBER EC-L6	DRAWING No. 52-006

UPDATED DRAWING NO., ADDED	DATE
Trm-1, Trm-2, Trm-3, Trm-4	
AND Trm-5, AND Trm-6 CODES	
AND DESCRIPTIONS,	REVISION
TC	BY