VOID

COUNTY	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
BIBB	STP00-0000-00(566)	20	1037

SURFACING AND CONCRETE QUANTITIES

ITEMS	UNIT	SARDIS CHURCH RD	SARDIS CHURCH RD EXTENSION	GOODALL MILL	INDUSTRIAL HWY	IND HWY CONNECTOR	HOUSTON RD	AVONDALE MILL RD	MINCHEW RD	RAMP A	RAMP B	RAMP C	RAMP D	US 247	TEMPORARY PVMT	APPROACH SLAB INLAY	DRIVEWAYS	GUARDRAIL	AS DIRECTED	AS REQUIRED	TOTALS
GR AGGR BASE CRS, INCL MATL	TN	30773	103231	810	381	6382	4464	55438	3732	1347	989	1703	1282	11126	5277	0	1938	0			228873
RECYCLED ASPH. CONC. LEVELING, INCL. BITUM. MATL. & H.L.	TN	0	882	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			882
RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	3749	11267	122	355	763	669	5023	669	0	0	0	0	2474	1262	22	726	1816			28917
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	6399	22535	198	90	1527	1069	10046	1339	0	0	0	0	2622	0	0	0	0			45825
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL MITUM MATL & H LIME	TN	4266	15023	132	60	1018	713	6697	893	0	0	0	0	2038	3365	27	0	3955			38187
BITUMINOUS TACK COAT	GAL	4920	16389	155	216	1110	843	7311	974	0	0	0	0	2761	612	0	349	0			35640
MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	6483	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			6483
REINF CONC APPROACH SLAB	SY	0	1034	0	0	0	0	577	0	194	194	0	0	0	0	0	0	0			1999
CONC SIDEWALK, 4 IN, GA STD. 9031-W	SY	4446	20250	0	0	0	0	9323	0	0	0	0	0	0	0	0	0	0			34019
CONC SIDEWALK, 8 IN	SY	70	524	0	19	0	0	82	0	0	0	0	0	0	0	0	0	0			695
CONCRETE MEDIAN, 7½IN	SY	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		500	500
CONCRETE MEDIAN, 4 IN	SY	622	2262	390	0	62	0	1628	0	0	0	0	0	0	0	0	0	0			4964
DRIVEWAY CONCRETE, 6 IN TK	SY	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	640	0			640
CONC VALLEY GUTTER, 6 IN	SY	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2035	0			2035
CONC CURB & GUTTER, 8 IN X 30 IN, TP 2, GA STD 9032-B	LF	9140	38228	0	0	0	0	13930	0	0	0	0	0	0	0	0	0	0			61298
CONC CURB & GUTTER, 8 IN X 30 IN, TP 7, GA STD 9032-B	LF	8555	36599	0	0	175	0	17339	0	0	0	0	0	0	0	0	0	0			62668
REM ASPH PVMT INCL BASE	SY	2358	0	0	0	0	0	0	0	0	0	0	0	3243	4743	0	0	0			10344
3' CONCRETE V GUTTER	LF	0	0	0	0	0	0	0	0	0	0	0	0	930	0	0	0	0			930
PLAIN PC CONC PVMT, CL 3 CONC, 8 INCH THK	SY	0	0	0	0	0	0	12112	0	2343	1720	2962	2229	0	0	0	0	0			21366

CONCRETE BARRIER QUANTITIES

ITEMS	UNIT	TOTALS
CONCRETE BARRIER, TYPE 21	LF	1300
CONCRETE BARRIER, TYPE 22	LF	450
CONCRETE SIDE BARRIER, TYPE 2A	LF	1800
CONCRETE SIDE BARRIER, TYPE 2C	LF	150
CONCRETE SIDE BARRIER, TYPE 7W	LF	1025
CONCRETE SIDE BARRIER, TYPE 7R	LF	2201
CONCRETE GLARE SCREEN, 18 INCH	LF	1300
CONCRETE RIGHT OF WAY MARKERS, GA STD. 9003	EA	292

REMOVE CONCRETE CULVERT WINGWALL

LOCATION	SIDE	DESCRIPTION	EACH
STA. 194+65	LT & RT	EXISTING DOUBLE 10'X10' RCBC	2

GUARDRAIL QUANTITIES

LOCATION	SIDE	"W" BEAM LF	"T" BEAM LF	ANCHORAGE TP 1	ANCHORAGE TP 12
SARDIS CH RD EXT/AVONDALE MILL RD					
192+50.00*T0*199+50.00	LT	700		1	1
193+75.00*T0*199+75.00	RT	600		1	1
201+00.00*T0*203+00.00	RT	200		1	1
200+25.00*T0*202+50.00	LT	225		1	1
ATTACH TO 7-R CONC BARRIER	LT	75	21		1
248+75.00*T0*250+50.00	LT	175		1	1
273+75.00*T0*276+00.00	RT	225		1	1
273+50.00*T0*273+75.00	LT	25		1	1
315+75.00*T0*319+75.00	RT	400		1	1
ATTACH TO BRIDGE STA 324+66.25	RT	375	21		1
ATTACH TO BRIDGE STA 324+66.25	LT	750	8	1	
BETWEEN BRIDGES	RT	332	29		
BETWEEN BRIDGES	LT	332	29		
ATTACH TO BRIDGE STA 331+48.68	RT	300	8	1	
ATTACH TO BRIDGE STA 331+48.68	LT	350	21		1
355+25*T0*363+50	RT	825		1	1
384+50*T0*390+00	RT	550		1	1
385+50*T0*391+50	LT	600		1	1
409+25*T0*412+25	RT	300		1	1
410+50*T0*413+00	LT	250		1	1
413+25*T0*416+00	RT	275		1	1
456+00*T0*460+75	LT	475		1	1
ATTACH TO BRIDGE STA 492+71.52	RT	50	21		1
ATTACH TO BRIDGE STA 492+71.52	LT	75	8	1	
ATTACH TO BRIDGE STA 496+94.52	RT	225	8	1	
ATTACH TO BRIDGE STA 496+94.52	LT	525	21		1
US 247 / SR 129 SB					
ATTACH TO 7-W CONC BARRIER	RT	175	21		1
RAMP A					
ATTACH TO BRIDGE STA 628+75.00	LT	25	21		1
ATTACH TO BRIDGE STA 628+75.00	RT	850	21		1
RAMP B					
ATTACH TO BRIDGE STA 715+33.50	LT	100	8	1	
ATTACH TO BRIDGE STA 715+33.50	RT	750	8	1	
RAMP D					
900+00*T0*908+50	RT	850		1	1
	TOTAL	11964	274	22	24

TRAFFIC CONTROL
PROJECT NO-STP00-0000-00(566) 1 LS

FIELD ENGINEER'S OFFICE - TP 3
TOTAL 1 EA

CLEARING AND GRUBBING
TOTAL 1 LUMP

IN PLACE EMBANKMENT
855224 CY

TEMPORARY BARRIER, METHOD 1
5315 LF

REMOVE CULVERT, CONCRETE

LOCATION	DESCRIPTION	LUMP
STA. 411+60	44' TRIPLE 8'X6' RCBC	1

*INCLUDES WINGWALLS & PARAPETS

PAVEMENT REINF. FABRIC STRIPS, SELF ADHESIVE, TP 2, 18"
TOTAL 9723 LF

AGGREGATE SURFACE COURSE
AS REQUIRED 5000 TN

BARRIER FENCE (ORANGE), 4 FT
TOTAL 13894 LF

GATE, FIELD FENCE - 10 FT
TOTAL 2 EA

GRANULAR EMBANKMENT, INCL MATL & HAUL
AS DIRECTED 4421 CY

GATE, FIELD FENCE - 12 FT
TOTAL 16 EA

FIELD FENCE WOVEN WIRE
TOTAL 20,780 LF

IMPACT ATTENUATOR UNIT, TYPE P-3-B-30
TOTAL 1 EA

IMPACT ATTENUATOR UNIT, TYPE P-3-S-30
TOTAL 1 EA

IMPACT ATTENUATOR UNIT, TYPE P-3-U-30
TOTAL 1 EA

TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR, TYPE 1-A
TOTAL 10 EA

BOX CULVERTS

STATION	SKEW	LENGTH (LF)	SIZE (FT X FT)	BARREL DESIGN NUMBER	BARREL CLASS "A" CONCRETE (CY)	BARREL BAR REINF. STEEL (LB)	WINGWALLS & PARAPETS CLASS "A" CONCRETE (CY)	WINGWALLS & PARAPETS BAR REINF. STEEL (LB)	APRON GA STD 2332 CLASS "A" CONCRETE (CY)	APRON GA STD 2332 BAR REINF. STEEL (LB)	FOUNDATION BACKFILL MAT'L TYP II GA STD 1030D (CY)	RIP RAP TYPE 3, 18 IN (SY)	RIP RAP TYPE 3, 24 IN (SY)	RIP RAP TYPE 3, 30 IN (SY)	PLASTIC FILTER FABRIC (SY)	GEORGIA STANDARD
STA. 194+64	75°	90	Double 10x10	1	268	32958	51	4037	13	898	83	0	0	0	0	2317, 2327, 2330, 2331
STA. 215+01	60°	200	7x4	2	169	22420	15	839	4	261	79	0	0	0	0	2323, 2329, 2331
STA. 274+92	60°	202	Double 7x4	2	305	31735	18	1069	6	407	138	214	0	0	214	2326, 2329, 2331
STA. 298+89	25°*	328	Double 5x3	1	236	34703	* 15	* 745	* 6	* 390	164	29	0	0	29	2325, 2328, 2331
STA. 310+30	90°	128	2- Double 6x4	1	269	32359	27	612	7	514	152	97	0	0	97	2325
STA. 386+50	45°	163	2- Triple 6x3	1	442	61680	38	2272	16	1148	270	72	0	0	72	2325, 2328, 2331
STA. 389+50	90°	112	Triple 6x3	1	152	21191	14	246	5	349	93	155	0	0	155	2325
STA. 411+60	90°	129	Triple 10x12	1	585	75646	65	5679	19	1344	172	45	0	0	45	2327
RAMP C																
STA. 810+00	90°	88	Triple 5x3	1	92	14256	2	237	5	308	62	0	0	0	0	2325
RAMP D																
STA. 905+50	90°	62	Triple 5x3	1	65	10044	2	237	5	308	44	0	0	0	0	2325
TOTAL					2583	336992	247	15973	86	5927	1256	612	0	0	612	

*NOTE: 45° SKEW HEADWALL

Kimley-Horn and Associates, Inc.
Engineering, Planning, and Environmental Consultants
Suite 220, 2 Sun Court
Norcross, Georgia 30092

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

DRAWING No. 6-01