BRIDGE EXCAVATION, GRADE SEPARATION		
TOTAL	3561	CY

CONC SLOPE PAV, 4 IN		
TOTAL	3309	SY

GROOVED CONCRETE		
TOTAL	8798	SY

CONCRETE BARRIER		
TOTAL	2513	LF

CONCRETE PARAPET, SPECIAL DESIGN		
TOTAL	350	LF

CLASS AA CONCRETE		
TOTAL	2271	CY

CLASS A CONCRETE		
TOTAL	94	CY

BAR REINF STEEL		
TOTAL	364344	LB

ALUM HANDRAIL, STD 3626		
TOTAL	269	LF

PILING, PSC, 14 IN SQ		
TOTAL	5810	LF

PILING, PSC, 16 IN SQ		
TOTAL	1740	LF

PILING, PSC, 24 IN SQ		
TOTAL	1140	LF

TEST PILE, PSC, 14 IN SQ		
TOTAL	5	EA

TEST PILE, PSC, 16 IN SQ		
TOTAL	3	EA

TEST PILE, PSC, 24 IN SQ		
TOTAL	2	EA

LOAD TEST, PSC, 14 IN SQ (IF REQD)		
TOTAL	5	EA

LOAD TEST, PSC, 16 IN SQ (IF REQD)		
TOTAL	2	EA

LOAD TEST, PSC, 24 IN SQ (IF REQD)		
TOTAL	1	EA

WATERPROOFING		
TOTAL	42	SY

CH LK FENCE, ZC COAT, 6FT, 9GA		
TOTAL	346	LF

SUPERSTR CONCRETE, CL AA, BR NO - 1 (657)		
TOTAL	LUMP	LS

PSC BEAMS, AASHTO TYPE II BR NO - 1		
TOTAL	1407	LF

PSC BEAMS, AASHTO TYPE III BR NO -1		
TOTAL	896	LF

SUPERSTR REINF STEEL, BR NO - 1 (124,838)		
TOTAL	LUMP	LS

SUPERSTR CONCRETE, CL AA, BR NO - 2 (568)		
TOTAL	LUMP	LS

PSC BEAMS, AASHTO, BULB TEE, 74 IN, BR NO - 2		
TOTAL	1533	LF

SUPERSTR REINF STEEL, BR NO - 2 (98,011)		
TOTAL	LUMP	LS

SUPERSTR CONCRETE, CL AA, BR NO - 3 (1,260)		
TOTAL	LUMP	LS

PSC BEAMS, AASHTO TYPE II BR NO - 3		
TOTAL	339	LF

PSC BEAMS, AASHTO TYPE III BR NO - 3		
TOTAL	773	LF

PSC BEAMS, AASHTO, BULB TEE, 54 IN, BR NO - 3		
TOTAL	3491	LF

SUPERSTR REINF STEEL, BR NO - 3 (264,019)		
TOTAL	LUMP	LS

ELASTOMERIC PROFILE BRIDGE JOINT SEALS, BR NO-4 (56)		
TOTAL	2	EA

SUPERSTR CONCRETE, CL AA, BR NO - 4 (321)		
TOTAL	LUMP	LS

STR STEEL, BR NO - 4 (772,093)		
TOTAL	LUMP	LS

SUPERSTR REINF STEEL, BR NO - 4 (101,646)		
TOTAL	LUMP	LS

Kimley-Horn and Associates, Inc.
Engineering, Planning, and Environmental Consultants
Suite 220, 2 Sun Court
Norcross, Georgia 30092

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

DRAWING No. 6-05