VOID

CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, TONE RIP RAP/ SAND BAGS	
TOTAL	140 EA

CONSTRUCTION EXIT	
TOTAL	16 EA

CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER OR BALED STRAW CHECK DAM	
TOTAL	15593 LF

CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	
TOTAL	1202 LF

CONSTRUCT AND REMOVE ROCK FILTER DAMS	
TOTAL	8 EA

CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	
TOTAL	78 EA

EROSION CONTROL MATS, SLOPES	
	31250 SY

MAINTENANCE OF TEMPORARY SILT FENCE, TP A	
TOTAL	897 LF

SOD	
TOTAL	1770 SY

EROSION CONTROL MATS, WATERWAYS	
TOTAL	5000 SY

NOTE: AS DIRECTED BY ENGINEER.

MAINTENANCE OF TEMPORARY SILT FENCE, TP C	
TOTAL	23994 LF

MAINTENANCE OF CHECK DAMS - ALL TYPES	
TOTAL	1400 LF

MAINTENANCE OF SEDIMENT BARRIER - BALED STRAW	
TOTAL	7797 LF

MAINTENANCE OF INLET SEDIMENT TRAP	
TOTAL	78 EA

MAINTENANCE OF CONSTRUCTION EXIT	
TOTAL	16 EA

MAINTENANCE OF ROCK FILTER DAM	
TOTAL	8 EA

CONSTRUCT AND REMOVE STONE FILTER RING	
TOTAL	10 EA

MAINTENANCE OF STONE FILTER RING	
TOTAL	10 EA

RIPARIAN, STREAM RESTORATION, WETLAND AND STREAM MITIGATION	
TOTAL	2 AC

WATER QUALITY INSPECTIONS	
TOTAL	36 MO

WATER QUALITY MONITORING AND SAMPLING	
TOTAL	3 EA

TEMPORARY SILT FENCE, TP A	
TOTAL	1793 LF

TEMPORARY SILT FENCE, TP C	
TOTAL	47988 LF

CONSTRUCT AND REMOVE RETROFIT		
STA. 116+07 RT	1	EA
STA. 805+50 LT	1	EA
TOTAL	2	EA

MAINTENANCE OF RETROFIT		
STA. 116+07 RT	1	EA
STA. 805+50 LT	1	EA
TOTAL	2	EA

ROCK EMBANKMENT		
TOTAL	14000	CY

PLASTIC FILTER FABRIC		
TOTAL	26531	SY

*SEE DETAIL ON SHEET 04-002

BARE ROOT SEEDLING AND PLANTINGS		
TOTAL	291	EA

GRASSING

AREAS	TEMPORARY GRASSING	MULCH	PERMANENT GRASSING	AGRICULTURAL LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT
	AC	TN	AC	TN	TN	LB
PERMANENT		258	43	86	31	2148
TEMPORARY	22	130				
DISTURBED		1548				
TOTAL	22	1936	43	86	31	2148

Kimley-Horn and Associates, Inc.
Engineering, Planning, and Environmental Consultants
Suite 220, 2 Sun Court
Norcross, Georgia 30092

REVISION DATES
12/03/12

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES
I-75 @ US 41 ROCKY FACE

DRAWING No. 06-014