DATE$$$	TIME$$$	PRF	DGN	COUNTY	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
$USER$		$$PENTABLE$$		APPLING/TOOMBS	BR000-0001-00(216)	308	322

WETLAND *2

ESA-SEE ENVIRONMENTAL RESOURCES IMPACT TABLE IN GENERAL NOTES FOR CONSTRUCTION RESTRICTIONS.

EASEMENT FOR CONSTRUCTION & MAINTENANCE OF SLOPES

END BRIDGE STA 88+20.00

BEGIN TEMPORARY CONCRETE BARRIER STA. 88+20

END TEMPORARY CONCRETE BARRIER STA. 90+12

Ds1 | Ds2 | Ds3

BEGIN TEMPORARY CONCRETE BARRIER STA. 91+00

WETLAND *2

ESA - WETLAND BOUNDARY

END TEMPORARY CONCRETE BARRIER STA. 96+86

BEGIN BRIDGE STA 96+86.00

MATCHLINE STA. 98+00 SEE DWG. 54.2-007

MATCHLINE STA. 83+00 SEE DWG. 54.2-005

10+00

90+00

15+00

95+00

85+00

16+00

EXISTING R/W

REQ'D R/W

BRIDGE REMOVAL

GAB

CONCRETE

ASPHALT

CONST. US 1/SR 4/SR 15

EXISTING U.S. HIGHWAY #1

US 1/SR 4/SR 15 PGL

BRUSH

WETLAND *3A

ESA - WETLAND BOUNDARY

DIRT

OPEN WATER/ WETLAND *6

3 HIGH STEEL PIPE GATE

OPEN WATER/ WETLAND *8

OPEN WATER *9

TYPE I-24* RIP RAP

END ENHANCED SWALE *1 STA 95+50.00

STONE DUMPED RIPRAP TP. 3

CHECK DAMS IN ENHANCED SWALE TO REMAIN IN PLACE

WETLAND *9A

WETLAND *8A

ESA - 25' WETLAND BUFFER

ESA - WETLAND BOUNDARY

EASEMENT FOR CONSTRUCTION AND MAINTENANCE OF BRIDGE

ESA-SEE ENVIRONMENTAL RESOURCES IMPACT TABLE IN GENERAL NOTES FOR CONSTRUCTION RESTRICTIONS.

OPEN WATER *5

WETLAND *4A

ESA - 25' OPENWATER BUFFER

ESA-SEE ENVIRONMENTAL RESOURCES IMPACT TABLE IN GENERAL NOTES FOR CONSTRUCTION RESTRICTIONS.

EASEMENT FOR THE CONSTRUCTION OF DRIVE

OPEN WATER *7

BEGIN ENHANCED SWALE *1 STA 92+50.00

ESA - 25' OPENWATER BUFFER

SEE DRAWING 5-001 FOR ENHANCED SWALE DETAILS

WETLAND

STREAM

OBLITERATE EXISTING PAVEMENT & GRADE TO DRAIN

STAGE 2 EROSION NOTES:
(a)- INSTALL ADDITIONAL BMPs AS NOTED
(b)- INSTALL PERMANENT SEEDING ALONG CUT AND FILL SLOPES
(c)- INSTALL PIPE OUTLET PROTECTION

LEGEND:

TRAFFIC ROUTE

STAGE 2
(a) SHIFT TRAFFIC AS SHOWN
(b) MAINTAIN ACCESS TO ACCESS ROAD
(c) COMPLETE CONSTRUCTION OF ACCESS ROAD AS SHOWN
(d) DEMOLISH EXISTING BRIDGES
(e) GRADE TO FINAL CONDITION
(f) CONSTRUCT GUARDRAIL ON WEST SIDE OF PROPOSED ROADWAY AND COMPLETE CONSTRUCTION OF GUARDRAIL AT ACCESS ROAD
(g) REMOVE TEMPORARY GUARDRAIL AND ANCHOR AT ACCESS ROAD
(e) REMOVE TEMPORARY BARRIERS SHOWN

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS.....BLA
END LIMIT OF ACCESS.....ELA
LIMIT OF ACCESS
REQ'D R/W & LIMIT OF ACCESS
ESA BOUNDARY
ORANGE BARRIER FENCE

Heath & Lineback Engineers
INCORPORATED
2390 CANTON ROAD, BUILDING 200
MARIETTA, GEORGIA 30066-5393

LAND LOT NO. : 618 & 619
LAND DISTRICT: 2
GMD : 43

SCALE IN FEET
0 50 100 200

REVISION DATES		
5/8/14		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

BMP LOCATION DETAILS STAGE 2 US 1 / SR 4 / SR 15

US 1 / SR 4 / SR 15 BRIDGE REPLACEMENT OVER ALTAMAHA RIVER, OVERFLOW 1 AND WILLIAMS CREEK
APPLING AND TOOMBS COUNTIES

DRAWING No. 54.2-006

1/5/2009 GPU