COUNTY	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
WHEELER	BR000-0001-00(220)	16	237

SUMMARY OF QUANTITIES-STANDARD SIGNS

STATION	INSTL. NO.	HIGHWAY SIGNS													SQUARE TUBE POST									BREAKAWAY SIGN SUPPORT (EACH)
		SIGN CODE	TP 1 MATL, REFL SHEETING TP 3			TP 2 MATL, REFL SHEETING TP 3			TP 1 MATL, REFL SHEETING TP 9			TP 2 MATL, REFL SHEETING TP 9			TYPE 7			TYPE 8			TYPE 9			
			SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	
US 280/SR 30																								
69+50	18	D2-3(66)-1				66" X 36"	1	11.00													12	1	12	
70+44	19	M3-4	21" X 15"	1	2.19													16	2	32				
		M1-4(30)(280)	30" X 24"	1	5.00																			
		M1-5(24)(30)	24" X 24"	1	4.00																			
		M6-3	21" X 15"	1	2.19																			
		M3-1	21" X 15"	1	2.19													18	1	18				
		M1-4(30)(319)	30" X 24"	1	5.00																			
		M1-4(30)(441)	30" X 24"	1	5.00																			
		M1-5(24)(31)	24" X 24"	1	4.00																			
		M5-1R	21" X 15"	1	2.19																			
70+50	20	R2-1(24)(55)	24" X 30"	1	5.00										13	1	13							
71+75	21	D1-2(48)	48" X 24"	1	8.00										12	1	12							
72+00	22								66" X 24"	1	11.00													
73+00	23	M2-1	21" X 15"	1	2.19													18	1	18				
		M1-4(30)(319)	30" X 24"	1	5.00																			
		M1-4(30)(441)	30" X 24"	1	5.00																			
		M1-5(24)(31)	24" X 24"	1	4.00																			
62+00	24	W4-2R(36)							36" X 36"	1	9.00				14	1	14							
60+50	25	D1-1(42)	42" X 18"	1	8.00				36TRI	1	7.46				13	1	13							
59+33	26	W2-2L(36)							36" X 36"	1	9.00				14	1	14							
		W16-8(48)							12" X 48"	1	4.00				13	1	13							
59+00	27	M3-2	21" X 15"	1	2.19													12	2	24				
		M1-4(30)(280)	30" X 24"	1	5.00																			
		M1-5(24)(30)	24" X 24"	1	4.00																			
		M6-3	21" X 15"	1	2.19																			
60+00	28	M1-4(30)(319)	30" X 24"		5.00																			
		M1-4(30)(441)	30" X 24"	1	5.00																			
		M1-5(24)(31)	24" X 24"	1	4.00																			
		M3-1	21" X 15"	1	2.19																			
		M5-1L	21" X 15"		2.19																			
55+00	29	M3-4	21"X15"		2.19																			
		M1-4(30)(319)	30" X 24"		5.00																			
		M1-4(30)(441)	30" X 24"	1	5.00																			
		M1-5(24)(31)	24" X 24"	1	4.00																			
		M1-4(30)(280)	30" X 24"	1	5.00																			
		M1-5(24)(30)	24" X 24"	1	4.00																			
57+00	30	D1-2(54)	54"X24"	1	9.00													12	1	12				
56+00	31	R2-1(24)(55)	24" X 30"	1	5.00																			
SUBTOTAL #2					139.90			11.00			33.00						79			104			12	
SUBTOTAL #1					93.33			16.50			92.79						199			63			32	
TOTAL					233.23			27.50			125.79						278			167			44	

GPLN

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY QUANTITIES

BRIDGE OVER HEART OF GEORGIA RAILROAD

DRAWING No. 06-006