VOID

LOCATION		INSTL. NO.	CODE	HIGHWAY SIGNS																SQUARE TUBE POST									
				TP 1, REFL SHT TP 3					TP 1, REFL SHT TP 9				TP 2, REFL SHT TP 3				TP 2, REFL SHT TP 9				TYPE 7			TYPE 8			TYPE 9			BREAKAWAY SIGN SUPPORT
				SIZE			QTY.	TOTAL AREA (SF)	SIZE			QTY.	TOTAL AREA (SF)	SIZE			QTY.	TOTAL AREA (SF)	SIZE			QTY.	TOTAL AREA (SF)	LENGTH (LF)	QTY (EA)	TOTAL LENGTH (LF)	LENGTH (LF)	QTY (EA)	TOTAL LENGTH (LF)	LENGTH (LF)	QTY (EA)	TOTAL LENGTH (LF)	(EA)
120+20	LT	27	W3-5																48	X	48	1	16.00	14.00	2	28.0							
123+05	LT	28	W8-13																48	X	48	1	16.00	14.00	2	28.0							
134+00	RT	29	W2-1																48	X	48	1	16.00				15.00	2	30.0				2
	RT		W16-8P						48	X	12	1	4.00																				
142+08	LT	30	D3-1	48	X	12	1	4.00																11.00	1	11.0							
	LT		D3-1	48	X	12	1	4.00																									
143+05	LT	31	D3-1	48	X	12	1	4.00																12.00	1	12.0							
	LT		D3-1	48	X	12	1	4.00																									
145+50	RT	32	R2-1											36	X	48	1	12.00						14.00	2	28.0							
145+52	LT	33	R2-1											36	X	48	1	12.00						14.00	2	28.0							
151+00	LT	34	W2-1																48	X	48	1	16.00				15.00	2	30.0				2
	RT		W16-8P						48	X	12	1	4.00																				
152+00	LT	35	W3-5																48	X	48	1	16.00	14.00	2	28.0							
156+00	LT	36	D10-1	10	X	18	1	1.25																11.50	1	11.5							
156+01	RT	37	D10-1	10	X	18	1	1.25																11.50	1	11.5							
177+00	RT	38	W2-2R																48	X	48	1	16.00				15.00	2	30.0				2
			W16-8P						48	X	12	1	4.00																				
180+00	RT	39	W1-2						36	X	36	1	9.00											13.00	1	13.0							
181+00	RT	40	R3-7R	36	X	36	1	9.00																13.00	1	13.0							
185+30	LT	41	W1-7						48	X	24	1	8.00											12.00	1	12.0							
	LT		OM3-L						12	X	36	1	3.00											13.00	1	13.0							
	LT		OM3-R						12	X	36	1	3.00											13.00	1	13.0							
186+07	RT	42	R1-2						36	TRI		1	4.5											13.00	1	13.0							
186+24	RT	43	D3-1	48	X	12	1	4.00																11.00	1	11.0							
	LT		D3-1	48	X	12	1	4.00																									
187+50	RT	44	R2-1	24	X	30	1	5.00																12.50	1	12.5							
191+00	LT	45	W2-2L						36	X	36	1	9.00											14.00	2	28.0							
	LT		W16-8P						48	X	12	1	4.00																				
192+00	RT	46	M3-1	24	X	12	1	2.00																13.00	1	13.0							
	RT		M1-5	30	X	24	1	5.00																									
193+25	LT	47	W1-2						36	X	36	1	9.00											13.00	1	13.0							
US19/SR3																																	
205+00	RT	48	M2-1	21	X	15	1	2.19																13.25	1	13.3							
	RT		M1-5	30	X	24	1	5.00																									
207+44	RT	49	D1-2											60	X	24	1	10.00						12.00	2	24.0							
210+44	RT	50	M3-1	24	X	12	1	2.00																14.25	2	28.5							
	RT		M1-5	30	X	24	1	5.00																									
	RT		M6-1	21	X	15	1	2.19																									
	RT		M3-1	24	X	12	1	2.00																									
	RT		M1-4	24	X	24	1	4.00																									
	RT		M6-3	21	X	15	1	2.19																									
	RT		M3-1	24	X	12	1	2.00																									
	RT		M1-5	24	X	24	1	4.00																									
	RT		M6-3	21	X	15	1	2.19																									
212+50	LT	51	D2-2	48	X	24	1	8.00																12.00	2	24.0							
215+39	OH	52	R3-5L	30	X	36	1	7.50																									
	OH		GN24	30	X	36	1	7.50																									
	OH		IN24	30	X	36	1	7.50																									
	OH		GN24	30	X	36	1	7.50																									
217+65	RT	53	R5-1A						42	X	30	1	8.75											12.50	1	12.5							
219+45	LT	54	R1-2						36	TRI		1	4.5											13.00	1	13.0							
219+65	RT	55	R5-1						36	X	36	1	9.00											13.00	1	13.0							
TOTAL SHT 6-004								**118**					**84**					**34**					**96**			**469**			**90**				**6**

Stantec

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

LEESBURG NORTH BYPASS
STP00-0001-00(420) 9/23/2013

DRAWING No.
6-004

GPLN