11/7/2013 12:43:16 PM USER:mnerenbaum	V:\1782\active\178202011\Roadway\DGN\001420ER17.DGN 50.0000 FT / IN.	STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
		GA	STP00-0001-00(420)	289	322

VOID

Curve Data
N = KC501
Δ = 60°23'12.11" (CCW)
D = 5°24'18.94"
T = 616.77'
L = 1117.18'
E = 166.38'
R = 1060.00'
PI STA = 187+54.51
N = 636466.2672
E = 2299458.4095
e = 6.00%

EPHEMERAL CHANNEL 26

ESA RESOURCE 1

BEGIN ORANGE BARRIER FENCE STA 185+75

Co

SEE SHEET 54-018 MATCH LINE STA. 189+00

STA. 185+60.42 S.R. 195
STA. 411+50.93 LESLIE HWY

Dsl | Ds2

Cd-F @ 100' SPACING STA. 183+00 TO STA. 189+00 LT

185+00

N 7°37'47.27" W

St-Rp

Cd-F @ 100' SPACING STA. 175+00 TO STA. 181+50 LT

EASEMENT FOR CONSTRUCTION OF FENCE

180+00

PC 181+37.74

SEE SHEET 54-016 MATCH LINE STA. 175+00

REQ'D R/W & LIMIT OF ACCESS

S 88°54'39.57" E CONST. ℄ SR 195

CURVE KC501

PI 411+35.95

410+00

LESLIE HWY

CONST. ℄

REQ'D R/W

EXIST. R/W

STA 410+00 RT DTCH ELE: 252.08 ALLOW WATER TO OUTFALL TO EXISTING DITCH

STAGE 1 TRAFFIC

Cd-F @ 100' SPACING STA. 175+50 TO STA. 181+00 RT

EASEMENT FOR CONSTRUCTION OF FENCE

EPHEMERAL CHANNEL 26

N/F GRIFFITH FARMS, LLC

MATCH LINE STA. 407+00 SEE SHEET 54-024

OeA OeB NhA IgA TfA

PERMANENT CONSTRUCTION
STAGING TRAFFIC

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS BLA
END LIMIT OF ACCESS ELA
LIMIT OF ACCESS
REQ'D R/W & LIMIT OF ACCESS
ORANGE BARRIER FENCE
ESA BOUNDARY
ESA - SEE GENERAL NOTES 'ENVIRONMENTAL RESOURCES IMPACT TABLE' FOR CONSTRUCTION RESTRICTIONS.

Stantec

SCALE IN FEET
0 50 100 200

REVISION DATES		
11/05/13		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

BMP LOCATION DETAILS
PHASE 2 - STAGE 1
LEESBURG NORTH BYPASS

STP00-0001-00(420) 9/23/2013

DRAWING No. 54-017

GPLN