11/7/2013 12:43:38 PM USER:mnerenbaum	V:\1782\active\178202011\Roadway\DGN\001420ER24.DGN 50.0000 FT / IN.	STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
		GA	STP00-0001-00(420)	296	322

VOID

ESA - WETLAND BOUNDARY *5

ESA - WETLAND BOUNDARY *5

315+00

WETLAND *5

N/F HENRY A. STUDDARD JANE A. STUDDARD

EXIST. R/W

SMITHVILLE RD N CONST. ℄

N 0°00'00.00" E

L.L.L.20

L.L.L.19

WETLAND *13

ESA - WETLAND BOUNDARY *13

N/F GRIFFITH LAND HOLDINGS, LLC

@ 100' SPACING STA. 143+00 TO STA. 147+00 LT

STA. 142+53.44 S.R. 195*
STA. 311+13.00 SMITHVILLE RD N

BEGIN ORANGE BARRIER FENCE STA 136+54

END ORANGE BARRIER FENCE STA 141+25

EASEMENT FOR CONSTRUCTION OF FENCE

140+00

145+00

REQ'D R/W & LIMIT OF ACCESS

CURVE *KC318

CONST. ℄

SR 195 S 89°54'20.97" E

MATCH LINE STA. 148+00 SEE SHEET 54-025

MATCH LINE STA. 135+00 SEE SHEET 54-023

PT 139+84.19

310+00

@ 100' SPACING STA. 139+50 TO STA. 142+25 RT

@ 100' SPACING STA. 143+00 TO STA. 148+00 RT

EDWARD J. LISENBY CAROLYN A. LISENBY

CHAIN LINK FENCE

N/F HENRY A. STUDDARD & JANE A. STUDDARD

RANDALL J. LUCKIE SUSAN H. LUCKIE

SMITHVILLE RD N CONST. ℄

TEMPORARY BARRIER

5' BARBED WIRE FENCE

LEESBURG CITY LIMIT

Curve Data
N = KC318
Δ = 40°13'20.71" (CW)
D = 4°48'53.18"
T = 435.74'
L = 835.40'
E = 77.27'
R = 1190.00'
PI STA = 135+84.54
N = 636507.2234
E = 2294252.6687
e = 5.90%

PERMANENT CONSTRUCTION
STAGING TRAFFIC

PROPERTY AND EXISTING R/W LINE
REQUIRED R/W LINE
CONSTRUCTION LIMITS
EASEMENT FOR CONSTR & MAINTENANCE OF SLOPES
EASEMENT FOR CONSTR OF SLOPES
EASEMENT FOR CONSTR OF DRIVES

BEGIN LIMIT OF ACCESS BLA
END LIMIT OF ACCESS ELA
LIMIT OF ACCESS
REQ'D R/W & LIMIT OF ACCESS
ORANGE BARRIER FENCE
ESA BOUNDARY
ESA - SEE GENERAL NOTES 'ENVIRONMENTAL RESOURCES IMPACT TABLE' FOR CONSTRUCTION RESTRICTIONS.

Stantec

SCALE IN FEET
0 50 100 200

REVISION DATES		
11/05/13		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

BMP LOCATION DETAILS
PHASE 2 - STAGE 2
LEESBURG NORTH BYPASS
STP00-0001-00(420) 9/23/2013

DRAWING No. 54-024

GPLN