ITEM	DESCRIPTION	UNIT	QUAN
	ROADWAY ITEMS		
150-1000	TRAFFIC CONTROL - PROJECT STP-0001-00(575)	LS	LUMP
153-1300	FIELD ENGINEERS OFFICE TP 3	EA	1
210-0100	GRADING COMPLETE- PROJECT STP-0001-00(575)	LS	LUMP
310-1101	GR AGGR BASE CRS, INCL MATL	TN	68211
402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	2000
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL	TN	38060
402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL	TN	8155
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL	TN	10873
413-1000	BITUM TACK COAT	GL	11861
432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	1000
441-0018	DRIVEWAY CONCRETE, 8 IN TK	SY	88
441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	20153
441-0748	CONCRETE MEDIAN, 6 IN	SY	1480
441-3999	CONCRETE V GUTTER	LF	5777
441-6222	CONC CURB & GUTTER ,8 IN X 30 IN ,TP 2	LF	1000
441-6740	CONC CURB & GUTTER ,8 IN X 30 IN ,TP 7	LF	1000
446-1100	PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	LF	48200
641-1100	GUARDRAIL, TP T	LF	42
641-1200	GUARDRAIL, TP W	LF	685
641-2200	DBL FACED GUARDRAIL, TP W	LF	50
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	1
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	1
641-6000	GUARDRAIL ANCHORAGE, TP 10 D, SPCL DES	EA	1
	DRAINAGE ITEMS		
550-1150	STORM DRAIN PIPE, 15 IN, H 1-10	LF	1604
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	3144
550-1240	STORM DRAIN PIPE, 24 IN, H 1-10	LF	104
550-1300	STORM DRAIN PIPE, 30 IN, H 1-10	LF	80
550-3315	SAFETY END SECTION 15 IN,STORM DRAIN,4:1 SLOPE	EA	1
550-3324	SAFETY END SECTION 24 IN,STORM DRAIN,4:1 SLOPE	EA	5
550-3530	SAFETY END SECTION 30 IN,STORM DRAIN,6:1 SLOPE	EA	2
550-4215	FLARED END SECTION, 15 IN, STORM DRAIN	EA	2
611-4003	RECONSTRUCT MISC DRAINAGE STRUCTURE	EA	31
611-8055	ADJUST MINOR STRUCTURE TO GRADE	EA	5
668-2100	DROP INLET, GP 1	EA	75
668-4300	STORM SEWER MANHOLE ,TP 1	EA	5
	TEMPORARY EROSION CONTROL		
163-0232	TEMPORARY GRASSING	AC	26
163-0240	MULCH	TN	1000
163-0300	CONSTRUCTION EXIT	EA	38
163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE,TP 3	EA	5
163-0520	CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	LF	818
163-0528	CONSTRUCT AND REMOVE FABRIC CHECK DAM -TYPE C SILT FENCE	LF	50976
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	147
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	10071
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	39889
165-0041	MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	50976
165-0087	MAINTENANCE OF SILT CONTROL GATE,TP 3	EA	3
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	38
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	147
167-1000	WATER QUALITY MONITORING & SAMPLING	EA	2
167-1500	WATER QUALITY INSPECTIONS	MO	18
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	79778
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	20142
643-8200	BARRIER FENCE (ORANGE),4 FT	LF	9242
716-2000	EROSION CONTROL MATS, SLOPES	SY	7015
	PERMANENT EROSION CONTROL		
603-2182	STN DUMPED RIP RAP, TP III ,24 IN	SY	1070
603-7000	PLASTIC FILTER FABRIC	SY	1070
700-6910	PERMANENT GRASSING	AC	51
700-7000	AGRICULTURAL LIME	TN	87
700-7010	LIQUID LIME	GL	73
700-8000	FERTILIZER MIXED GRADE	TN	27
700-8100	FERTILIZER NITROGEN CONTENT	LB	1450
710-9000	PERMANENT SOIL REINFORCING MAT	SY	3380
716-1000	EROSION CONTROL MATS,WATERWAYS	SY	560
	SIGNING ITEMS		
632-0003	CHANGEABLE MESSAGE SIGN, PORTABLE, TYPE 3	EA	4
636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	SF	647
636-1029	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 3	SF	197
636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	1047
636-1041	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 9	SF	784
636-2070	GALV STEEL POSTS, TP 7	LF	2959
636-2080	GALV STEEL POSTS, TP 8	LF	1051
636-2090	GALV STEEL POSTS, TP 9	LF	240
636-3010	GROUND MOUNTED BREAKAWAY SIGN SUPPORT	EA	7
639-2002	STEEL WIRE STRAND CABLE ,3/8 IN	LF	1875
639-4003	STRAIN POLE TP III	EA	6

VOLKERT & ASSOCIATES, INC.
CONSULTING ENGINEERS
175 TOWNPARK DRIVE
SUITE 140
KENNESAW, GEORGIA 30144
(770) 919-9520

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF CONSULTANT DESIGN

DATE	REVISIONS	DATE	REVISIONS
3/19/08	REPLACED PAY ITEM 446-1002 WITH 446-1100	3/06/09	REV. EROS. CONT. MAINT. QUANTITIES
3/19/08	REVISED PAY ITEM 643-8200	8/25/09	REV. EROSION CONTROL QUANTITIES
5/20/08	REVISED PAY ITEM 643-8200	9/01/09	
	165-0522, 165-0523, 165-0040		
	165-0070, 167-1500, 716-2000		

GEORGIA DEPARTMENT OF TRANSPORTATION
DETAILED ESTIMATE
PROJECT STP-0001-00(575)
COUNTY FLOYD
DATE
DRAWING NO. 9-01

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-0001-00(575)	26	352

Thu Sep 03 09:00:16 2009
Thu Sep 03 09:00:16 2009

9/3/2009 9:00:22 AM \\ad01-dsk\ADPLOT\OFFICE\GA_KIMBROUGH\TEMP\ 1\ 0001575\TCH\0001575TCH1E4.pmf GA-UDT