SUMMARY OF QUANTITIES

ROADWAY ITEMS	ROADWAY PAVING ITEMS									DRIVEWAY PAVING ITEMS									CONCRETE						MISC. ITEMS		
										4" RESIDENTIAL 6" COMMERCIAL				COMMERCIAL AND RESIDENTIAL													
										CONCRETE				ASPHALT													
	RECYC. ASPHALT CONCRETE 25mm SUPERPAVE GP 2 ONLY INCL. BITUM & H-LIME (1.5") (402-3130)	RECYC. ASPHALT CONCRETE 19mm SUPERPAVE GP1 OR 2 INCL. BITUM & H-LIME (2") (402-3190)	RECYC. ASPHALT CONCRETE 25mm SUPERPAVE GP1 OR 2 INCL. BITUM & H-LIME (4") (402-3210)	GRADED AGGR. BASE COURSE, INCLUDING MATL. (310-1101)	BITUMINOUS TACK COAT (413-1000)	RECYC. APHALT CONCR LEVELING INCL. BITUM (402-6182)	MILL ASPH CONC PVMT VARIABLE DEPTH (432-5010)	CLASS "B" CONCRETE BASE OR PAVEMENT WIDENING (500-9999)	PAVEMENT REINFORCING FABRIC, BITUM BINDER INCL. BITUM (446-1100)			DRIVEWAY CONCRETE 6" THICK (441-0016)		GAB (310-1101)	ASPH CONC 12.5 mm SP, (1.5") (402-3130)	ASPH CONC 19 mm SP, (402-3190)	ASPH CONC 25 mm SP, (4") (402-3121)	BITUMINOUS TACK COAT (413-1000)	CONCRETE MEDIAN 7.5 IN (MEDIAN)	CONCRETE MEDIAN 4 IN (ISLANDS)	CONC CURB & GUTTER 6 IN x 24 IN TYPE 2 GA. STD. 9032B (441-6062)	CONC CURB & GUTTER 8 IN x 24 IN TYPE 1 GA. STD. 9032B (MOUNTABLE)		CONCRETE R/W MARKER GA. STD. 9003 (634-1200)		
DRAWING NUMBER	TON	TON	TON	TON	GAL	TON	SQ. YD.	CU. YD.	LIN. FT.			SQ. YD.		TON	TON	TON	TON	GAL	SQ. YD.	LIN. FT.	SQ. YD.	LF.	LF.		EACH		DRAWING NUMBER
13-01	154	111	259	378	89	46	1095		742					52	19	25		8							4		13-01
13-02	233	331	771	1141	169	285			700			49		39	4	20						45			8		13-02
13-03	440	784	1606	2754	351									151	56	74	147	24				312			9		13-03
13-04	266	504	1118	1736	203									73	27	36		16							4		13-04
13-05	253	459	1045	1582	207		428					63		36	13	18		6							18		13-05
13-06	48				21		647					10		4	2	2		1									13-06
14-01	29	39	49	159	25							117													1		14-01
14-02	144	192	241	787	122																				9		14-02
14-03	154	196	245	801	128	107			120					120	10	14	27	5							7		14-03
14-04	50	23	29	94	28	48	148		260																2		14-04
SUBTOTAL	1771	2639	5363	9432	1343	486	2318		1822			239		475	131	189	174	60				357			62		SUBTOTAL
AS DIRECTED	70	106	268	377	54	15	93	6	55			12		24	7	10	9	3									AS DIRECTED
TOTAL	1841	2745	5631	9809	1397	501	2411	6	1877			251		499	138	199	183	63				357			62		TOTAL

MILLED RUMBLE STRIPS (SKIP) (456-2015)

STP00-0001-00(769) 1 GLM

TRAFFIC CONTROL (150-1000)

STP00-0001-00(769) LUMP SUM

FIELD ENGINEER'S OFFICE- TYPE 3 (153-1300)

1 EACH

GRADING COMPLETE (210-0100)

STP00-0001-00(769) LUMP SUM

AGGREGATE SURFACE COURSE (318-3000)

TEMPORARY DETOUR 2	260 TONS
AS DIRECTED	500 TONS
TOTAL	760 TONS

TEMPORARY SHORING (522-1000)

STP00-0001-00(769) LUMP SUM

CHANGEABLE MESSAGE SIGN PORTABLE TYPE 3 (632-0003)

6 EA

TO BE USED AS DIRECTED BY ENGINEER

PROPOSED GUARDRAIL QUANTITIES

LOCATION	"W" BEAM (641-1200)	"T" BEAM (641-1100)	ANCHORAGES TP 1 (641-5001)	ANCHORAGES TP 12 (641-5012)
	LF	LF	EA	EA
STA 19+26.15 RT THOMPSON RD TO STA 119+40.00 RT S.R. 53	476		2	
STA 19+18.00 TO STA 19+26.15 RT THOMPSON RD		9		
STA 112+53. RT		9		1
Subtotal	476	18	2	1
As Directed by Engineer				
TOTALS	476	18	2	1

Heath & Lineback Engineers INCORPORATED
2390 CANTON ROAD, BUILDING 200
MARIETTA, GEORGIA 30066-5393

MULKEY ENGINEERS & CONSULTANTS
1255 CANTON STREET, SUITE G
ROSWELL, GEORGIA 30075
(678) 461-3511

REVISION DATES
3/2/2012

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 1
SUMMARY OF QUANTITIES
ROADWAY

DRAWING No. 6-01