4/3/2014 11:55:23 AM \\GDOT-DSN1\GOPLOT\QCF\QGC.qcf asova M:\0001817. 752180. 712430\0001817 DGN\CW Grant Current dgn\0018170N01.prf

VOID

SUMMARY OF QUANTITIES

TRAFFIC CONTROL	
PROJECT	LUMP
STP00-0001-00(817)	LUMP SUM

TRAFFIC CONTROL, PORTABLE IMPACT ATTENUATOR, TYPE 1		
TOTAL (STAGING)	26	EA

TEMPORARY CURB CUT, WHEELCHAIR RAMPS		
TOTAL FOR STAGING	8	EA

FIELD ENGINEERS OFFICE TP 3		
TOTAL	1	EA

CONSTRUCTION VIBRATION MONITORING	
PROJECT	LUMP
STP00-0001-00(817)	LUMP SUM

CLEARING & GRUBBING	
PROJECT	LUMP
STP00-0001-00(817)	LUMP SUM

UNCLASS EXCAV		
TOTAL	282,817	CY

57% IS ROCK (RAW)
INLCUDES 2 SEPTIC FIELDS AT 4000 CY EACH
INLCUDES REMOVAL/BLASTING, REUSE, & HAULING OFF EXCESS

BORROW EXCAV, INCL MATL		
TOTAL	229,517	CY

FOUND BKFILL MATL, TP II		
AS DIRECTED	4000	CY

ROCK EMBANKMENT		
AS DIRECTED (STA 432+00 TO STA 438+50)	3000	CY

SEE PROJECT NOTE #1

RAILROAD CONSTRUCTION	
PROJECT	LUMP
STP00-0001-00(817)	LUMP SUM

SUB-BALLAST		
SUBTOTAL	5393	TN
AS DIRECTED	107	TN
TOTAL	5500	TN

OVEREXCAVATION OF CONTAMINATED SOIL		
AS DIRECTED	50	CY

AGGR SURF CRS		
AS DIRECTED	500	TN

PAVEMENT ITEMS

ITEMS	UNIT	13-001	13-002	13-003	13-004	13-005	13-006	13-007	13-008	13-009	13-010	13-011	13-012	14-001	14-002	14-003	14-004	14-005	14-006	14-007	14-008	14-009	14-010	14-011	14-012	14-013	14-014	14-015	14-016	14-017	14-018	14-019	14-020	14-021	14-022	14-023	14-024	14-025	14-026	14-027	14-028	14-029	14-030	14-031	14-032	14-033	UNDER C&G	SUBTOTALS	DRIVEWAYS	STAGING	AS DIRECTED	TOTALS
RECYCLED ASPH CONC 12.5MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TON	496	384	527	565	718	338	251	220	241	298	312	88	205	497	409	286	270	394	371	395	509	237	262	236	378	167	178	167	34	103	275	113	0	36	0	150	0	88	126	0	22	51	0	0	86	0	10483	83	591	443	11600
RECYCLED ASPH CONC 19MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TON	5	104	690	710	958	451	334	293	322	397	389	40	0	57	539	381	360	525	495	527	679	316	349	315	469	49	238	223	3	137	259	106	0	44	0	192	0	117	83	0	29	63	0	0	114	0	11362	110	788	440	12700
RECYCLED ASPH CONC 25MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TON	23	470	3032	2758	4310	2029	1504	1319	1448	1787	1418	0	0	256	2424	1716	1562	2292	2227	2143	2995	1420	1571	1416	2108	218	475	446	13	206	434	458	0	67	0	288	0	176	125	0	43	95	0	0	171	0	45443	0	1184	2273	48900
RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TON	175	1097	132	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1404	0	989	107	2500
BITUM TACK COAT	GAL.	305	328	932	922	1306	615	456	400	439	542	482	51	124	354	737	520	482	705	675	684	916	430	476	429	655	145	216	203	24	125	285	162	0	40	0	175	0	107	114	0	26	58	0	0	104	0	15749	49	717	685	17200
GR AGGR BASE CRS, INCL MATL	TON	37	747	4938	4780	6858	3228	2392	2098	2304	2843	2385	0	0	407	3857	2730	2536	3711	3543	3615	4819	2259	2499	2253	3353	347	1701	1598	20	703	1508	766	0	227	0	1387*	0	601	426	0	147	324	0	0	584	15370	93901	452	4033	4414	102800
MILL ASPH CONC PVMT, VARIABLE DEPTH	SQ. YD.	1042	0	0	414	0	0	0	0	0	0	202	668	2484	5424	51	0	0	0	0	0	0	0	0	0	313	1545	0	0	373	0	971	386	0	0	0	0	0	0	770	0	0	0	0	0	0	0	14643	0	0	757	15400

*INLCUDES 404 TON
FOR DETENTION POND
ACCESS ROAD

3/1/2007 GOUNT

GEORGIA
DEPARTMENT OF TRANSPORTATION

REVISION DATES		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN
SUMMARY OF QUANTITIES

P. I. NO. 0001817

DRAWING NO. 06-001

4/3/2014 11:55:23 AM \\GDOT-DSN1\GOPLOT\QCF\QGC.qcf asova M:\0001817. 752180. 712430\0001817 DGN\CW Grant Current dgn\0018170N01.prf