COUNTY	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
MUSCOGEE/CHATTAHOOCHEE	STP-0002-00(408)	9	106

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
	ROADWAY ITEMS		
150-1000	TRAFFIC CONTROL - 0002-00(408)	LS	LUMP SUM
210-0100	GRADING COMPLETE - 0002-00(408)	LS	LUMP SUM
	INCLUDES REMOVAL OF GUARDRAIL		
310-1101	GR AGGR BASE CRS, INCL MATL	TN	217
402-3113	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1268
402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	126
402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1691
413-1000	BITUM TACK COAT	GL	473
436-1000	ASPHALTIC CONCRETE CURB - 0002-00(408)	LF	2324
441-0204	PLAIN CONC DITCH PAVING, 4 IN	SY	2528
446-1002	PVMT REINF FABRIC STRIPS, TP 2, INCL BITUM BINDER	LF	15793
641-1100	GUARDRAIL, TP T	LF	478
641-1200	GUARDRAIL, TP W	LF	7950
641-2200	DBL FACED GUARDRAIL, TP W	LF	7150
641-5001	GUARDRAIL ANCHORAGE, TP 1	EA	13
641-5012	GUARDRAIL ANCHORAGE, TP 12	EA	15
641-6000	GUARDRAIL ANCHORAGE TP 10D, SPCL DES	EA	12
	EROSION CONTROL - PERMANENT		
700-6910	PERMANENT GRASSING	AC	7
700-7000	AGRICULTURAL LIME	TN	21
700-7010	LIQUID LIME	GL	18
700-8000	FERTILIZER MIXED GRADE	TN	5
700-8100	FERTILIZER NITROGEN CONTENT	LB	700
716-2000	EROSION CONTROL MATS, SLOPES	SY	8990
	EROSION CONTROL - TEMPORARY		
163-0232	TEMPORARY GRASSING	AC	4
163-0240	MULCH	TN	102
163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	4
163-0521	CONSTRUCT AND REMOVE TEMPORARY DITCH CHECKS	EA	25
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	9
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	LF	6342
165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	979
165-0040	MAINTENANCE OF EROSION CONTROL CHECKDAMS/DITCH CHECKS	EA	25
165-0087	MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	4
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	9
167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	2
167-1500	WATER QUALITY INSPECTIONS	MO	12
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	12684
171-0030	TEMPORARY SILT FENCE, TYPE C	LF	1958
	SIGNING & MARKING		
636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	SF	54
636-1029	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 3	SF	359
636-2070	GALV STEEL POSTS, TP 7	LF	270
636-2080	GALV STEEL POSTS, TP 8	LF	397

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
	DRAINAGE ITEMS		
500-3101	CLASS A CONCRETE	CY	2
550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	159
550-3518	SAFETY END SECTION 18 IN, STORM DRAIN, 6:1 SLOPE	EA	8
576-1018	SLOPE DRAIN PIPE, 18 IN	LF	300
577-1100	METAL DRAIN INLET - COMPLETE ASSEMBLY	EA	15
611-9000	CAPPING MINOR STRUCTURE	EA	2

GRESHAM SMITH AND PARTNERS

Kimley-Horn and Associates, Inc.

REVISION DATES
2/28/05

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: TRAFFIC & SAFETY DESIGN

DETAILED ESTIMATE

DRAWING No. 9-01

GPLN

I:\015862014 Lindsay Creek Parkway\CADD\002408DT01.dgn
03/01/2005
05:19:36 PM