

GENERAL NOTES

- AT ALL EXPOSED CONDUIT LOCATIONS, FIBERGLASS OR GALVANIZED RIGID METAL CONDUIT SHALL BE USED AS SHOWN IN PLANS.
- THE CONTRACTOR SHALL LOCATE AND CONTACT ALL UTILITIES BEFORE DIGGING TO ELIMINATE ANY CONFLICTS WITH EXISTING UNDERGROUND UTILITIES. THE CONTRACTOR SHALL USE THE ONE-CALL CENTER TELEPHONE NUMBER (800) 282-7411 FOR THE MARKING OF UNDERGROUND UTILITIES. FOR HIGHWAY LIGHTING PLANS, THE CONTRACTOR SHALL CONTACT THE DEPARTMENT AT (404) 656-5396.
- THE CONTRACTOR SHALL REPLACE IN LIKE KIND AND SIZE, AT NO SEPARATE EXPENSE TO THE DEPARTMENT, ANY BARRIER WALL, FENCE, DITCH PAVING, CURBING, SIDEWALK, GUTTER, SLOPE PAVEMENT, RUMBLE STRIPS, SIGNS, GUARDRAIL, LANDSCAPING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 702), GRASSING (IN ACCORDANCE WITH GEORGIA SPECIFICATIONS SECTION 700), UTILITY SERVICE LINES, STORM DRAIN PIPES, AND ANY RETAINING WALLS THAT IS REMOVED, DAMAGED, OR DESTROYED DUE TO THE INSTALLATION OF CONDUIT, FIBER OPTIC CABLE, STRAIN POLES, OR PROPOSED DEVICES. THE CONTRACTOR WILL NOT BE REQUIRED TO MAINTAIN LANDSCAPING AS SPECIFIED IN SECTION 702.3.07 OF THE GDOT SPECIFICATIONS.
- THE CONTRACTOR SHALL REMOVE THE ASPHALT IN A MANNER TO PROVIDE A NEAT LINE, WHERE CONDUIT IS INSTALLED. THE CONTRACTOR SHALL INLAY TO MATCH EXISTING SURFACE AFTER CONDUIT IS INSTALLED. THE COST FOR ASPHALT REMOVAL AND ASPHALT INLAY SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR CONDUIT DUCT BANK.
- ANY REQUIRED EROSION CONTROL DEVICES WILL NOT BE MEASURED SEPARATELY AND SHALL BE INCLUDED IN THE COST OF THE OVERALL BID PRICE.
- WITHIN 24 HOURS, THE CONTRACTOR SHALL REPAIR ALL EXISTING CONDUIT, CABLE, OR PIPE THAT IS DAMAGED BY THE INSTALLATION OF CONDUIT, FIBER OPTIC CABLE, STRAIN POLES, OR PROPOSED DEVICES. THERE IS NO SEPARATE PAYMENT FOR THIS WORK.
- PAVEMENT MARKING AND RE-STRIPING ITEMS SHALL BE REPLACED IN LIKE KIND AND SIZE. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.
- THE CONTRACTOR SHALL CONTACT THE DEPARTMENT'S FILE PLANS ROOM (404) 656-5408 FOR DRAINAGE PLANS AS NEEDED FOR THIS PROJECT.
- CONDUIT UNDER RAMPS SHALL BE INSTALLED BY DIRECTIONAL BORING, UNLESS NOTED OTHERWISE ON THE PLANS.
- THE ELECTRICAL POWER SERVICE ASSEMBLY POINTS SHOWN ON PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE RISER POINTS. ALL SERVICE RISER POINTS SHALL BE LOCATED WITHIN THE EXISTING RIGHT OF WAY AT THE NEAREST POINT WITHIN THE EXISTING RIGHT OF WAY. THE CONTRACTOR MAY OBTAIN ALTERNATE SERVICE POINT LOCATIONS THROUGH COORDINATION WITH THE UTILITY COMPANIES. ALTERNATE SERVICE POINT LOCATIONS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL. THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A DETAILED POWER ROUTING PLAN FOR THE 2" TYPE 2 CONDUIT FROM THE ELECTRICAL POWER SERVICE ASSEMBLY POINT TO EACH DEVICE FOR REVIEW APPROVAL BY THE ENGINEER. PAYMENT FOR COPPER WIRE, PULL BOXES, TRANSFORMERS, AND DIRECTIONAL BORES ASSOCIATED WITH THE INSTALLATION OF HORIZONTAL RUNS OF POWER CONDUIT SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR 2" TYPE 2 CONDUIT.
- UNLESS SPECIFIED OTHERWISE ON THE PLANS, ALL PROPOSED STRAIN POLES SHALL BE INSTALLED A MINIMUM OF 6' BEHIND EXISTING OR REQUIRED GUARDRAIL WHERE SHOWN ON THE PLANS.
- UNLESS SHOWN OTHERWISE ON THE PLANS, THE CONTRACTOR SHALL REMOVE ALL EXISTING SHOWCASE RADAR SYSTEMS, ELECTRONICS, AND THEIR ASSOCIATED CONTROLLER CABINETS AFTER ALL DEVICES INSTALLED BY THIS PROJECT ARE IN PLACE AND FULLY OPERATIONAL. ALL EXISTING RADAR SYSTEMS, CONTROLLER CABINETS, AND ELECTRONICS TO BE REMOVED SHALL BE DELIVERED TO BUILDING 5 LOCATED AT 935 EAST CONFEDERATE AVENUE, ATLANTA GEORGIA, 30316. THE CONTRACTOR SHALL CONTACT THE STATE SIGNAL ENGINEER AT (404) 624 -7124 ONE-WEEK PRIOR TO DELIVERY. THE POLE, ALL VERTICAL AND HORIZONTAL CONDUIT, AND CABLE FROM THE ELECTRICAL POWER SERVICE ASSEMBLY POINT SHALL REMAIN IN PLACE. THE CONTRACTOR SHALL TURN OFF MAIN SOURCE CIRCUIT BREAKER AND LOCK THE BREAKER CABINET WITH A PADLOCK. THE CONTRACTOR SHALL SUPPLY PADLOCKS AND KEYS. ALL PADLOCKS USED FOR LOCKING CIRCUIT BREAKERS SHALL BE KEYED THE SAME. ALL PAD PADLOCK KEYS SHALL BE GIVEN TO THE ENGINEER. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT. THE CONTRACTOR SHALL NOT DISTURB ANY OTHER EXISTING ATMS DEVICES, EXCEPT WHERE SPECIFIED IN THE PLANS.

- ANY EXISTING LOOP DETECTORS THAT ARE CUT, DAMAGED, OR DESTROYED SHALL NOT BE REPAIRED BY SPLICING THE LOOPS CABLES TOGETHER. ALL LOOP LINES THAT ARE CUT, DAMAGED, OR DESTROYED SHALL BE REPLACED ENTIRELY AT NO SEPARATE EXPENSE TO THE DEPARTMENT WITHIN TWO WEEKS. THE EXISTING LOOP DETECTORS ARE SHOWN ON THE PLANS FOR INFORMATION ONLY. THE CONTRACTOR SHALL CONTACT THE OFFICE OF INFORMATION SERVICES AT (770) 986-1356 ONE WEEK PRIOR TO DOING ANY WORK AT THESE LOCATIONS.
- NO NOTICE OF INTENT IS REQUIRED FOR THIS PROJECT.
- UNLESS SHOWN OTHERWISE ON THE PLANS, THE CONTRACTOR SHALL INSTALL DUCT BANK UNDER SHOULDER LANE.
- MINOR TREE TRIMMING AND REMOVAL MAY BE REQUIRED AS DIRECTED BY THE ENGINEER. PAYMENT FOR THIS SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.
- BEFORE WORKING AROUND EXISTING HUB BUILDINGS, THE CONTRACTOR SHALL CONTACT THE ITS MANAGER AT (404) 624-7811 72 HOURS IN ADVANCE OF ANY EXCAVATION IN THE AREA TO ALLOW GDOT STAFF TO LOCATE GDOT ITS INFRASTRUCTURE.

UTILITIES CONTACT INFORMATION

ATLANTA GAS LIGHT COMPANY MR. BRIAN LEAVELL PHONE: 404-584-4702	GEORGIA POWER COMPANY MR. TOM JACKSON PHONE: (404) 506-2428 & (404) 506-3280
DEKALB COUNTY PUBLIC WORKS DEPARTMENT, MR. RICK DANIELS PHONE: 770-621-7231	SOUTHERN NATURAL GAS COMPANY MR. ROBERT STARKS PHONE: (205)326-2063
UNITED WATER SERVICES MR. PETER TINUBU PHONE: 404-235-2029	AT&T BROADBRAND MRS. CATHY CAMPBELL PHONE: (770)559-2166
FULTON COUNTY PUBLIC WORKS MR. RAY WOOTEN, JR. PHONE: 404-730-7400	ADELPHIA BUSINESS SOLUTIONS MR. WESLEY PARSONS PHONE: (770)395-3684
CLAYTON COUNTY WATER AUTHORITY MR. GARY HOWE PHONE: 770-961-2130	AT&T CORPORATION MRS. PEGGY J. WOMACK PHONE: (404)810-3189
AT&T BROADBAND MRS. CATHY CAMPBELL PHONE: 770-559-242	GREYSTONE POWER CORPORATION MR. SANDY BEASLEY PHONE: (770)949-7880 & (770)370-2032
COLONIAL PIPELINE MR. MICKEY ELLIOT PHONE: 770-819-3557	CITY OF EAST POINT MR. BRUCE DEBOLT PHONE: (404)765-1039
BELLSOUTH TELECOMMUNICATIONS MR. SEV BURKHALTER PHONE: 770-493-2006	NORTHSTAR COMMUNICATION GROUP C/O LEVEL 3 COMMUNICATIONS MRS. JACKIE TEMPLES PHONE: (770)427-6786
GEORGIA POWER TRANSMISSION MR. BILL MADDOX PHONE: 404-817-3053	QWEST COMMUNICATIONS MR. GEORGE MCELVAIN PHONE: (770)427-6786
CLAYTON COUNTY DOT MR. LENARD SCROGGINS PHONE: 770-477-3674	PLANTATION PIPE LINE COMPANY MR. BLAIR H. NORTHEN, JR., P.E. PHONE (770)751-4109
GDOT COMMUNICATIONS CABLE BUILDING 5 PHONE: 404-624-7811	

DESIGNED BY	NAME	DATE	FIRST DRAWN	NAME	DATE	GEORGIA DEPARTMENT OF TRANSPORTATION	ATMS DESIGN I-285 FROM I-75 SOUTH INTERCHANGE EAST TO I-20 GENERAL NOTES SHEET	ACCOUNT NO.
	CHECKED BY			FIRST DRAWN				DRAWING NO.
	SUPERVISED BY							
	SUBMITTED BY			DATE				