STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	NHS-0002-00(754)	6	146

SUMMARY OF QUANTITIES-CHANGEABLE MESSAGE SIGNS & TEST SITE STRUCTURE

REVISED AND REDRAWN: 1-07-05

STATION	INSTAL NO	GUARD RAIL GA. STDS. 4010 & 4011	GUARD RAIL ANCHORAGES GA. STDS. 4012C & 4040				STRUCTURAL SUPPORT (LUMP)			CHANGEABLE MESSAGE SIGNS (EACH)									
											LED PIXEL CMS. WALK-IN								
											3 x 15			3 x 18			3 x 21		
		LINEAR FEET	TYPE (EACH)				SUPPORT NO.	TYPE	LENGTH	SIGN NO.	12"	15"	18"	12"	15"	18"	12"	15"	18"
			1	12															
290+00 SB	1						NAV G53-99	I	77'- 0"	206									1
521+00 SB	2						NAV G49-63	I	77'- 0"	205									1
300+50 NB	3	125	1	1			NAV H53-79	I	77'- 0"	246									1
553+30 NB	4	125	1	1			NAV H49-03	I	77'- 0"	247									1
376+70 NB	5	75		1			NAV H52-35	I	87'- 6"	TEST SITE STRUCTURE									
TOTALS		325	2	3															4

CONCRETE MEDIAN BARRIER

LIN FT

STATION		QUANTITY	
BEGIN	END	REMOVE	REQ'D TP 26
289+70	290+30	60	60
520+70	521+30	60	60
300+20	300+80	60	60
553+00	553+60	60	60
376+40	377+00	60	60
TOTALS		300	300

NOTES:

NEW BARRIER SHALL MATCH EXISTING BARRIER IN MAXIMUM WIDTH AT THE TOP AND TAPER RATE.

ANY GLARE SCREEN REMOVED SHALL BE REPLACED. COST SHALL BE INCLUDED IN PRICE BID FOR TP 26 BARRIER.

GENERAL NOTES:

1. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO AVOID ANY INTERFERENCE WITH UNDERGROUND UTILITIES. ANY DAMAGE TO UTILITIES CAUSED BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. CONTRACTOR SHALL CALL (800) 282-7411 PRIOR TO ANY DIGGING.
2. THE CONTRACTOR SHALL PROVIDE MAINTENANCE WALKWAYS ON STRUCTURAL SUPPORT TYPES I, II, III, IV AND VII. MAINTENANCE WALKWAYS ARE NOT REQUIRED ON STRUCTURAL SUPPORT TYPES V AND VI. MAINTENANCE WALKWAYS ON EXISTING STRUCTURES SHALL BE MODIFIED (IF NECESSARY) TO MEET THE REQUIREMENTS OF GDOT SPECIFICATION 638. COST FOR THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR NEW SIGN MATERIAL.
3. FOR LOCATION OF GUARDRAIL, SEE GEORGIA STANDARDS 4022A AND 4051 AND/OR CONSTRUCTION DETAILS.
4. COST FOR ANY REQUIRED TEMPORARY EROSION CONTROL SHALL BE INCLUDED IN PRICE BID FOR SIGN STRUCTURES.
5. ANY TREES, SHRUBS, OR FLOWERS THAT ARE DAMAGED DURING INSTALLATION OF NEW SIGN STRUCTURES SHALL BE REPLACED IN KIND AT NO ADDITIONAL COST TO THE DEPARTMENT IN ACCORDANCE WITH SECTION 702 OF THE GEORGIA SPECIFICATIONS, EXCEPT THAT SECTION 702.3.07 SHALL NOT APPLY TO THIS PROJECT.

	NAME	DATE		NAME	DATE
DESIGNED BY			FIRST DRAWN		
CHECKED BY			LAST DRAWN		
SUPERVISED BY					

GEORGIA DEPARTMENT OF TRANSPORTATION

SUBMITTED BY | DATE

ATMS DESIGN
I-285 FROM I-75 SOUTH INTERCHANGE EAST TO I-20
CMS SUMMARY SHEET

ACCOUNT NO.

DRAWING NO.

..\cad files\cmssum.dgn