

EXHIBIT "A"


PLANT SCHEDULE						
ITEM	SCIENTIFIC NAME	COMMON NAME	QTY	SIZE	SPACING	NOTES
T-1	CERCIS CANADENSIS	RED BUD	17	1" CAL., 7' - 8' HGT.	20' O.C.	SINGLE-TRUNK, PINK
T-2	QUERCUS VIRGINIANA	LIVE OAK	8	3" CAL., 10' - 12' HGT.	50' O.C.	FULL SPECIMENS
T-3	MAGNOLIA VIRGINIANA	SWEET BAY MAGNOLIA	28	1" CAL., 7' - 8' HGT.	20' O.C.	SINGLE-TRUNK, WHITE
T-4	ILEX VOMITORIA	YAUPON HOLLY	25	1" CAL., 7' - 8' HGT.	15' O.C.	FULL TO GROUND
T-5	ILEX ATTENUATA 'SAVANNAH'	SAVANNAH HOLLY	20	1" CAL., 7' - 8' HGT.	15' O.C.	FULL TO GROUND

LANDSCAPE GENERAL NOTES:

- ENGINEER TO APPROVE ALL REVISIONS TO PLANT LOCATIONS.
- LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIR OF ANY UTILITY LINES DAMAGED DURING PLANTING.
- ALL DISTURBED AREAS NOT COVERED BY STRUCTURES, PAVING OR LANDSCAPING INCLUDING MEDIANS SHALL BE GRASSED.
- CITY OF SAVANNAH TO INSTALL ANY REQUIRED IRRIGATION COMPONENTS SUCH AS TEEGATOR BAGS AFTER PROJECT IS COMPLETE AT NO ADDITIONAL COST TO GADOT. CITY OF SAVANNAH WILL COORDINATE WITH GADOT PRIOR TO IRRIGATION INSTALLATION TO INSURE COMPLIANCE WITH GADOT POLICIES.
- LANDSCAPE CONTRACTOR SHALL GUARANTEE AND MAINTAIN PROPOSED LANDSCAPING PER SPECIAL PROVISION 702.
- ALL SIZES SPECIFIED ARE THE MINIMUM SIZE REQUIRED AT TIME OF PLANTING.

CITY OF SAVANNAH PARK & TREE DEPARTMENT
 TREE PROTECTION NOTES:


- TREE PROTECTION SHALL ADHERE TO THE FOLLOWING STANDARDS SPECIFIED IN:
 A. THE LANDSCAPE & TREE ORDINANCE OF THE CITY OF SAVANNAH
 B. THE LANDSCAPE & TREE ORDINANCE COMPLIANCE MANUAL OF THE CITY OF SAVANNAH
- THE TREE PROTECTION DEVICE (UNLESS NOTED OTHERWISE IN THE PLANS OR DIRECTED BY THE ENGINEER) SHALL BE A 4' TEMPORARY CHAIN LINK FENCE CONSTRUCTED AT AND AROUND THE PERIMETER OF THE TREE PROTECTION ZONE. THE FENCE SHALL BE ATTACHED TO GALVANIZED METAL POSTS, SPACED NO FURTHER THAN 8' APART.
- TREE PROTECTION DEVICES SHALL BE ERECTED PRIOR TO THE START OF CONSTRUCTION AND SHALL REMAIN IN PLACE UNTIL ALL ROADWAY WORK IS COMPLETED AND LANDSCAPE INSTALLATION HAS BEGUN. BROKEN OR DISLODGED TREE PROTECTION DEVICES SHALL BE IMMEDIATELY REPAIRED.
- ALL DESIGNATED TREE PROTECTION ZONES MUST BE PROTECTED FROM SEDIMENTATION BY USE OF EROSION CONTROL DEVICES.
- NO VEHICLES SHALL BE PARKED; NO CONSTRUCTION MATERIALS STORED; OR ANY SUBSTANCES POURED OUT, DISPOSED OF OR PLACED WITHIN ANY TREE PROTECTION ZONE AT ANY TIME DURING CLEARING AND CONSTRUCTION OF THIS PROJECT.
- NO CHANGE OF GRADE WITHIN THE TREE PROTECTION ZONE SHALL BE ALLOWED AROUND EXISTING TREES EXCEPT FOR THE ADDITION OF MULCH UNLESS NOTED OTHERWISE IN THE PLANS.
- TREES WITHIN A TREE PROTECTION ZONE SHALL NOT BE PRUNED OR REMOVED WITHOUT PRIOR KNOWLEDGE AND CONSENT BY THE ENGINEER AND IN COORDINATION WITH THE CITY OF SAVANNAH LANDSCAPE ARCHITECT OR DESIGNER.
- ALL RETAINED OR PLANTED TREES SHALL BE PROTECTED OR SITUATED SO AS TO PREVENT DAMAGE FROM ENVIRONMENTAL CHANGES OR LAND DISTURBANCE RESULTING FROM ANY BUILDING OR FACILITY CONSTRUCTION WITHIN OR IMMEDIATELY ADJACENT TO THE CRITICAL ROOT ZONE OF THE TREE(S).
- ANY DAMAGE OR INJURY TO TREES SHALL BE REPORTED IMMEDIATELY TO THE ENGINEER AND THE CITY OF SAVANNAH PARK AND TREE DEPARTMENT SITE INSPECTOR AT (912) 651-6610.



CITY OF SAVANNAH PARK & TREE DEPARTMENT
 PLANTING NOTES:


- ALL PLANTING SHALL ADHERE TO THE FOLLOWING STANDARDS AS SPECIFIED IN:
 A. THE CITY OF SAVANNAH LANDSCAPE AND TREE ORDINANCE.
 B. THE CITY OF SAVANNAH LANDSCAPE AND TREE ORDINANCE COMPLIANCE MANUAL.
- ANY DEVIATION FROM THESE PLANS IN EITHER SPECIES OR LAYOUT MUST BE SPECIFICALLY APPROVED BY THE ENGINEER IN COORDINATION WITH THE LANDSCAPE ARCHITECT FOR THE CITY OF SAVANNAH OR DESIGNER.
- CONTRACTORS ARE RESPONSIBLE FOR INSPECTION OF EXISTING CONDITIONS AND MUST REPORT ANY DISCREPANCIES.
- NO LARGE OR MEDIUM TREE SPECIES SHALL BE PLANTED WITHIN 10 FEET OF ANY UNDERGROUND UTILITY LINE OR UNDERNEATH ANY OVERHEAD POWER LINES, AND SMALL TREE SPECIES MUST MAINTAIN A MINIMUM 5 FEET SEPARATION FROM UNDERGROUND UTILITY LINES.
- ALL TREES SHALL BE HEALTHY, VIGOROUS, WITH A NORMAL HABIT OF GROWTH EVEN DISTRIBUTION OF BRANCHES, A STRAIGHT TRUNK WHICH EXHIBITS GOOD TRUNK TAPER, WITH LIMBS NOT LOWER THAN FOUR FEET ABOVE THE GROUND DEPENDENT UPON THE SPECIES. TREES SHALL BE FREE FROM DISEASE, INSECT INFESTATION, MECHANICAL INJURY, GIRDLING ROOTS, OR OTHER OBJECTIONABLE FEATURES THAT WOULD CAUSE THE TREE TO DECLINE OR BECOME STRUCTURALLY UNSOUND. TREES SHALL BE WELL-BRANCHED AND DENSELY FOLIATED WHEN IN LEAF.
- PLANTS SHALL BE SUBJECT TO INSPECTION FOR CONFORMITY TO SPECIFICATION REQUIREMENTS AND APPROVAL BY THE ENGINEER IN COORDINATION WITH THE CITY OF SAVANNAH PARK AND TREE DEPARTMENT. SUCH APPROVAL SHALL NOT IMPAIR THE RIGHT OF INSPECTION AND REJECTION DURING THE PROGRESS OF THE WORK. ACCEPTANCE AT THE NURSERY WHERE THE PLANT IS GROWING PRIOR TO TRANSPLANTING DOES NOT PRECLUDE REJECTION AT THE SITE FOR JUST CAUSE.
- TREES SHALL BE PLANTED AT PROPER DEPTH OR SHALL BE REJECTED AT TIME OF INSPECTION.
- STAKE TREES ONLY WHEN NECESSARY. IF USED, STAKING AND GUYING SHALL FOLLOW THE CITY OF SAVANNAH PARK AND TREE DEPARTMENT SPECIFICATIONS.
- LANDSCAPE CONTRACTORS ARE REQUIRED TO ATTEND A PRE-PLANTING MEETING WITH THE CITY OF SAVANNAH PARK AND TREE DEPARTMENT PRIOR TO START OF PROJECT. PLEASE CONTACT THE PARK AND TREE DEPARTMENT SITE INSPECTOR AT (912)651-6610 TO SET UP MEETING.

HINESLEY AND ASSOCIATES
 Landscape Architecture and Planning
 1 SORRELWOOD CROSS
 SAVANNAH, GEORGIA 31411
 (912) 224-3091 PHONE/ vhinesley@bellsouth.net




- NOTES:
 1. STAKE TREES ONLY WHEN NECESSARY. STAKES SHALL BE REMOVED 6 MONTHS AFTER PLANTING.
 2. OTHER ALTERNATE STAKING METHODS MAY BE USED UPON APPROVAL BY PARK AND TREE.

CITY OF SAVANNAH
 STANDARD CONSTRUCTION DETAILS
 ALTERNATIVE TREE STAKING
 APPROVED: [Signature] N.T.S. DATED: JULY 2007
 CITY ENGINEER T4




- NOTES:
 1. STAKE TREES ONLY WHEN NECESSARY. STAKES SHALL BE REMOVED 6 MONTHS AFTER PLANTING.
 2. TREES LARGER THAN 2" CAL/PER SHOULD BE STAKED BY THREE GUY STRAPS WHEN NECESSARY.

CITY OF SAVANNAH
 STANDARD CONSTRUCTION DETAILS
 TREE STAKING
 APPROVED: [Signature] N.T.S. DATED: JULY 2007
 CITY ENGINEER T3



- NOTES:
 1. PRUNE ONLY CROSSOVER LIMBS, CO-DOMINANT LEADERS, AND BROKEN OR DEAD BRANCHES. SOME INTERIOR TWIGS AND LATERAL BRANCHES MAY BE PRUNED; HOWEVER, DO NOT REMOVE THE TERMINAL BUDDS OF BRANCHES THAT EXTEND TO THE EDGE OF THE CROWN. ALL PRUNING SHALL CONFORM TO ANSI A300 STANDARDS. IMPROPERLY PRUNED TREES MAY BE REJECTED BY THE CITY.
 2. STAKE TREES ONLY WHEN NECESSARY. SEE CITY TREE STAKING DETAILS.

CITY OF SAVANNAH
 STANDARD CONSTRUCTION DETAILS
 TREE PLANTING
 APPROVED: [Signature] N.T.S. DATED: JULY 2007
 CITY ENGINEER T1



- FOR ADDED PROTECTION:
 - PROVIDE 4" DEEP WOOD CHIP MULCH OVER ANY UNPROTECTED ROOT ZONE.
 - MAKE CLEAN CUTS ON ROOTS EXPOSED BY GRADING AND BACKFILL IMMEDIATELY.
 - PROVIDE TEMPORARY IRRIGATION WHERE PRACTICAL AND FEASIBLE.

CITY OF SAVANNAH
 STANDARD CONSTRUCTION DETAILS
 TREE PROTECTION
 APPROVED: [Signature] N.T.S. DATED: JULY 2007
 CITY ENGINEER T2

*ADJACENT TO ROADWAY TRAFFIC, 4' ORANGE BARRIER FENCE SHALL BE SUBSTITUTED FOR CHAIN LINK FENCE.

REVISION DATES

STATE OF GEORGIA
 DEPARTMENT OF TRANSPORTATION
 OFFICE: URBAN DESIGN
 LANDSCAPING PLANS

SR 25 CO / WEST BAY STREET
 IMPROVEMENTS

DRAWING No.
 29-001

McGee Partners, Inc.

