2/25/2008 8:03:37 AM \\GDOT-DSN\GOPLOT\OCF\gg.kip8000-paper_36x24-scale_to_fit.pct tannon M:\0003790 - 15th St @ Central in Augusta\PRF&\0003790revsumgenno tes.prf GO-UDI

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-0003-00(790)	3	70

REVISION DATES				
8/13/07	2/12/08			
9/7/07				
1/28/08				
1/29/08				

REVISION SUMMARY

REVISION DATE	SHEET NO.	DESCRIPTION
8/13/07	3	ADDED DATE TO REVISION SUMMARY
8/13/07	5	ADDED QUANTITIES REQ'D BY AMENDMENT FOR MULCH, LIME, AND FERTILIZER
9/7/07	1	ADDED ESA-HAZARDOUS MATERIAL BOUNDARY; ENLARGED ESA-HISTORIC BOUNDARIES
9/7/07	2	ADDED DESC. OF EROSION CONTROL (EC) DEATILS; REV. EC DRAWING NUMBERS
9/7/07	3	ADDED DESC. OF REVISIONS TO REVISION SUMMARY
9/7/07	5	ADDED REVISIONS TO QUANTITIES BY AMENDMENT DATED 9/7/07
9/7/07	14-16	ADDED ESA-HAZARDOUS MATERIAL BOUNDARY; ADD. ESA TO HISTORIC BOUNDARIES;
		ADDED ORANGE BARRIER FENCE AROUND TREE
9/7/07	21-23	ADDED ESA-HAZARDOUS MATERIAL BOUNDARY; ADD. ESA TO HISTORIC BOUNDARIES;
		ADDED ORANGE BARRIER FENCE AROUND TREE
9/7/07	63	REV. TYPE B TO HAY BALES(Hb); MOVED Hb FROM C/F; REM. SHEET REF.;
		REV. TITLE BLOCK AND DRAWING NO.
1/28/08	3	ADDED DATE TO REVISION SUMMARY
1/28/08	4	ADDED QUANTITIES REQ'D ON CONSTRUCTION
1/28/08	30-31	REV. STRAIN POLES TO MAST ARMS TO ELIMINATE STR ON PARCEL 1;
		ADDED DIR. BORE & CONDUIT & ADD'L INFORMATION FOR PED POLES
1/29/08	3	ADDED DATE TO REVISION SUMMARY
1/29/08	14	REVISED STRAIN POLE LOCATIONS DUE TO SIGNAL REVISIONS
2/12/08	1	ADDED REVISION DATE TO COVER
2/12/08	3	ADDED DATE TO REVISION SUMMARY
2/12/08	14	REVISED PARCEL 1 ESMT TO TEMPORARY ESMT
2/12/08	21	REVISED PARCEL 1 ESMT TO TEMPORARY ESMT
2/12/08	63	REVISED PARCEL 1 ESMT TO TEMPORARY ESMT
2/12/08	66	ADDED REVISION DATE TO COVER
2/12/08	67	REVISED PARCEL 1 ESMT TO TEMPORARY ESMT

GENERAL NOTES

1. THE TOTAL ACRES SHOWN ON THE PLANS FOR CLEARING AND GRUBBING ARE FOR INFORMATION ONLY. THE DEPARTMENT OF TRANSPORTATION ASSUMES NO RESPONSIBILITY FOR ITS' ACCURACY. THE CONTRACTOR SHALL BID ON CLEAR & GRUB - LUMP SUM AND IT SHALL BE HIS RESPONSIBILITY TO DETERMINE THE ACTUAL ACRES TO BE CLEARED AND GRUBBED. NO CLAIMS WILL BE CONSIDERED FOR EXTRA COMPENSATION IF THE CONTRACTOR RELIES ON THE ACRES SHOWN ON THE PLANS.

2. THE AREA SHOWN ON THE PLANS FOR PERMANENT GRASSING IS FOR INFORMATION ONLY. THE DEPARTMENT OF TRANSPORTATION ASSUMES NO RESPONSIBILITY FOR ITS' ACCURACY, THE CONTRACTOR SHALL BID ON THE PERMANENT GRASSING, AND IT SHALL BE HIS RESPONSIBILITY TO DETERMINE THE ACTUAL AREA TO BE GRASSED, NO CLAIMS SHALL BE CONSIDERED FOR EXTRA COMPENSATION IF THE CONTRACTOR RELIES ON THE AREA SHOWN ON THE PLANS.

3. ALL DRIVES THAT ARE TO BE RECONSTRUCTED SHALL BE REPLACED IN KIND UNLESS NOTED OTHERWISE ON THE PLANS, I.E., ASPHALT FOR ASPHALT, CONCRETE FOR CONCRETE. WHERE REQUIRED, DRIVES SHALL BE PAVED AS FOLLOWS:

ASPHALT DRIVES	RESIDENTIAL:	RECYCLED ASPHALT CONCRETE 12.5MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME (165 LBS/S.Y.) 6" GRADED AGGREGATE BASE
	COMMERCIAL:	RECYCLED ASPHALT CONCRETE 12.5MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME (165 LBS/S.Y.) RECYCLED ASPHALT CONCRETE 19MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME (220 LBS/S.Y.) 6" GRADED AGGREGATE BASE
CONCRETE DRIVES	RESIDENTIAL:	8" VALLEY GUTTER 8" CONCRETE DRIVEWAY
	COMMERCIAL:	8" VALLEY GUTTER 8" CONCRETE DRIVEWAY

DRIVEWAYS WILL BE PAVED BACK TO THE TIE-IN POINT OR REQUIRED RIGHT OF WAY.

4. RIGHT-OF-WAY MARKERS IN RESIDENTIAL LAWNS AND DEVELOPED COMMERCIAL AREAS SHALL BE PLACED FLUSH WITH THE FINISHED SURFACE.

5. ANY MILE POST MARKER THAT MAY BE DISTURBED OR REMOVED DURING CONSTRUCTION OR THAT BECOMES TOO CLOSE TO THE NEW EDGE OF PAVEMENT SHALL BE RESET OR REPLACED AS PER GEORGIA STANDARD NO. 9033 (MILEPOST).

6. REMOVE ONLY THOSE TREES NECESSARY FOR CONSTRUCTION AND SAFETY PURPOSES EXCEPT AS NOTED ON PLANS. ALL OTHERS SHALL REMAIN.

7. WHEN PARTIAL PAVEMENT REMOVAL IS REQUIRED THE PAVEMENT SHALL BE SAWED TO A NEAT LINE.

8. THE CONTRACTOR SHALL ADHERE TO THE CALL BEFORE YOU DIG LAW BY CALLING THE UNDERGROUND PROTECTION CENTER AT 1-800-282-7411 BEFORE BEGINNING CONSTRUCTION.

9. A NOTICE OF INTENT (NOI) FOR STORMWATER DISCHARGE IS NOT REQUIRED FOR THIS PROJECT.

10. NO WORK INCLUDING THE PARKING AND STORAGE OF VEHICLES SHOULD OCCUR WITHIN THE ELIGIBLE NATIONAL REGISTER BOUNDARIES OF THE RESOURCES DESIGNATED AS HISTORIC BOUNDARIES.

11. MATCH EXISTING DRIVEWAY WIDTHS AND RADII AND TIE IN DRIVEWAY OVERLAY BEFORE THE SIDEWALK TO AVIOD THE ELIGIBLE NATIONAL REGISTER BOUNDARIES OF THE RESOURCES DESIGNATED AS HISTORIC BOUNDARIES.

12. SOIL CONTAMINATION FROM UST'S EXCEEDING EPD REGULATORY LIMITS WAS ENCOUNTERED WITHIN THE REQUIRED RIGHT OF WAY AT SITE NOS. 2 & 4 AT A DEPTH OF 10 FEET. AT SITE NO. 4, GROUNDWATER CONTAMINATION LEVELS EXCEEDED EPD REGULATORY LIMITS. ANY EXCAVATION AT SITE NO. 4 POSES A POTENTIAL CONSTRUCTION HAZARD.

13. THE UST'S AT SITE NO. 2 WILL NOT BE IMPACTED BY ADDITIONAL RIGHT OF WAY REQUIREMENTS.

14. THE LOCATION OF THE UST'S COULD NOT BE DETERMINED FOR THE SITE NO. 4. ANY UST'S ENCOUNTERED ON THIS SITE SHALL BE HANDLED IN ACCORDANCE WITH GDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION, SECTION 217 - REMOVAL OF UNDERGROUND STORAGE TANKS.

15. THE CONTRACTOR SHALL IMPLEMENT THE BEST POSSIBLE ENGINEERING AND MANAGEMENT CONTROLS TO ENSURE ADEQUATE PROTECTION OF EMPLOYEE SAFETY IN ACCORDANCE WITH GEORGIA'S RULES FOR HAZARDOUS WASTE MANAGEMENT.

16. ANY CONTAMINATED SOIL EXCAVATED DURING CONSTRUCTION ACTIVITIES AT SITE NOS. 2 & 4 MUST BE DISPOSED OF AT A PERMITTED LINED MUNICIPAL SOLID WASTE LANDFILL. COST TO BE INCLUDED IN OVERALL BID PRICE FOR GRADING COMPLETE.

17. THE GA. POWER POLE LOCATED IN THE SOUTHWEST QUADRANT OF THE INTERSECTION WILL REMAIN IN PLACE. THE SIDEWALK WILL BE PLACED TO THE REQ'D R/W LINE HEADER CURB.

UTILITY OWNERS

ELEC	AL DANNER GEORGIA POWER COMPANY P.O.BOX 188 290 NORTH PEACHTREE ST LINCOLNTON, GA 30817 (706) 836-0130	SEWER	RUSSELL THIES AUGUSTA UTILITIES DEPT. 360 BAY STREET, SUITE 180 AUGUSTA, GA 30901 (706) 312-4139	TELEPHONE	AUSTIN SAPP BELLSOUTH TELECOMMUNICATIONS INC. 3841 WRIGHTSBORO ROAD AUGUSTA, GA 30909 (706) 228-5203	CABLE TV	GENE HOLCOMB KCM TELECOM 1755 NORTH BROWN ROAD LAWRENCEVILLE, GA 30043 (678) 985-6138
GAS	CHRIS TWEEDLE ATLANTA GAS LIGHT CO. 10 PEACHTREE PLACE, 11TH FL ATLANTA, GA 30309 (404) 584-3111	WATER	RUSSELL THIES AUGUSTA UTILITIES DEPT. 360 BAY STREET, SUITE 180 AUGUSTA, GA 30901 (706) 312-4139	CABLE TV	RICHARD STRENGTH KNOLOGY OF AUGUSTA 3714 WHEELER ROAD AUGUSTA, GA 30909 (706) 533-2066	CABLE TV	KEVIN O'MEARA COMCAST 105 RIVER SHOALS PARKWAY AUGUSTA, GA 30909 (706) 739-1865

GDOT Georgia Department of Transportation

Dig Safely.

1-800-282-7411

770-623-4344

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF URBAN DESIGN

REVISION SUMMARY & GENERAL NOTES

DRAWING No. 1-03