## SUMMARY OF QUANTITIES

STATE	PROJECT N	UMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-0003-	00(790)	9	70
	REVISI	ON DATE	S	

	ROAD	NAY IT	EMS						·		
	RECYCLED ASPH. CONC. 12.5MM SUPERPAVE, GP 2 ONLY INCL BITUM MATL & H LIME	RECYCLED ASPH. CONC. 19MM SUPERPAVE, GP 1 OR 2 INCL BITUM MATL & H LIME	ASPH. CONC.  C CP 1 OR 2  M MATL & H	GR AGGR BASE CRS, INCL MATL	CONCRETE HEADER CURB 6 IN, TYPE 2	MILL ASPH CONC PVMT VARIABLE DEPTH	BITUM TACK COAT	CONCRETE VALLEY GUTTER, 8 IN	CLASS B CONC, BASE OR PVMT' WIDENING	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH
15TH STREET	TON	TON	TON	TON	LF	SY	GAL.	SY	CY	TN	LF
$STA \ 3+42 \ to \ STA \ 4+92$	313					3790	189			76	46
CENTRAL AVENUE	·										
STA 10+50 to STA 13+72	113	4	5	19	115	1337	70		2		46
UNDER CURB & GUTTER				28							
DRIVEWAYS								34			
AS DIRECTED BY ENGINEER										2	
TOTAL	426	4	5	47	115	5127	259	34	2	78	92

CONC SIDEWALK, 4 LOCATION INCL RAMPS	IN
LOCATION INCL RAMPS	SQ.YD.
CENTRAL AVENUE LT	151
CENTRAL AVENUE RT	72
15TH STREET RT	26
15TH STREET LT	94
AS DIRECTED	30
TOTAL	373

1/6/2007 9:31;39 AM //CD01-DSNI/C0PL07/QCF/go\_Kip8000\_paper\_36x24,qcf tlannon M:/0003790 - 15th St @ Centralin Augusta/PRFs/0003790sumofquant,prf CO-UDI

CONC CURB & GUTTER 8 IN x 30 IN. TP.2					
STATION TO STATION	SIDE	LIN.FT.			
CENTRAL 13 + 07.67 - 15TH 4+85.81	LT	98			
CENTRAL 13 + 36.84 - 15TH 3 + 60.15	RT	52			
15TH ST. 3 + 58.65 TO 3 + 85.42	RT	27			
AS DIRECTED		50			
TOTAL		227			

EROSION C	ONTROL	
PERMANENT GRASSING	1	ACRE

TEMPORARY SILT FENCE, TP B

AS DIRECTED BY ENGINEER 250 LF

MAINTENANCE OF TEMPORARY SILT FENCE, TP B

AS DIRECTED BY ENGINEER 125 LF

GRADING	COMPLETE
STP-0003-00(790)	LUMP SUM

	RIGHT	OF	WAY	MARKERS	
TOTAL	,			3	

TRAFFIC CONTROL

STP-0003-00(790) LUMP SUM

TRAFFIC SIGNAL INSTALLATION NO-1
TOTAL
LUMP SUM

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF URBAN DESIGN