SUMMARY OF QUANTITIES

STATION	INSTL NO	SIGN CODE	HIGHWAY SIGNS: TP 1 MATL, REFL SHEETING, TP 3			TP 2 MATL, REFL SHEETING, TP 3			TP 1 MATL, REFL SHEETING, TP 9			TP 2 MATL, REFL SHEETING, TP 9			SQUARE TUBE POST: TYPE 7			TYPE 8			TYPE 9			BREAKAWAY SIGN SUPPORT (EACH)
			SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	SIGN SIZE	QUAN	AREA (SQ. FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	LENGTH (FT.)	QUAN	TOTAL (FT.)	
COLLINS HILL ROAD SURVEY (CONT'D.)																								
63+57	33	R5-1(30)							30" x 30"	1	6.25				13	1	13							
63+58	34	R3-17	30" x 24"	1	5.00										13	1	13							
		R3-17b	30" x 12"	1	2.50																			
65+57	35	R5-1a(36)							36" x 24"	1	6.00				12	1	12							
66+00	36	M2-1	21" x 15"	1	2.19										14	1	14							
		M1-5(30)(316)	30" x 24"	1	5.00																			
67+00	37	W3-3(36)							36" x 36"	1	9.00										15	1	15	
67+24	38	R5-1(30)							30" x 30"	1	6.25				13	1	13							
67+78	39	R6-2R(24)	24" x 30"	1	5.00										13	1	13							
68+10	40	D1-2(48)	48" x 24"	1	8.00										12	1	12							
69+00	41	R2-1(24)(40)	24" x 30"	1	5.00										13	1	13							
69+40	42	M4-5(24)	24" x 12"	1	2.00													17	2	34				2
		M3-4(24)	24" x 12"	1	2.00																			
		M3-2(24)	24" x 12"	1	2.00																			
		M1-5(30)(316)	30" x 24"	2	10.00																			
		M6-1L	21" x 15"	1	2.19																			
		M6-3	21" x 15"	1	2.19																			
69+41	43	R5-1a(36)							36" x 24"	1	6.00				12	1	12							
70+00	44	R3-17	30" x 24"	1	5.00										12	1	12							
70+85	45	R4-4a	36" x 24"	1	6.00										12	1	12							
70+86	46	R5-1(30)							30" x 30"	1	6.25				13	1	13							
71+00	47	W4-2R(36)							36" x 36"	1	9.00										15	1	15	
72+07	48	R5-1(30)							30" x 30"	1	6.25				13	1	13							
72+12	49	R3-17	30" x 24"	1	5.00										12	1	12							
72+46	50	R560-5	18" x 24"	1	3.00										12	1	12							
73+00	51	M3-2(24)	24" x 12"	1	2.00																15	1	15	
		M1-5(30)(316)	30" x 24"	1	5.00																			
		M5-1L	21" x 15"	1	2.19																			
74+07	52	R5-1a(36)							36" x 24"	1	6.00				12	1	12							
74+30	53	W8-13(30)							30" x 30"	1	6.25				14	1	14							
75+00	54	M4-5(24)	24" x 12"	1	2.00																16	1	16	
		M3-4(24)	24" x 12"	1	2.00																			
		M1-5(30)(316)	30" x 24"	1	5.00																			
		M6-1R	21" x 15"	1	2.19																			
75+77	55	R4-4	36" x 30"	1	7.50										13	1	13							
76+25	56	W9-2L(36)							36" x 36"	1	9.00										15	1	15	
77+65	57	M3-2(24)	24" x 12"	1	2.00																15	1	15	
		M1-5(30)(316)	30" x 24"	1	5.00																			
		M6-1L	21" x 15"	1	2.19																			
SUB-TOTAL #2					109.13						76.25						228			34			91	2

PBS&J

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY OF QUANTITIES

STANDARD HIGHWAY SIGNS
SR 316

DRAWING No. 6-20