TABLE SR 20/BUFORD DR - from Reynolds Rd to Hurricane Shoals Rd - DEVICE SPLICING DETAILS

SPLICE CLOSURE LOCATION		DEVICE ID									
RING	DEVICE STATION SPLICE LOCATION	CCTV	TRAFFIC SIGNAL	TRUNK CABLE 1 FIBER #	TRUNK CABLE 2 FIBER #	DROP FIBER #	FUNCTION	DROP TO DEVICE	DESTINATION OR FDC PORT	COMMENTS OR CHANNEL	FIELD SWITCH GBIC PORT
	SR 20/BUFORD DR STA.80+00, 65 LT			GW S020F.01 THRU	GW S012.01 THRU						
1	SR 20/BUFORD DR AT LENDON CONN./ REYNOLDS RD		INSTALLATION NO.5 (GCDOT #700)	GW S020F.03		GW-D700.01	RX1	001	SIGNAL - SR 20/BUFORD DR AT SWANSON DR (GCDOT #370)	Chan 01	LX
				GW S020F.04		GW-D700.02	TX1		SIGNAL - SR 20/BUFORD DR AT SWANSON DR (GCDOT #370)	Chan 01	
				GW S020F.03		GW-D700.03	TX2		INSTALLATION NO.6 (GCDOT #699)	Chan 01	LX
				GW S020F.04		GW-D700.04	RX2		INSTALLATION NO.6 (GCDOT #699)	Chan 01	
1	SR 20/BUFORD DR AT SR 316 WB RAMPS	GW No.036	INSTALLATION NO.6 (GCDOT #699)	GW S020F.03		GW-D699.01	RX1	002	INSTALLATION NO.5 (GCDOT #700)	Chan 01	LX
				GW S020F.04		GW-D699.02	TX1		INSTALLATION NO.5 (GCDOT #700)	Chan 01	
				GW S020F.03		GW-D699.03	TX2		INSTALLATION NO.7 (GCDOT #698)	Chan 01	LX
				GW S020F.04		GW-D699.04	RX2		INSTALLATION NO.7 (GCDOT #698)	Chan 01	
4	SR 20/BUFORD DR STA.87+80, 72 LT			GW S020F.65	GDOTS.R.20-002.01				NAV-258 SR 316 WB FIBER	Chan 04	
				GW S020F.66	GDOTS.R.20-002.02				NAV-258 SR 316 WB FIBER	Chan 04	
				GW S020F.67	GDOTS.R.20-002.03				NAV-258 SR 316 WB FIBER	Chan 04	
				GW S020F.68	GDOTS.R.20-002.04				NAV-258 SR 316 WB FIBER	Chan 04	
4	SR 20/BUFORD DR STA.91+72, 71 LT			GW S020F.61	GDOTS.R.20-001.01				NAV-257 SR 316 EB FIBER	Chan 04	
				GW S020F.62	GDOTS.R.20-001.02				NAV-257 SR 316 EB FIBER	Chan 04	
				GW S020F.63	GDOTS.R.20-001.03				NAV-257 SR 316 EB FIBER	Chan 04	
				GW S020F.64	GDOTS.R.20-001.04				NAV-257 SR 316 EB FIBER	Chan 04	
1	SR 20/BUFORD DR AT SR 316 EB RAMPS		INSTALLATION NO.7 (GCDOT #698)	GW S020E.03		GW-D698.01	RX1	003	INSTALLATION NO.6 (GCDOT #699)	Chan 01	LX
				GW S020E.04		GW-D698.02	TX1		INSTALLATION NO.6 (GCDOT #699)	Chan 01	
				GW S020E.03		GW-D698.03	TX2		INSTALLATION NO.8 (GCDOT #043)	Chan 01	LX
				GW S020E.04		GW-D698.04	RX2		INSTALLATION NO.8 (GCDOT #043)	Chan 01	
1	SR 20/BUFORD DR AT HURRICANE SHOALS RD		INSTALLATION NO.8 (GCDOT #043)	GW S020E.03		GW-D043.01	RX1	004	INSTALLATION NO.7 (GCDOT #698)	Chan 01	LX
				GW S020E.04		GW-D043.02	TX1		INSTALLATION NO.7 (GCDOT #698)	Chan 01	
				GW S020E.03		GW-D043.03	TX2		SIGNAL - SR 20/BUFORD DR AT INDUSTRIAL PARK DR (GCDOT #531)	Chan 01	LX
				GW S020E.04		GW-D043.04	RX2		SIGNAL - SR 20/BUFORD DR AT INDUSTRIAL PARK DR (GCDOT #531)	Chan 01	
	SR 20/BUFORD DR STA.108+55, 55 LT			GW S020E.01 THRU	GW S012.01 THRU						

PBS&J

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

ATMS PLANS
FIBER ALLOCATION DETAILS

SR 316 FROM COLLINS HILL RD TO HI-HOPE RD.

DRAWING No. 28-19