SUMMARY OF QUANTITIES-STANDARD SIGNS

STATION	INSTL. NO.	CODE	SIGNS (TYPE III REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQUARE FEET	TYPE 2 (0.10) SIZE	QTY	SQUARE FEET	SIGNS (TYPE VI REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQUARE FEET	TYPE 2 (0.10) SIZE	QTY	SQUARE FEET	SQUARE TUBE POST TYPE 7 LENGTH (FEET)	QTY	TOTAL LENGTH	TYPE 8 LENGTH (FEET)	QTY	TOTAL LENGTH	TYPE 9 LENGTH (FEET)	QTY	TOTAL LENGTH	BREAKAWAY SIGN SUPPORT EACH
44+00		R2-1(36)				36 x 48	1	12.00							13	2	26							
44+50		R5-1(30)							30 X 30	1	6.25				13	1	13							
45+00		R1-1(36)							36 OCT	1	7.46				13	1	13							
46+18		R1-2(36)							36 TRI	1	3.90													
47+40		R5-1(30)							30 X 30	1	6.25				13	1	13							
49+00		R5-1A(36)													13	1	13							
49+21		D1-1A(48)	48 x 12	1	4.00										14	1	14							
51+00		M3-3(24)	24 x 12	1	2.00				36 x 24	1	6.00				13	1	13				13	1	13	
51+00		M1-4(30)	30 x 24	1	5.00																			
51+00		M1-5(30)	30 x 24	1	5.00																			
53+25		R1-2(36)							36 TRI	1	3.90				13	1	13							
53+56		R5-1(30)							30 X 30	1	6.25				13	1	13							
55+05		R5-1(30)							30 X 30	1	6.25				13	1	13							
56+00		R3-1(30)	30 x 30	1	6.25										13	1	13							
56+68		M3-1(24)	24 x 12	1	2.00																13	1	13	
56+68		M1-4(30)	30 x 24	1	5.00																			
56+68		M1-5(30)	30 x 24	1	5.00																			
58+00		R2-1(36)				36 x 48	1	12.00							13	2	26							
59+50		D2-1(48)	48 x 12	1	4.00										14	1	14							
96+00		D1-2(48)	48 x 12	1	4.00										14	1	14							
96+71		R5-1A(36)							36 x 24	1	6.00				13	1	13							
96+71		R5-1A(36)							36 x 24	1	6.00				13	1	13							
97+00		R3-5	30 x 24	2	20.00																			
97+00		R3-5 (R)	30 x 24	1	10.00																			
97+50		M6-1L	21 x 15	1	2.19										16.25	2	32.5							
97+50		M6-1R	21 x 15	1	2.19																			
97+50		M1-5(30)	30 x 24	2	10.00										13	2	26							
97+50		M1-4(30)	30 x 24	2	10.00																			
97+50		M3-1(24)	24 x 12	1	2.00																			
97+50		M3-3(24)	24 x 12	1	2.00										12	1	12							
98+17		R5-10A(30)	30 x 36	1	7.50										13	1	13							
99+38		R5-1(30)							30 X 30	1	6.25				13	1	13							
99+26		R5-1(30)							30 X 30	1	6.25				13	1	13							
99+48		R6-2(24)	18 x 24	1	3.00										13	1	13							
SUM				23	111.1		2	24		12	70.76					27	359.5					2	26	
ROUNDED TOTAL					120			24			80						360						26	

DATE	REVISIONS	DATE	REVISIONS

GEORGIA
DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
STANDARD SIGNS