

Environmental Resources Impact Table

Resource Name/Type	Location		Side	Construction Activity	Permitted Activity	Controlling Criteria	Special Provision?	Comments including any permit expiration dates
	Beginning STA	Ending STA						
Open Water 1 Buffer	~10+	~16+	Lt	None	None	NPDES		Any impacts will require a buffer variance or written permission from EPD prior to commencement of the activity.
Open Water 1	~10+	~16+	Lt	None	None	Section 404 of the CWA		Any impacts to the open water would require evaluation for a Section 404 permit.
Wetland 2	~15+	~37+	both	Roadway and bridge construction	Approximately 0.24 acre permanent fill and 0.45 temporary clearing	Section 404 of the CWA		Any additional fill other than what is shown on the plans will require a permit modification or a new permit prior to commencement of the activity.
Wetland 3	~17+	~22+	Lt	Roadway and bridge construction	Approximately 0.06 acre permanent fill	Section 404 of the CWA		Any additional fill other than what is shown on the plans will require a permit modification or a new permit prior to commencement of the activity.
Open Water 4 Buffer	~18+	~19+	Rt	None	None	NPDES		Any impacts to the buffer will require a buffer variance or written permission from EPD prior to commencement of the activity.
Open Water 4	~18+	~19+	Rt	None	None	Section 404 of the CWA		Any impacts to the open water would require evaluation for a Section 404 permit.
Stream 5 Buffer	~23+	~30+	both	Roadway and bridge construction	Activities within 100 ft of the proposed bridge are exempt.	NPDES		Roadway drainage exemption - work beyond 100 ft of the proposed bridge will require a buffer variance or written permission from EPD prior to commencement of the activity.
Stream 5	~23+	~28+	both	Roadway and bridge construction	39 linear feet of bank armoring	Section 404 of the CWA		Any additional impacts to the stream would require evaluation for a Section 404 permit.
Open Water 6 Buffer	~27+	~28+	Lt	Fence construction	Fencing is exempt.	NPDES		Any other impacts to the buffer will require a buffer variance or written permission from EPD prior to commencement of the activity.
Open Water 6	~27+	~28+	Lt	None	None	Section 404 of the CWA		Any impacts to the open water would require evaluation for a Section 404 permit.
Migratory Birds	25+	26+	both	Roadway and bridge construction	Refer to Special Provision 107.23G	Migratory Bird Treaty Act	107.23g	Refer to Special Provision 107.23G
Protected Species	Entire Project Length (Open Water 1, Wetland 2, Open Water 4)		both	Roadway and bridge construction	Refer to Special Provision 107.23G	Endangered Species Act	107.23g	Refer to Special Provision 107.23G
Stream 6a Buffer	~32+	~34+	both	Fence and culvert construction	Fencing and activities within 50 ft of the proposed drainage are exempt.	NPDES		Roadway drainage and fencing exemption - work beyond 50 ft of the proposed drainage will require a buffer variance or written permission from EPD prior to commencement of the activity.
Stream 6a	~32+	~34+	both	Culvert construction	58 linear feet of impact (14 linear feet of bank armoring and 44 feet of additional culvert length)	Section 404 of the CWA		Any additional impacts to the stream would require evaluation for a Section 404 permit.



REVISION DATES

01/11/12		

STATE OF GEORGIA
 DEPARTMENT OF TRANSPORTATION

OFFICE:
 GENERAL NOTES

SR 203 OVER DRY CREEK
 BRIDGE REPLACEMENT
 BR000-0005-00(572) 11/3/2011

DRAWING No.
04-002