DETAILED ESTIMATE

ITEM CODE NO.	DESCRIPTION	UNIT	QUANTITY
150-1000	TRAFFIC CONTROL - STP-0005-00(893)	LS	LUMP
158-1000	TRAINING HOURS	HR	1000
441-0104	CONCRETE SIDEWALK, 4 IN	SQ YD	1,836
441-6022	CONCRETE CURB & GUTTER, 6 IN X 30 IN, TP2	LF	1,000
615-1200	DIRECTIONAL BORE-3 IN	LF	635
636-1032	HIGHWAY SIGNS TP 2 MATL, REFL SHEETING, TP 6	SQ FT	1,889
636-2070	GALV STEEL POSTS, TP 7	LF	1,819
639-2001	STEEL WIRE STRAND CABLE, 1/4 IN	LF	11427
639-3004	STEEL STRAIN POLE, TYPE IV	EA	7
639-3014	STEEL STRAIN POLE, TYPE IV , INCL LUMINAIRE ARM	EA	67
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 1 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 2 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 3 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 4 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 5 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 6 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 7 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 8 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 9 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 10 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 11 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 12 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 13 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 14 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 15 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 16 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 17 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 18 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 19 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 21 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 22 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 23 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 24 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 25 - STP-0005-00(893)	LS	LUMP
647-1000	TRAFFIC SIGNAL INSTALLATION NO. 30 - STP-0005-00(893)	LS	LUMP
647-2120	PULL BOX, PB-2	EA	2
647-2140	PULL BOX, PB-4	EA	27
653-1704	THERMOPLASTIC SOLID TRAFFIC STRIPE, 24 IN, WHITE	LF	734
653-1804	THERMOPLASTIC SOLID TRAFFIC STRIPE, 8 IN, WHITE	LF	5,056
653-3501	THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 IN, WHITE	GLF	90
682-6120	CONDUIT, RIGID, 2 IN	LF	115
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	395
682-6233	CONDUIT, NONMETL, TP 3, 2 IN	LF	850
687-1000	TRAFFIC SIGNAL TIMING - STP-0005-00(893)	LS	LUMP
935-1112	OUTSIDE PLANT FIBER OPTIC CABLE, LOOSE TUBE, SINGLE MODE, 12 FIBER	LF	2,488
935-1113	OUTSIDE PLANT FIBER OPTIC CABLE, LOOSE TUBE, SINGLE MODE, 24 FIBER	LF	12,202
935-1511	OUTSIDE PLANT FIBER OPTIC CABLE, DROP, SINGLE MODE, 6 FIBER	LF	8,164
935-3201	FIBER OPTIC CLOSURE, AERIAL (SEALED), 6 FIBER	EA	15
935-3203	FIBER OPTIC CLOSURE, AERIAL (SEALED), 24 FIBER	EA	1
935-3501	FIBER OPTIC CLOSURE, FDC (WALL MOUNTED), 6 FIBER	EA	25
935-4010	FIBER OPTIC SPLICE, FUSION	EA	68
935-5050	FIBER OPTIC PATCH CORD, SM	EA	1
935-6562	EXTERNAL TRANSCEIVER, DROP AND REPEAT, 1310 SINGLE MODE (SIGNAL JOBS)	EA	25
935-8000	TESTING - STP-0005-00(893)	LS	LUMP

REVISED: 03-23-04

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-0005-00(893)	7.	92

REVISIONS

DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION
02-23-04	EKN	ITEM NO. 639-1032 QTY. TO 1889 SQ FT			
02-23-04	EKN	DELETED REM. STEEL STRAIN POLE			
02-23-04	EKN	ADDED TRAFFIC SIGNAL TIMING			

TRANSCORE®

	NAME	DATE
DESIGNED BY	EKN	01/03
CHECKED BY	ENW	10/03
SUPERVISED BY: ARTHUR E. HAYNES		

	NAME	DATE
FIRST DRAWN	NDH	01/03
LAST DRAWN	RDG	10/03
SUBMITTED BY: ENW		DATE: 10/03

GEORGIA
DEPARTMENT OF TRANSPORTATION

DETAILED ESTIMATE SHEET

ACCOUNT NO.

DRAWING NO.