STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA	CSSTP-0006-00(41)	14	495

USE ON CONSTRUCTION

CONCRETE CURB & GUTTER 8"x30" TYPE 7, STD. 9032-B

STATION TO STATION	SIDE	LIN.FT.
100+00.00 TO 107+00.00	MED	1542
117+05.00 TO 125+00.00	MED	1516
RAMP A ISLAND	MED	103
RAMP B ISLAND	MED	147
RAMP C ISLAND	MED	104
RAMP D ISLAND	MED	153
TOTAL		3565

CONCRETE CURB & GUTTER 8"X30" TYPE 2, STD. 9032-B

STATION TO STATION	SIDE	LIN.FT.
106+50.00 TO 117+05.00	LT	942
117+05.00 TO 121+50.00	LT	530
121+50.00 TO 124+50.00	LT	267
103+45.00 TO 117+05.00	RT	1360
117+05.00 TO 122+45.00	RT	586
122+45.00 TO 124+32.00	RT	194
TOTAL		3879

GUARDRAIL QUANTITIES

GA STDS 4010, 4011A, 4012C, 4012D, 4040, 4052, 4270

LOCATION/SIDE	"T" BEAM	"W" BEAM	ANCHORAGES GA STD 4012-D	ANCHORAGES GA STD 4040	ASPHALT HEADER CURB
	LIN FT	LIN FT	TP 1	TP 12	LIN FT
SIXES ROAD					
102+00 TO 104+00 RT	10	206		1	
114+28 TO 348+23 RT	10	319		1	319
203+50 TO 110+94 RT	10	502	1		502
401+11 TO 121+00 LT		454		1	
113+59 TO 401+14 LT	10	292	1		290
RAMP B					
346+00 TO 348+23 LT		223			
346+00 TO 348+23 LT					125
RAMP C					
416+67 TO 423+75 RT	10	732	1	1	732
426+00 TO 428+00 RT	10	200	1		200
RAMP D					
512+00 TO 513+00 RT	10	100		1	100
515+60 TO 517+50 RT	10	169	1		
524+17 TO 527+50 RT	10	335		1	335
530+00 TO 532+50 RT	10	202	1		202
541+50 TO 545+50 RT		401	1	1	400
544+50 TO 545+50 LT		100	1	1	
TOTALS	100	4235	8	8	3205

NOTE: STATIONS 102+00 TO 104+00 RT ADDITIONAL LENGTH 7' POLES ARE TO BE USED WITH 1' CLEARANCE BEHIND GUARDRAIL (SEE STANDARD 4052)

IMPACT ATTENUATOR UNIT, TYPE P-3-B-30

LOCATION	QTY
109+06	1
115+34	1
TOTAL (EA)	2

REINFORCED CONCRETE APPROACH SLAB GA. STD. 9017-M & P

LOCATION	REINFORCED CONCRETE APPROACH SLAB INCL SLOPED EDGE & SUBBASE	CATCH BASINS GA. STD. 9017-C	12" SLOPE DRAIN PIPE	CLASS B CONCRETE APRON
	SQUARE YDS	EACH	LIN. FT	CU. YDS
110+50 RT	171			
110+50 LT	161			
114+00 RT	182			
114+00 LT	166			
TOTALS	680			

RIGHT OF WAY MARKERS

17 EA

CONCRETE SIDEWALK, 4 IN.

1719 SY

CHANGEABLE MESSAGE SIGN, PORTABLE TYPE 3

TOTAL (EACH) 4

SIDE DRAIN PIPE

STATION	SIDE	LIN. FT. 15"	18"	24"	30"	FLARED END SECTION-EACH STD. 1120 15"	18"	24"	30"
124+50.00	RT		65				2		
TOTALS			65				2		

CONCRETE BARRIER

LOCATION	SIDE	TYP. 2 LIN. FT.	TYP. 2A LIN. FT.	TYP. 2B LIN. FT.	TYP 7-TS LIN. FT.
WALL 1 STA 513+00.00 TO 516+50.00	RT	40	211		21
WALL 2 STA 527+50.00 TO 530+00.00	RT		196	55	21
WALL 3 STA 424+00.00 TO 426+00.00	RT		200		21
WALL 4 STA 104+00.00 TO 106+50.00	RT	100	150		10.5
WALL 5 STA 341+86.00 TO 346+50.00	RT		164	300	
STA 109+19+00 TO 110+80.00	MED	267			
STA 114+00.00 TO 115+20.00	MED	250			
STA 401+00.00 TO 405+50.00 RAMP C WALL REPLACEMENT	RT	50		400	
TOTAL		707	921	755	73.5

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES
2/3/2011
4/27/2011
6/3/2011
7/27/2011
8/11/2011
8/24/2011
9/13/2011

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY OF QUANTITIES

CSSTP-0006-00(041)
SIXES ROAD

DRAWING No. 6-02

3/1/2007 GQUANT