SUMMARY OF QUANTITIES - MISCELLANEOUS

VOID

DELINEATORS (EACH)

INCLUDING POST - SEE GA. STD. 9030C

LOCATION	TYPE 1			TYPE 1A			TYPE 2	
	CLEAR	YELLOW	RED	CLEAR	YELLOW	RED	CLEAR	YELLOW
RAMP 'A' SURVEY	11	11						
						4		
RAMP 'B' SURVEY	9	9						
RAMP 'C' SURVEY	13	13					7	
RAMP 'D' SURVEY	12	12				6	27	
TOTAL	45	45				10	34	

GENERAL NOTES:

1. Delineators shall be placed along the right side of the through Interstate roadways, two(2) feet beyond the outside edge of roadway shoulder or the face of an unmountable curb, or in the line of the guard rail. At Interchanges, delineators shall be located along the outside of ramp curves, i.e., on the left side for ramps curving to the right and on the right side for ramps curving to the left. Spacing on Interstate mainlines shall be 528 feet. Spacing on ramps shall be 100 feet unless otherwise shown on the plans.
2. Installation of delineators shall be with until grassing has been accepted by the State.
3. Red delineators, Type 1 or Type 1A, shall be installed on exit ramps facing toward the ramp terminal beginning at the "Wrong Way" signs and ending at the ramp terminal. Spacing shall be 100 feet unless otherwise shown on the plans.
4. Delineator color shall be the same as the edgeline. For additional information, see Ga. Standard 9030c.

GPLN

DESIGNED BY: TF	CHECKED BY: PA	DATE: 6-23-10
	REVIEWED BY:	DATE:

GEORGIA
DEPARTMENT OF TRANSPORTATION

NOT TO SCALE

REVISIONS

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: TRAFFIC OPERATIONS
SIGNING AND MARKING PLANS
DELINEATORS AND/OR MILEPOSTS

DRAWING No. 06-1(