













STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CSSTP-0006-00040	415	495



NORMAL DITCH SECTION

SIDE DITCHES WILL BE PROTECTED AS SHOWN ON THE PLANS.

SIDE DITCHES WILL BE FLARED OUT TO NATURAL GROUND WHERE GROUND SLOPE DOES NOT EXCEED 4% AND WATER WILL FLOW AWAY FROM ROADWAY. WHERE NATURAL GROUND EXCEEDS 4% SLOPE EXTEND SIDE DITCH TO NATURAL CHANNEL WITHIN R/W.

SIDE DITCHES TO TAIL OUT WATER FROM LONG CUT SECTIONS WILL BE PROJECTED AS DESIGNATED ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

BERM DITCHES WILL BE USED WHERE NATURAL GROUND SLOPES TOWARDS THE ROADWAY IN FILL SECTIONS. BERM DITCHES WILL BE PROTECTED AS SHOWN ON THE PLANS.

SOD DITCH CHECKS WILL BE USED IN BERM DITCHES ON GRADES OF 2:1% OR OVER AS SHOWN ON THE PLANS.

UNPAVED BERM DITCHES WILL BE FLARED OUT TO NATURAL GROUND AT INLETS OF CROSS DRAINS.

NOTE: SURFACE DITCHES WILL BE REQUIRED AT THE TOP OF CUT SLOPES WHERE SHOWN ON THE PLANS OR WHERE IT IS DETERMINED BY THE ENGINEER ON CONSTRUCTION THAT THEIR USE IS ESSENTIAL IN GENERAL. SURFACE DITCHES WILL BE REQUIRED WHERE THE SLOPE OF THE NATURAL GROUND AT THE TOP OF THE CUT DRAINS TOWARDS THE ROADWAY AND THE MATERIAL IN THE BACK SLOPE IS SUBJECT TO EROSION. SURFACE DITCHES ARE TO BE PROTECTED AS SHOWN ON PLANS.

CONSTRUCTION DETAILS

BERM DITCHES  
SIDE DITCHES  
SURFACE DITCHES

REV. & REDR. JULY, 1980

NO SCALE