

AS-BUILT PLANS 12/12/12

PIPE CURVED ALIGNMENT USING SECTIONS WITH DROPPED JOINTS

NOTE TO DESIGNER:
A COST COMPARISON ESTIMATE SHALL BE MADE BEFORE PIPE CURVED ALIGNMENT IS SPECIFIED.

NOTES FOR PIPE CURVED ALIGNMENT:

- PLANS ARE TO SPECIFY ONLY THE PIPE DIAMETER "D", THE ANGLE "Δ", AND THE TANGENT ALIGNMENT.
- PIPE WALL THICKNESS "T", PIPE SECTION LENGTHS "L", AND DROP IN PIPE JOINT "Δ" VARIES ACCORDING TO PIPE PRODUCER AND IS BASED ON FEASIBILITY.
- THE RADIUS "R" AND THE NUMBER OF DROPPED JOINT PIPE SECTIONS "N" IS DETERMINED BY (1) & (2) ABOVE. MINOR MODIFICATIONS IN THE RADIUS "R" ARE NORMALLY MADE SO THAT "N" WILL BE A WHOLE NUMBER.
- PIPE SECTIONS SHALL BE ORIENTED SUCH THAT THE PLANE OF THE DROPPED JOINT IS AT RIGHT ANGLES TO THE THEORETICAL CIRCULAR CURVE. THE TOP OF SECTIONS ARE TO BE MARKED SO THAT THE DEFLECTION ANGLE IS PROPERLY ORIENTED.
- DETAILS ARE SHOWN FOR CONCRETE PIPE. CURVED ALIGNMENT FOR C.M. PIPE SHALL BE AS RECOMMENDED BY THE MANUFACTURER AND APPROVED BY THE ENGINEER.
- PAYMENT PER LIN. FT. PIPE INCLUDES PIPE SECTIONS WITH DROPPED JOINTS.

FORMULA:
$$\tan \frac{\Delta}{N} = \frac{L}{R + \frac{D}{2} + t}$$

WHERE:
 N = NUMBER OF PIPE SECTIONS WITH DROPPED JOINTS
 D = INSIDE DIAMETER OF PIPE
 Δ = DEFLECTION ANGLE, DEGREES
 R = RADIUS OF CURVATURE (FT.)
 t = PIPE WALL THICKNESS (FT.)
 L = NORMAL LENGTH OF PIPE SECTION (FT.) 4', 6', OR 8' TYPICAL.

SECTION WITH DROPPED JOINT

DETAILS OF CONCRETE JUNCTION BOX (PRECAST OR BUILT IN PLACE)

REINFORCED CONCRETE TOP

SECTIONAL VIEW

PLAN VIEW (SHOWN WITHOUT REQ'D. TOP)

T = 6" FOR CONCRETE

DETAILS OF BRICK JUNCTION BOX FOR BRICK T= 8" (MAX. 10 FT. DEPTH)

SECTIONAL VIEW

PLAN VIEW (SHOWN WITHOUT REQ'D. TOP)

⊗ PREVENT BOND WITH EITHER 30 LB. ASPHALT SATURATED FELT OR PREFORMED FOAM JOINT FILLER.

SEE GEN. NOTE NO.3

PIPE SIZE	MIN. W OR W	MIN. H	MIN. H
15"	2'-0"	1'-9"	2'-9"
18"	2'-3"	2'-1"	3'-1"
24"	2'-10"	2'-6"	3'-8"
30"	3'-5"	3'-3"	4'-3"
36"	4'-0"	3'-10"	4'-9"
42"	4'-7"	4'-5"	5'-5"
48"	5'-2"	5'-0"	6'-0"

PIPE ELBOW SECTION (PRE-FABRICATED)

PLAN VIEW

SPLICE DETAIL (TYPICAL)

NOTES FOR PIPE ELBOW:

- PAYMENT FOR LIN. FT. OF PIPE INCLUDES ELBOWS.
- ELBOW ANGLE Δ SHALL VARY ACCORDING TO NEED, BUT SHALL NOT BE GREATER THAN 45°. THE CONTRACTOR SHALL INFORM PRODUCER AS TO ANGLE REQUIRED.
- CONCRETE PIPE SHALL BE CUT BEFORE BEING CURED AND STEEL EXPOSED FROM EACH SIDE OF CUT. (a) EXPOSED STEEL SHALL BE REJOINED, FILLER RODS AT LEAST EQUAL TO RODS IN PIPE SHALL BE ADDED AS NEEDED FOR HANDLING STRENGTH & TO HOLD GROUT. (b) ALL VOID IN SPLICE SHALL BE PACKED WITH GROUT MORTAR RICH ENOUGH TO GIVE STRENGTH AT LEAST EQUAL TO REMOVED CONCRETE WITH INSIDE SMOOTHED OUT.
- C.M. PIPE ELBOW NOT SHOWN, BUT MAY BE SPECIFIED. SOLID WELD SHALL BE REQUIRED FOR C.M. ELBOW JOINT WITH GALVANIZING AND/OR COATINGS REPAIRED AS REQ'D.

BOLT, RING & WASHER DETAILS

ALTERNATE CONNECTION FOR BOLT & RING

STEEL LIFTING BAR DETAIL

LIFT BAR SHALL BE ABLE TO MOVE UP & DOWN

DETAILS OF CIRCULAR PRECAST JUNCTION BOX
(REINFORCING AND DESIGN SHALL COMPLY WITH A.S.T.M. C-478 EXCEPT AS OTHERWISE SHOWN. MATERIALS SHALL COMPLY WITH GA. STD. SPECIFICATIONS FOR PRECAST MANHOLE)

PIPE SIZE	MIN. I.D.	T ₁ (MIN.)	T ₂ (MIN.)	MAX. PIPE CONC. C.M.	REBARS IN BOTTOM
4'-0"	5"	6"	30"	36"	#5
5'-0"	5"	8"	42"	48"	#5
6'-0"	6"	8"	54"	54"	#6

GENERAL NOTES:

- SPECIFICATIONS: GEORGIA STANDARD, CURRENT EDITION & SUPPLEMENTS THERE TO.
- ILLUSTRATED PIPES, PIPE JOINTS, ALIGNMENT, SIZES, ETC. ARE SHOWN AS REPRESENTATIVE. ACTUAL REQUIREMENTS VARY PER LOCATION AS INDICATED IN THE PLANS.
- JUNCTION BOXES DO NOT HAVE TO BE CONSTRUCTED SQUARE. W & H, DIMENSIONS MAY VARY ACCORDING TO PIPE SIZE.
- ALL JUNCTION BOX TOPS SHALL BE EQUIPPED WITH EITHER AN EYE BOLT & RING (SHOWN) OR A LIFTING BAR (ALTERNATE).
- REINFORCING IS REQUIRED FOR ALL PRECAST JUNCTION BOXES. REINFORCING MAY BE OMITTED FOR BUILT IN PLACE CONCRETE BOXES NOT OVER 10 FT. DEEP AND NOT LARGER THAN 3' x 3'. CONSTRUCTION JOINTS PERMITTED IF DOWELED OR KEYS, ALL JUNCTION BOX TOPS SHALL BE REINFORCED.

CONCRETE COLLAR FOR DEFLECTING PIPE

PLAN SECTION

NOTES FOR CONCRETE COLLARS:

- PERIMETERS OF CONCRETE COLLARS DO NOT HAVE TO BE SMOOTH LINES. COLLARS MAY BE FORMED AGAINST COMPACTED OR UNDISTURBED SOIL. DIMENSIONS ARE MINIMUM. COLLAR MAY BE SQUARE, ROUND OR SHAPE MAY VARY SO LONG AS MINIMUM DIMENSIONS ARE OBTAINED.
- ALL CONCRETE COLLARS ARE TO BE CONSTRUCTED WITH CLASS A CONCRETE.
- PAYMENT FOR LIN. FT. OF PIPE INCLUDES COLLARS.

CONCRETE COLLAR FOR JOINING PIPE

PLAN OR SIDE SECTION

DEPARTMENT OF TRANSPORTATION
STATE OF GEORGIA

STANDARD
PRECAST OR BUILT IN PLACE
JUNCTION BOXES
PIPE COLLARS, PIPE ELBOW
& PIPE CURVED ALIGNMENT

NO SCALE REV. & REDR. JULY 1985

DES. RML (SUBMITTED) *Chad Havens*
 DRW. RML STATE ROAD & AIRPORT DESIGN ENGR.
 TRA. GME (APPROVED) *Hal Kuehn*
 CHK. RKC STATE HIGHWAY ENGINEER

NUMBER
9031U

THE LPA GROUP
TRANSPORTATION CONSULTANTS
A UNIT OF MICHAEL BAKER CORPORATION
3595 ENGINEERING DRIVE
NORCROSS, GEORGIA 30092
(770) 263-9118

NO.	DATE	DESCRIPTION

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: INNOVATIVE PROGRAM DELIVERY
GEORGIA STANDARDS

DRAWING No.
41-044