VOID

SUMMARY OF STRIPING QUANTITIES

	THERMOPLASTIC PAVEMENT MARKING													RAISED PVMNT MARKERS	
	SOLID STRIPE					SKIP STRIPE		HATCHING							
	WHITE	WHITE	WHITE	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	ARROW	ARROW	ARROW	WORD		
	5 INCH	8 INCH	10 INCH	24 INCH	5 INCH	5 INCH	5 INCH			TYPE 1	TYPE 2	TYPE 3	TYPE 1	TYPE 1	TYPE 3
LOCATION	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	GLF	GLF	SQ. YDS.	SQ. YDS.	EACH	EACH	EACH	EACH	EACH	EACH
PROJECT TOTAL:	15505	1870	485	201	10855	6160	1600	462	296	17	51	3	11	135	275

SUMMARY OF SIGNING QUANTITIES

		HIGHWAY SIGNS									POSTS									
		TYPE 3 SHEETING			TYPE 3 SHEETING			TYPE 9 SHEETING												BREAKAWAY SIGN SUPPORT
		TYPE 1 (0.080 ±.005 IN.)			TYPE 2 (0.100 ±.005 IN.)			TYPE 1 (0.080 ±.005 IN.)			TYPE 7 (2" 14GA)			TYPE 9 (2 1/4" 14GA)			TYPE 8 (2 1/2" 12GA)			
											LENGTH			LENGTH			LENGTH			
LOCATION	CODE	SIZE	QTY	SQ. FT.	SIZE	QTY	SQ. FT.	SIZE	QTY	SQ. FT.	LIN. FT.	QTY	LIN. FT.	LIN. FT.	QTY	LIN. FT.	LIN. FT.	QTY	LIN. FT.	EA
US 29/ SR 14																				
STA. 110+00 LT.	R4-7	24"X30"	1	5.0							13.0	1	13.0							
STA. 110+15 LT.	M4-5	36"X18"	1	4.5																
	M1-1	24"X24"	1	4.0							14.0	1	14.0							
STA. 111+40 LT.	R8-3A	18"X24"	1	3.0							12.0	1	12.0							
STA. 112+19 LT.	W3-3							36"X36"	1	9.0				14.3	1	14.3				
STA. 113+13 LT.	R8-3A	18"X24"	1	3.0							13.0	1	13.0							
STA. 115+10 RT.	R8-3A	18"X24"	1	3.0							13.0	1	13.0							
STA. 115+16 LT.	R1-1							36"X36"	1	9.0				14.3	1	14.3				
STA. 115+84 RT.	M2-1	30"X12"	1	2.5																
	M1-5	24"X24"	1	4.0							13.0	1	13.0							
STA. 117+00 RT.	R3-7	36"X36"	1	9.0							13.0	1	13.0							
STA. 117+10 RT.	R14-1	24"X18"	1	3.0																
	I-8	42"X24"	1	7.0										13.7	1	13.7				
STA. 117+60 RT.	W11-2							36"X36"	1	9.0				15.3	1	15.3				
	W16-9P							24"X12"	1	2.0										
STA. 118+00 LT.	M4-1A	36"X18"	1	4.5																
	M1-4	24"X24"	1	4.0										13.5	1	13.5				
	M3-3	36"X18"	1	4.5																
	M1-5	24"X24"	1	4.0																
	M1-4	24"X24"	1	4.0										16.0	1	16.0				
STA. 118+48 LT.	R5-1	36"X36"	1	9.0										14.3	1	14.3				
STA. 118+78 LT.	R5-1	36"X36"	1	9.0										14.3	1	14.3				
STA. 119+00 RT.	R3-7	36"X36"	1	9.0							13.0	1	13.0							
STA. 119+30 RT.	M3-4	30"X15"	1	3.13													15.0	2	30.0	2
	M3-2	30"X15"	1	3.13																
	M1-5(16)	24"X24"	1	4.0																
	M1-5(16)	24"X24"	1	4.0																
	M6-3	30"X21"	1	4.38										15.3	1	15.3				
	M6-1R	30"X21"	1	4.38										15.3	1	15.3				
STA. 119+75 RT.	W3-3							36"X36"	1	9.0				15.6	1	15.6				
	W16-8P							42"X15"	1	4.38										
SUBTOTAL				119.02						42.38			104.0			161.9			30	2

CHA
270 Peachtree St. NW, Suite 1500 • Atlanta, GA 30303-1283
Main: (678) 954-5000 • www.chacompanies.com

REVISION DATES		
4/07/14		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY QUANTITIES

PROJECT: CSMSL-0006-00(293)
COUNTY: COWETA

DRAWING No. 6-004

GPLN