VOID

SUMMARY OF QUANTITIES-STANDARD SIGNS

STATION	INSTL NO	CODE	SIGNS (TYPE IX) REFLECTIVE SHEETING) TYPE 1 (0.08) SIZE	QTY	SQ FT	SQUARE TUBE POST TYPE 9 LENGTH FEET	QTY	TOTAL LENGTH
102+50	1	W8-13(36)	36	1	9.00	13	1	13
103+20	2	R3-17(24X18)	24 X 18	1	3.00	12	1	12
104+75	3	R3-17(24X18)	24 X 18	1	3.00	12	1	12
105+23	4	1-3(42X24)	42 X 24	1	7.00	12	1	12
109+60	5	R3-17(24X18)	24 X 18	1	3.00	12	1	12
109+13	6	1-3(42X24)	42 X 24	1	7.00	12	1	12
110+48	7	R4-4(36X30)	36 X 30	1	7.50	13	1	13
112+16	8	W8-13(36)	36	1	9.00	13	1	13
112+09	9	R4-7(24X30)	24 X 30	1	5.00	13	1	13
112+57	10	RS-031(24X24)	24 X 24	1	4.00	12	1	12
112+57	11	RS-031(24X24)	24 X 24	1	4.00	12	1	12
113+27	12	R1-1(30)	30	1	3.00	13	1	13
113+62	13	R3-17(24X18)	24 X 18	1	3.00	12	1	12
			TOTALS		67.50			161.00

SUMMARY OF QUANTITIES-WATER AND SEWER MAIN

ITEM DESCRIPTION	UM	QUANTITY
WATER MAIN, 8 IN	LF	999
STEEL CASING, 16 IN	LF	80
REMOVE EXISTING WATER MAIN 8 IN	LF	574
FLOWABLE FILL	CY	37
CONCRETE BLOCKING (CLASS B CONCRETE)	CY	15
GATE VALVE, 8 IN	EA	1
GATE VALVE, 8 IN (INSERT TYPE)	EA	2
WATER MAIN, 16 IN	LF	972
STEEL CASING, 24 IN	LF	100
REMOVE EXISTING WATER MAIN, 16 IN	LF	559
GATE VALVE, 16 IN (INSERT TYPE)	EA	2
FIRE HYDRANT	EA	3
WATER SERVICE LINE, ¾IN	LF	217
WATER METER, ¾IN	EA	1
SANITARY SEWER FORCE MAIN, 4 IN	LF	600
STEEL CASING, 10 IN	LF	72
REMOVE EXISTING SANITARY SEWER FORCE MAIN, 4 IN	LF	404
BUTTERFLY VALVE, 16 IN	EA	2

TRAFFIC STRIPING

ITEM	UNIT	QUANTITY
THERMOPLASTIC SOLID TRAFFIC STRIPE, 8 IN, WHITE	LF	260
THERMOPLASTIC SOLID TRAFFIC STRIPE, 24 IN, WHITE	LF	24
THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	2434
THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, YELLOW	LF	700
SKIP TRAFFIC STRIPE, 5 IN, WHITE (THERMOPLASTIC)	GLF	1614
SKIP TRAFFIC STRIPE, 5 IN, WHITE (PAINT)	GLF	382
PAVEMENT MARKING ARROW, TYPE 1	EA	3
PAVEMENT MARKING ARROW, TYPE 2	EA	6
PREFORMED PLASTIC SOLID, 8 IN, CONTRAST (BLACK-YELLOW)	LF	662
PREFORMED PLASTIC SKIP, 8 IN, CONTRAST (BLACK-WHITE)	LF	662
SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	2055
RAISED PAVEMENT MARKERS, TYPE 3	EA	30

LIGHTING

ITEM	UNIT	QUANTITY
REM LIGHTING STANDARD	EA	1

GRESHAM SMITH AND PARTNERS

NOT TO SCALE

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: PROGRAM DELIVERY

SUMMARY OF QUANTITIES
CR 481/COLLEGE STATION ROAD

CSBRG-0006-00(320)
CLARKE COUNTY

DRAWING No. 06-003