agraves

SUMMARY OF QUANTITIES

TRAFFIC CONTROL	
CSSTP-0006-00(435)	LS
GRADING COMPLETE	
CSSTP-0006-00(435)	LS

AGGR SURF CRS	
TOTAL	225 TN

DRIVEWAY CONC, 6 IN TK	
TOTAL	33 SY
SAWED JOINTS IN EXISTING PAVEMENT	
TOTAL	12 LF

RIGHT OF WAY MARKERS	
TOTAL	12 EA

FLOWABLE FILL	
TOTAL	10 CY

CLASS "B" CONCRETE (PIPE PLUGS)	
TOTAL	1 CY

CONCRETE CURB AND GUTTER, 8"X30", TP 2	
TOTAL	335 LF

CONCRETE HEADER CURB, 8", TP 3	
TOTAL	126 LF

CONC VALLEY GUTTER	
TOTAL	18 SY

ROADWAY QUANTITIES

ITEM		MAINLINE	SHDLR	SIDEROAD MAXWELL	SIDEROAD JOYNER	SIDEROAD RIDGECREST	SIDEROAD GRADY	PVMT EDGE TREATMENT	As Directed by Eng.	GRAND TOTAL
RECYCLED ASPH CONC. 9.5 mm SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	349	65	6	19	7	9	2	92	549
RECYCLED ASPH CONC. 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	195	104	10	31	10			70	420
RECYCLED ASPH CONC. 25 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	293	155	25	76	25			115	689
RECYCLED ASPH CONC. LEVELING, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	22		1	1	1	1		5	31
BITUMINOUS TACK COAT	GL	345	113	11	33	11	5		104	622
GR AGGR BS CRS 8IN	SY	1728	913	89	271	89			618	3708
INDENTION RUMBLE STRIPS - GROUND-IN-PLACE - INTERMEDIATE	GLM	0.32								0.32

DRIVEWAY QUANTITIES

STA./SIDE	WIDTH	RECYCLED ASPH. CONC. 9.5 mm TYPE II SUPERPAVE, INCL BITUM MATL & H LIME (165 LBS/SQ YD)	RECYCLED ASPH. CONC. 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME (220 LBS/SQ YD)	6" GAB	BITUMINOUS TACK COAT
209+72.29 RT.	14'	6 TONS		68 SY	5 GALS
210+48.70 RT.	14'	6 TONS		67 SY	5 GALS
211+19.56 RT.	20'	7 TONS		78 SY	6 GALS
211+23.68 LT.	14'	7 TONS		78 SY	6 GALS
211+92.44 RT.	33'	9 TONS	12 TONS	103 SY	13 GALS
212+66.69 RT.	33'	9 TONS	11 TONS	101 SY	12 GALS
213+27.52 RT.	14'	2 TONS		26 SY	2 GALS
216+13.03 RT.	16'	5 TONS		67 SY	5 GALS
217+61.54 LT.	14'	6 TONS		68 SY	5 GALS
218+30.43 RT.	14'	5 TONS		54 SY	4 GALS
218+73.05 LT.	14'	6 TONS		71 SY	6 GALS
219+55.09 RT.	20'	8 TONS	10 TONS	90 SY	11 GALS
219+60.22 LT.	14'	6 TONS		75 SY	6 GALS
220+01.40 LT.	14'	6 TONS		78 SY	6 GALS
221+02.69 LT.	14'	2 TONS		19 SY	2 GALS
TOTAL		90 TONS	33 TONS	1043 SY	94 GALS
AS DIRECTED		18 TONS	7 TONS	209 SY	19 GALS
GRAND TOTAL		108 TONS	40 TONS	1252 SY	113 GALS

CLASS "B" CONC BASE OR WIDENING	
TOTAL	35 CY
PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	
TOTAL	40 LF

STORM DRAIN QUANTITIES

STATION	STORM DRAIN PIPE GA STD 1030D H=1-10		SAFETY GRATE TYPE 1		SAFETY END SECTION 18"
			HEADWALL & SAFETY INLET CONC INCL REIN STEEL	REINFORCEMENT STEEL	
	18" LF	24" LF	CY	SF	EA
214+53.07		80	2	56	
213+32.58 LT.	56				2
214+81.47 RT.	56				1
215+98.87 LT.	56				2
221+15.65 RT.	56				2

DROP INLET QUANTITIES

STRUCTURE NUMBER	STATION/ LOCATION	GA STD 1019A TYPE E WITH HOOD	
		EA	H=
DS-A1	214+53.07 RT	1	5.15

SUMMARY OF SIDE DRAIN PIPE

LOCATION	18" PIPE	18" SAFETY END SECTIONS 6:1
STATION & SIDE	FT.	EA
209+72.20 RT.	48.00	2.00
210+48.70 RT.	48.00	2.00
211+19.56 RT.	56.00	2.00
211+23.68 LT.	72.00	2.00
216+13.03 RT.	56.00	2.00
217+61.54 LT.	56.00	2.00
218+30.43 RT.	64.00	2.00
218+73.05 LT.	48.00	2.00
219+00.00 RT.	64.00	2.00
219+55.09 RT.	56.00	2.00
219+60.22 LT.	56.00	2.00
220+01.40 LT.	64.00	2.00
221+02.69 LT.	64.00	2.00
TOTAL	752.00	26.00

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES
11/27/12

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: District 4 Tifton
SUMMARY OF QUANTITIES
SR 93 @ JOYNER RD

DRAWING No. 6-001

3/1/2007 GQUANT