

## SUMMARY OF QUANTITIES-CHANGEABLE MESSAGE SIGNS

STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	CSMSL-0006-00( 478)	20	43

INSTALLATION NUMBER	HIGHWAY	STATION	GUARD RAIL	GUARDRAIL ANCHORAGES		STRUCTURAL SUPPORT			CHANGEABLE MESSAGE		
			G A . S T D S 4010 AND 4011	G A . S T D S . 4012C & 4040		( L U M P )			S I G N S ( E A C H )		
			( L I N E A R F E E T )	TYPE 1	TYPE 12	NAVIGATOR STRUCTURE NUMBER	TYPE	SPAN	S I G N NUMBER	S I Z E	C H A R A C T E R H E I G H T
1	I-85 NB	209+00	250	1	1	NAV E 90-15	III	28	494	3X15	18"
2	I-75 SB	619+30	200			NAV D 260-61	III	28	495	3X15	18"
3	I-85 SB	505+90	125		1	NAV F 98-33	III	28	496	3X15	18"
4	I-75 NB	451+25				NAV C 257-66	III	28	497	3X15	18"
TOTAL			575	1	2						

GENERAL NOTES:

1. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO AVOID ANY INTERFERENCE WITH UNDERGROUND UTILITIES. ANY DAMAGE TO UTILITIES CAUSED BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. CONTRACTOR SHALL CALL (770) 623-4344 PRIOR TO ANY DIGGING.
2. MAINTENANCE WALKWAYS ARE REQUIRED ON THE STRUCTURAL SUPPORTS FOR ALL SIGNS IN THIS PROJECT (TYPE III.)
3. FOR LOCATION OF GUARDRAIL, SEE GEORGIA STANDARDS 4022A AND 4051 AND/OR CONSTRUCTION DETAILS.
4. COST FOR ANY REQUIRED TEMPORARY EROSION CONTROL SHALL BE INCLUDED IN BID PRICE FOR SIGN STRUCTURES.
5. ANY TREES, SHRUBS, OR FLOWERS THAT ARE DAMAGED DURING INSTALLATION OF NEW SIGN STRUCTURES SHALL BE REPLACED IN KIND AT NO ADDITIONAL COST TO THE DEPARTMENT IN ACCORDANCE WITH SECTION 702 OF THE GEORGIA SPECIFICATIONS, EXCEPT THAT SECTION 702.1 SHALL NOT APPLY TO THIS PROJECT.
6. THE CONTRACTOR SHALL ENSURE THAT ALL MESSAGE SIGNS INSTALLED BY THIS PROJECT HAVE A MINIMUM SIGHT DISTANCE OF 900 FT. CLEARING OF OBSTACLES TO OBTAIN THE MINIMUM SIGHT DISTANCE SHALL BE IN ACCORDANCE WITH SECTION 201 PF THE GEORGIA SPECIFICATIONS. THE COST OF THIS WORK SHALL BE INCLUDED IN THE OVERALL PRICE BID FOR THE PROJECT.

STATE OF GEORGIA  
DEPARTMENT OF TRANSPORTATION  
OFFICE OF TRAFFIC OPERATIONS

ITS - CMS & SURVEILLANCE  
ENHANCEMENTS TO EXISTING SYS