

### ROADWAY SURFACING QUANTITIES

	UNIT	QUANTITY	AS DIRECTED BY ENGINEER	TOTAL
AGGREGATE SURFACE COARSE	TN	502	48	550

### GUARDRAIL QUANTITIES

BEGIN STA	END STA	SIDE	TYPE 'W'-BEAM LENGTH (LF)	TYPE 'T'-BEAM LENGTH (LF)	TYPE 1 ANCHORS (EA)	TYPE 12 NON-FLARED ANCHORS (EA)
CR183/PLANTATION RD						
11+87.37	13+55.02	RT	150	21		1
12+86.87	13+57.52	LT	50	21	1	
15+43.09	17+51.24	RT	188	21	1	
15+40.37	18+61.02	LT	300	21		1
TOTAL			688	84	2	2

### TYPE I SPILLWAY GDOT STD 9017J

ITEM	UNIT	QUANTITY	AS DIRECTED	TOTAL
SLOPE DRAIN PIPE, 18"	LF	21	4	25
CLASS B CONCRETE (OUTLET APRON)	CY	0.17	.83	1
CONCRETE SPILLWAY, TYPE 1	EA	1	0	1

### REINFORCED CONCRETE APPROACH SLAB GDOT STD 9017Q

BEGIN STA	END STA	APPROACH SLAB (SY)
CR183/PLANTATION RD		
13+34.00	13+54.00	57
15+44.00	15+64.00	57
SUB-TOTAL		114
AS DIRECTED BY ENGINEER		6
TOTAL		120

### TRAFFIC CONTROL CSBRG-0006-00(660)

TOTAL	LUMP SUM
-------	----------

NOTE: THE ACTUAL BEGINNING AND ENDING OF GUARDRAIL MAY BE ADJUSTED TO MEET FIELD CONDITION, AS DIRECTED BY THE ENGINEER.

### GRADING COMPLETE CSBRG-0006-00(660)

TOTAL	LUMP SUM
-------	----------

### FENCING

ROADWAY	SIDE	BEGIN STA	END STA	FIELD FENCE BARBED WIRE 3 STRANDS (LF)
PLANTATION RD/ CR 183	RT	10+66.85	13+59.92	293
PLANTATION RD/ CR 183	LT	12+55.25	13+75.23	126
PLANTATION RD/ CR 183	RT	14+60.89	15+88.58	128
PLANTATION RD/ CR 183	LT	14+85.34	19+71.00	525
PLANTATION RD/ CR 183	RT	18+04.01	19+65.00	180
AS DIRECTED BY ENGINEER				48
TOTAL				1300

### STONE DUMPED RIPRAP TYPE 3, 18 IN

LOCATION	RIP-RAP SY	PLASTIC FILTER FABRIC SY
13+80 LT	8	8
15+63 RT	3	3
17+38 RT	8	8
AS DIRECTED	1	1
TOTAL	20	20

### RIGHT OF WAY MARKERS

EA	18
----	----

### GRASSING ITEMS

ITEM	PERMANENT GRASSING	TEMPORARY GRASSING	AGRICULTURAL LIME	FERTILIZER MIXED GRADE	FERTILIZER NITROGEN CONTENT	MULCH
UNIT	AC	AC	TON	TON	LB	TON
	2	1	2	2	100	28
AS DIRECTED BY ENGINEER			1	1	20	6
TOTAL	2	1	3	3	120	34

### EROSION CONTROL ITEMS

	CONSTRUCTION EXIT	MAINTENANCE OF CONSTRUCTION EXIT	EROSION CONTROL MATS, SLOPES	CONST. & REM FABRIC CHECK DAM TYPE C SILT FENCE	TEMPORARY SILT FENCE, TYPE C	MAINTENANCE OF TEMP. SILT FENCE, TYPE C	CONSTRUCT AND REMOVE TEMPORARY PIPE SLOPE DRAIN	MAINTENANCE OF CHECK DAMS - ALL TYPES	PERMANENT SOIL REINFORCING MAT	CONSTRUCT AND REMOVE SEDIMENT BARRIER-BALED STRAW	MAINTENANCE OF SEDIMENT BARRIER-BALED STRAW
	EA	EA	SY	LF	LF	LF	LF	LF	SY	LF	LF
SUB-TOTAL	2	2	1680	740	2441	1221	75	370	733	214	107
AS DIRECTED BY ENGINEER			320	160	259	129	15	80	77	86	43
TOTAL	2	2	2000	900	2700	1350	90	450	810	300	150

### WATER QUALITY MONITORING & SAMPLING

EA	2
----	---

### WATER QUALITY INSPECTIONS

MO	12
----	----