

GENERAL NOTES

1. ALL WORK, MATERIALS, AND EQUIPMENT SHALL CONFORM TO THE GEORGIA DEPARTMENT OF TRANSPORTATION'S "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF TRANSPORTATION SYSTEMS", CURRENT EDITION.

2. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL NEW GUYS ON EXISTING UTILITY POLES WHEN ATTACHING MESSENGER CABLE OR FIBER OPTIC CABLE TO THE POLES (AT NO ADDITIONAL COST) UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

3. THE CONTRACTOR SHALL REPLACE THE FOLLOWING IN KIND AND SIZE. (AT NO ADDITIONAL EXPENSE TO THE CITIES OF SANDY SPRINGS, ROSWELL AND ALPHARETTA): ANY BARRIER WALL, FENCE, DITCH, PAVING, CURBING, EXISTING EROSION CONTROL, SIDEWALK, GUTTER, SLOPE PAVEMENT, SIGNS, LOOP DETECTORS/LEAD-INS, GUARDRAIL, LANDSCAPING, GRASSING, UTILITY SERVICE LINES, STORM DRAIN PIPES, MASONRY WALLS, AND PAVING THAT IS REMOVED, DAMAGED, OR DESTROYED DURING THE COURSE OF CONSTRUCTING THIS PROJECT. THERE SHALL BE NO SEPARATE PAYMENT FOR THIS WORK. COST FOR THIS WORK SHALL BE INCLUDED IN THE OVERALL BID PRICE.

4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EROSION CONTROL MEASURES TO ENSURE COMPLIANCE WITH ALL STATE AND FEDERAL LAWS AND GUIDELINES. THE COST SHALL BE CONSIDERED INCIDENTAL AND INCLUDED IN THE OVERALL BID PRICE. AS GOVERNED UNDER SECTION 161.5 OF THE SPECIFICATIONS. NO SEPARATE PAYMENTS FOR INDIVIDUAL ITEMS SHALL BE MADE TO THE CONTRACTOR FOR EROSION CONTROL.

5. NOTICE OF INTENT IS NOT REQUIRED FOR THIS PROJECT.

6. ALL WORK SHALL CONFORM TO THE "NATIONAL ELECTRICAL CODE," CURRENT EDITION AND THE "NATIONAL ELECTRICAL SAFETY CODE," CURRENT EDITION.

7. CUSTOM CABLE MARKING IN 935.2.B.1 IS NOT REQUIRED ON 12 SM FIBER OPTIC DROP CABLES (935-1511).

8. THE CONTRACTOR SHALL REPAIR ALL EXISTING CONDUIT, CABLE, OR PIPE THAT IS DAMAGED BY THE INSTALLATION OF CONDUIT, FIBER OPTIC CABLE, STRAIN POLES, OR PROPOSED DEVICES WITHIN 24 HOURS. THERE IS NO SEPARATE PAYMENT FOR THIS WORK.

9. CONTRACTOR SHALL NOT RELOCATE PROPOSED STRAIN POLES WITHOUT THE APPROVAL OF THE ENGINEER.

10. MINOR TREE TRIMMING AND REMOVAL MAY BE REQUIRED AS DIRECTED BY THE ENGINEER. PAYMENT FOR THIS SHALL BE INCLUDED IN THE OVERALL BID PRICE FOR THIS PROJECT.

11. THE ELECTRICAL POWER SERVICE ASSEMBLY POINTS SHOWN ON PLANS ARE FOR THE CONTRACTOR'S USE IN DETERMINING POWER ROUTING TO EACH DEVICE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL ELECTRICAL UTILITY COMPANIES TO PROVIDE POWER TO THE SERVICE POINTS.

12. CONTRACTOR SHALL LEAVE A 5' SLACK COIL OF FDC PRE-TERMINATED CABLE IN EACH CABINET.

13. ALL EQUIPMENT SHOWN TO BE REMOVED SHALL BE RETURNED IN WORKING CONDITION TO THE LOCAL AGENCY'S TRAFFIC ENGINEERING DEPARTMENT: CITY OF SANDY SPRINGS, 7840 ROSWELL RD. BUILDING 500, SANDY SPRINGS GEORGIA 30350. (770) 730-5600
CITY OF ROSWELL, 1810 HEMBREE RD. ALPHARETTA GEORGIA 30009. (678) 297-6200
CITY OF ALPHARETTA, 1790 HEMBREE RD. ALPHARETTA GEORGIA 30009. (770) 594-6420
CONTRACTOR SHALL CALL 48 HOURS PRIOR TO DELIVERY OF EQUIPMENT. COST OF DELIVERY SHALL BE INCLUDED IN THE OVERALL BID PRICE.

14. REMOVAL AND REHAB OF EXISTING PULLBOXES FOR NEW CONDUIT OPENINGS SHALL BE INCLUDED IN THE COST OF THE NEW CONDUIT INSTALLATION.

15. THIS PROJECT CONTAINS 0.15 ACRES OF DISTURBED AREA, LESS THAN 1 ACRE, AND THEREFORE DOES NOT REQUIRE A FULL SET OF EROSION CONTROL PLANS.

16. THE CONTRACTOR SHALL NOT STAGE OR STORE ANY EQUIPMENT WITHIN THE ENVIRONMENTALLY SENSITIVE AREA (ESA) BOUNDARY.

17. ALL MOUNTING EQUIPMENT FOR CCTV CAMERAS SHALL BE INCLUDED IN THE COST OF CCTV SYSTEM, TYPE B

18. CONTRACTOR SHALL DELIVER ITEMS TO BE INSTALLED BY CITY OF ROSWELL TO:

CITY OF ROSWELL
1810 HEMBREE ROAD
ALPHARETTA, GA 30009

| UTILITY OWNERS | |
|----------------|-------------------------------------|
| UTILITY | OWNER |
| GAS | ATLANTA GAS LIGHT CO. |
| SEWER & WATER | FULTON COUNTY WATER & SEWER |
| WATER | ROSWELL PUBLIC WORKS |
| WATER | CITY OF ATLANTA |
| CABLE TV | COMCAST CABLE CO |
| ELECTRIC | GEORGIA POWER COMPANY |
| TELEPHONE | AT&T |
| OTHER | SANDY SPRINGS PUBLIC WORKS |
| OTHER | ALPHARETTA ENGINEERING/PUBLIC WORKS |
| OTHER | ROSWELL DOT |



**Know what's below
Call before you dig**



REVISION DATES

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC OPERATIONS

GENERAL NOTES

SR 9 ATMS
ABERNATHY RD. TO
FORSYTH COUNTY LINE

DRAWING No.
4-1