SR 92 RELOCATION DOUGLASVILLE, GA

UTILITY OWNERS

ALL THE FOLLOWING UTILITY OWNERS WERE REPORTED TO HAVE FACILITIES WITHIN THE VICINITY OF THIS PROJECT AT THE TIME OF THE SUE INVESTIGATION. UTILITIES FOUND WITHIN THE LOS AT THE TIME OF THE SUE INVESTIGATION ARE NOTED FOR EACH UTILITY OWNER LISTED AND ARE SHOWN ON THE PLANS HEREON.

AGL RESOURCES (AGL)
(GAS)
10 PEACHTREE PLACE
ATLANTA, GA 30309
KELLEE NEWMAN
(404) 584-4536

AT&T (ATT)
(TELEPHONE)
2310 PARKLAKE DRIVE
ATLANTA, GA 30309
JOE ORDWAY
(770) 514-9755

CITY OF DOUGLASVILLE (CD)
(ELECTRIC - LIGHTING)
6695 CHURCH STREET
DOUGLASVILLE, GA 30133
WILLIAM OSBORNE
(770) 920-3000
*AS SHOWN ON PLANS

COMCAST (COM)
(CATV)
2925 COURTYARDS DRIVE
NORCROSS, GA 30345
MAXIME LAURENCEAU
(770) 559-2096

DOUGLAS COUNTY SCHOOL SYSTEM (DCSS)
(FIBER OPTIC COMMUNICATIONS)
8334 CONNALLY DRIVE
DOUGLASVILLE, GA 30134
LEE CHRISTIANSON
(678) 895-2044
*AS SHOWN ON PLANS

DOUGLAS COUNTY WATER AND SEWER AUTHORITY
(WATER/SEWER)
P.O. BOX 1157
DOUGLASVILLE, GA 30133
DANIEL MANNY
(770) 920-3837

GDOT
(TRAFFIC CONTROL)
5025 NEW PEACHTREE ROAD
CHAMBLEE, GA 30341
KEITH MURPHY
(770) 986-1765

GEORGIA POWER (DISTRIBUTION) (GP)
(ELECTRIC)
241 RALPH McGILL BLVD. NE
ATLANTA, GA 30308
JARRETT DAVIS
(404) 506-4474

GEORGIA POWER (TRANSMISSION) (GPT)
(ELECTRIC)
241 RALPH McGILL BLVD. NE
ATLANTA, GA 30308
DON ST. CLAIR
(404) 506-2644
*AS SHOWN ON PLANS

GREYSTONE ELECTRIC (GS)
(ELECTRIC)
4040 BANKHEAD HIGHWAY
DOUGLASVILLE, GA 30134
BLAKE NEALER
(770) 370-2465
*AS SHOWN ON PLANS

NORFOLK SOUTHERN RAILROAD
(NSRR) (T-CUBED)
(FIBER OPTIC COMMUNICATIONS)
1200 PEACHTREE STREET NE
ATLANTA, GA 30309
BOX 146
TIM HARRISON
(404) 323-1709
*AS SHOWN ON PLANS

SYNC GLOBAL (SG)
(FIBER OPTIC COMMUNICATIONS)
1090-A PACIFIC AVENUE
BREMEN, GA 30110
CHRISTY RAINWATER
(770) 843-4572
*AS SHOWN ON PLANS

UNLESS OTHERWISE NOTED ON PLAN SHEETS:

- ALL CATV LINES ARE OWNED BY COMCAST.
- ALL GAS LINES ARE OWNED BY AGL.
- ALL TELEPHONE LINES ARE OWNED BY AT&T.
- ALL ELECTRIC LINES ARE OWNED BY GEORGIA POWER.
- ALL TRAFFIC CONTROL LINES ARE OWNED BY GDOT.
- ALL WATER AND SEWER LINES ARE OWNED BY DOUGLAS COUNTY.

SUBSURFACE UTILITY ENGINEERING NOTES

(1) A QUALITY LEVEL "A" SUBSURFACE UTILITY ENGINEERING INVESTIGATION (SUE) WAS PERFORMED AND COMPLETED ON 08/29/12 FOR THIS PROJECT. QUALITY LEVEL "A" DATA WAS OBTAINED AT 9 TEST HOLE LOCATIONS. A SUBSEQUENT QUALITY LEVEL "A" SUE INVESTIGATION WAS PERFORMED AND COMPLETED ON 02/01/13 FOR THIS PROJECT. QUALITY LEVEL "A" DATA WAS OBTAINED AT 28 TEST HOLE LOCATIONS. A TOTAL OF 37 TEST HOLES WERE COMPLETED FOR PHASE I. A SUBSEQUENT QUALITY LEVEL "A" SUE INVESTIGATION WAS PERFORMED AND COMPLETED ON 02/08/13 FOR THIS PROJECT. QUALITY LEVEL "A" DATA WAS OBTAINED AT 32 TEST HOLE LOCATIONS FOR PHASE II. A SUBSEQUENT QUALITY LEVEL "A" SUE INVESTIGATION WAS PERFORMED AND COMPLETED ON 03/19/13 FOR THIS PROJECT. QUALITY LEVEL "A" DATA WAS OBTAINED AT 87 TEST HOLE LOCATIONS FOR PHASE III.

(2) A QUALITY LEVEL "B" SUBSURFACE UTILITY ENGINEERING INVESTIGATION (SUE) WAS PERFORMED AND COMPLETED ON 02/09/11 FOR THIS PROJECT. THE EXISTING UNDERGROUND FACILITIES SHOWN HEREON WERE INCLUDED IN THIS SUE INVESTIGATION. THE PRESENCE OF THESE UTILITY FACILITIES HAS BEEN THOROUGHLY INVESTIGATED AND THE METHOD OF DETERMINING THEIR LOCATION IS INDICATED AS SHOWN IN THE PLANS. UTILITIES THAT HAVE BEEN INSTALLED AFTER THE DATE ABOVE HAVE NOT BEEN INCLUDED IN THIS INVESTIGATION AND SHOULD BE CONSIDERED AS FROM RECORD DRAWING ONLY. ALL OTHER EXISTING TOPOGRAPHIC FEATURES DEPICTED HEREON HAVE BEEN REFERENCED FROM A TOPOGRAPHIC / MAPPING SURVEY AND CONTROL PACKAGE PROVIDED BY GDOT AND DATED 09/16/10. SO-DEEP, INC. DOES NOT WARRANT OR CERTIFY THE ACCURACY OR COMPLETENESS OF THE INFORMATION PROVIDED BY GDOT.

(3) PLEASE NOTE THAT SO-DEEP COMPLETED A SUE INVESTIGATION FOR PJ.#0006900 (TASK ORDER #6) ON 11/09/10. THE LOS WAS SUBSEQUENTLY EXPANDED UNDER TASK ORDER #8. THE COMPLETED SUE INVESTIGATION FOR TASK ORDER #6 HAS BEEN INCORPORATED INTO THIS TASK ORDER #8 SUE INVESTIGATION.

(4) BEGINNING 01-10-2011. SYNC GLOBAL BEGAN THE INSTALLATION OF AN OVERHEAD FIBER OPTIC CABLE AND GUY ANCHORS TO EXISTING POLES ALONG SR 92. THE CONSTRUCTION HAS STARTED AT THE EAST END OF THIS PROJECT. THE TERMINAL POINT OF THIS INSTALLATION IS NOT KNOWN AT THIS TIME. AT THE TIME THE INSTALLATION OF THE FIBER OPTIC CABLE BEGAN, SO-DEEP HAD COMPLETED OUR FIELD SURVEYS AND FINAL CHECKS. THESE FACILITIES ARE NOT SHOWN IN OUR UTLE FILE OR THE POLE DATA TABLES.

(5) ALL UTILITY INFORMATION HEREON IS DEPICTED TO QL-B UNLESS OTHERWISE NOTED.

(6) EMPTY CONDUITS, TRAFFIC CONTROL SENSORS IN PAVING, AND IRRIGATION/SPRINKLER LINES WERE NOT INCLUDED IN THIS SUE PROJECT.

(7) THE EQUIPMENT USED FOR DESIGNATING INCLUDED A METROTECH 810 & 850, PIPEHORN, AND GPR. TOPCON SURVEYING INSTRUMENTS (INCLUDING GPS) WERE USED IN THE DATA COLLECTION.

(8) SIZE AND MATERIAL TYPE INFORMATION SHOWN HEREON IS TAKEN FROM AVAILABLE UTILITY RECORDS.

(9) ALL UNDERGROUND TELEPHONE IS DIRECT-BURIED UNLESS OTHERWISE NOTED.

VOID

LEGEND

ALL VAULTS SHOWN ARE BASED UPON SURFACE INFORMATION OR UTILITY RECORDS. THE SIZE, LOCATION AND ORIENTATION HAS BEEN DEPICTED TO QUALITY LEVEL "D" (QL-D) UNLESS OTHERWISE NOTED.

ABBREVIATIONS:

(QL-C)	EXISTING UTILITY STRUCTURES HAVE BEEN FIELD LOCATED AND SURVEYED TO ASSIST IN DEPICTING THE UTILITIES SHOWN ON RECORDS. NO ELECTRONIC DESIGNATING INFORMATION WAS OBTAINED.
(QL-D)	DEPICTED ACCORDING TO UTILITY RECORD INFORMATION. NO ELECTRONIC DESIGNATING INFORMATION WAS OBTAINED.
(DATFI)	DEPICTED ACCORDING TO FIELD INSPECTION
(FO)	FIBER OPTIC
(AATUR)	ABANDONED ACCORDING TO UTILITY RECORDS
(AATFI)	ABANDONED ACCORDING TO FIELD INSPECTION
(EATFI)	EMPTY ACCORDING TO FIELD INSPECTION
OUTSIDE DROP	SANITARY LATERAL THAT DROPS VERTICALLY JUST OUTSIDE A SANITARY MANHOLE AND ENTERS BOTH THE TOP AND BOTTOM OF THE MANHOLE. SO-DEEP SHOWS ONLY THE INVERT ELEVATION FOR THE TOP LATERAL.
(A)	UTILITY ATTACHED TO BRIDGE
EOI	END OF ELECTRONIC DESIGNATING INFORMATION
(NAP)	NO ASSOCIATED PIPING FOUND FROM UTILITY STRUCTURE
(NAC)	NO ASSOCIATED CABLES FOUND FROM UTILITY STRUCTURE
E———	UTILITY ENDPOINT
COMM	COMMUNICATIONS
UNK	UNKNOWN UTILITY OWNER OR MATERIAL TYPE OF UTILITY
COND.	CONDUIT
PLAS.	PLASTIC
STL.	STEEL
WRPD.	WRAPPED
AC.	ASBESTOS CEMENT
CI.	CAST IRON
DI.	DUCTILE IRON
T.C.	TERRA COTTA
RCP	REINFORCED CONCRETE PIPE
SB	PEDESTRIAN TRAFFIC SIGNAL BUTTON
GA	GUY ANCHOR
E-HV	HIGH VOLTAGE ELECTRIC TRANSMISSION LINE
MET.	METALLIC
F.L.	FLOW LINE
MCD	MULTIPLE CONCRETE DUCT
PR	PAIR
PVC	POLYVINYL CHLORIDE
PVT	PRIVATE
O.D.	OUTSIDE DIAMETER
M.I.D.	MEASURED INTERIOR DEPTH
RR	RAILROAD
SMH	SANITARY MANHOLE
CO	CLEANOUT
GV	GAS VALVE
GTS	GAS TEST STATION
STR	STRAND
THH	TELEPHONE HANDHOLE
WM	WATER METER
SVC	SERVICE, UNKNOWN SIZE/TYPE
HH	HAND HOLE
TS	TEST STATION
UGS	UNDERGROUND SPLICE

SO-DEEP, INC.
SUBSURFACE UTILITY ENGINEERING SERVICES

Georgia Office Address
60 Chamisa Road
Building 1, Suite 101
Covington, GA 30016
678-342-2775

Date: 03-22-13	Field Work By: R.B.
Scale: N/A	Drafted By: R.S.
Sheet: COVER	Checked By: J.T.
County: DOUGLAS	Task Order No.: 1
Project No.: CSSTP-0006-00(900)	
CSSTP-0006-00(901) / STP00-0186-01(011)	
P.I. No.: 0006900 / 0006901 / 720970-	
Filename: 006900UTLE.DGN	So-Deep Projects: SGMC760 SGLD666
SGLD754 SGLD770 SGLD776	

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: UTILITIES
UTILITY PLANS

SR 92 RELOCATION
P.I. #0006900 / 0006901 / 720970-
TASK ORDER #1 (JOB ORDER #3/#4/#6)

DRAWING No. 24-00A