TRAFFIC SIGNAL INSTALLATION NO. 26		
LOCATION: Lawrenceville Hwy @ Idlewood Rd		
LIST OF MATERIALS		
PROJECT NUMBER: CSSTP-0007-00(004)		
LIST OF MATERIALS	UNIT	QUANTITY
CONTROLLER CABINET ASSEMBLIES		
A. CONTROLLER UNIT, MODEL 2070L	EA	1
D. CABINET ASSEMBLY, MODEL 332	EA	1
E. SWITCH PACK	EA	12
F. DC ISOLATOR	EA	3
J. 2010 CONFLICT MONITOR, EXTENDED FEATURES	EA	1
K. BATTERY BACKUP SYSTEM		
- EXTERNAL MOUNTED, CABINET (per GDOT specs)	EA	1
LOOP/PED LEAD-IN WIRE (SHIELDED, TWISTED/1000 FT)		
A. 3 PAIR, 18 AWG	REEL	1
SIGNAL CABLE (14 AWG)		
B. 7 CONDUCTOR, PER 1000 FT.	REEL	2
ONE-WAY, 3-SECTION, 12" SIGNAL HEAD w/(5mm) PIXELATED VIEW LED's, PLASTIC	EA	4
ONE-WAY, 5-SECTION, 12" SIGNAL HEAD w/(5mm) PIXELATED VIEW LED's SIGNAL HEAD (CLUSTER), PLASTIC	EA	4
ONE-WAY, 1-SECTION, 18" LED COUNTDOWN PEDESTRIAN SIGNAL HEAD, FULL HAND/MAN OVERLAP		
1. 9" HIGH, Numbers	EA	8
PEDESTRIAN PUSHBUTTON STATION ASSEMBLY		
B. 9" x 15", w/Double Push Button Station Adapter for 4" Dia Pedestrian Pole, Adjustable	EA	8
B. 9" x 15", R10-3e, (L)eft or (R)ight, Countdown	EA	8
BACK PLATE FOR ONE-WAY, 3-SECTION, 12" SIGNAL HEAD	EA	4
BACK PLATE FOR ONE-WAY, 5-SECTION, CLUSTERED 12" SIGNAL HEAD	EA	4
HARDWARE FOR MAST ARM MOUNTING	EA	8
HARDWARE FOR PEDESTAL POLE, TOP POST MOUNTING, ONE-WAY BRACKET ASSEMBLY	EA	1
HARDWARE FOR SIDE-OF-POLE MOUNTING, ONE-WAY BRACKET ASSEMBLY	EA	1
HARDWARE FOR SIDE-OF-POLE MOUNTING, TWO-WAY BRACKET ASSEMBLY	EA	3
PEDESTAL POLE & SQUARE BASE	EA	1
MISCELLANEOUS MATERIALS NEEDED TO COMPLETE INSTALLATION	LUMP	LUMP

332 CABINET INPUT ASSIGNMENT

SLOT		1	2	3	4	5	6	7	8	9	10	11	12	13	14
UPPER INPUT FILE															
	TYPE	DET	DET	DET	DET	DET	DET	DET	DET	DET	TBA	TBA	DC	DC	DC
	CARD	IVDS	IVDS			IVDS	IVDS						DC ISO	DC ISO	DC ISO
CHANNEL 1	C1 PIN	56	39	63	47	58	41	65	49	60		80	67	68	81
	FUNCTION	VID 1	VID 2A			VID 3	VID 4						02 PED	06 PED	FLASH
	FIELD TERM	TB2 1,2	TB2 5,6	TB2 9,10	TB4 1,2	TB4 5,6	TB4 9,10	TB6 1,2	TB6 5,6	TB6 9,10			TB8 4,6	TB8 7,9	N/C
CHANNEL 2	C1 PIN	56	43	76	47	58	45	78	49	62		53	69	70	82
	FUNCTION		VID 2B										04 PED	08 PED	STOP TIME
	FIELD TERM	TB2 3,4	TB2 7,8	TB2 11,12	TB4 3,4	TB4 7,8	TB4 11,12	TB6 3,4	TB6 7,8	TB6 11,12			TB8 5,6	TB8 8,9	N/C
LOWER INPUT FILE															
	TYPE	DET	DET	DET	DET	DET	DET	DET	DET	DET	TBA	TBA	DC	DC	DC
	CARD	IVDS	IVDS			IVDS	IVDS								
CHANNEL 1	C1 PIN	55	40	64	48	57	42	66	50	59		54	71	72	51
	FUNCTION	VID 5	VID 6A			VID 7	VID 8								
	FIELD TERM	TB3 1,2	TB3 5,6	TB3 9,10	TB5 1,2	TB5 5,6	TB5 9,10	TB7 1,2	TB7 5,6	TB7 9,10			TB9 4,6	TB9 7,9	TB9 10,12
CHANNEL 2	C1 PIN	55	44	77	48	57	46	79	50	61		75	73	74	52
	FUNCTION		VID 6B												
	FIELD TERM	TB3 3,4	TB3 7,8	TB3 11,12	TB5 3,4	TB5 7,8	TB5 11,12	TB7 3,4	TB7 7,8	TB7 11,12			TB9 5,6	TB9 8,9	TB9 11,12

GRESHAM SMITH AND PARTNERS

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: TRAFFIC SAFETY AND DESIGN

MATERIALS LIST/INPUT TABLE

LAWRENCEVILLE HWY. AT IDLEWOOD RD. /MAIN ST.
INTERSECTION 26

DRAWING No. 27-84