

ENVIRONMENTAL RESOURCES IMPACT TABLE

RESOURCE NUMBER	RESOURCE NAME/TYPE	LOCATION		SIDE	CONSTRUCTION ACTIVITY	PERMITTED ACTIVITY	CONTROLLING CRITERIA	SPECIAL PROVISION	COMMENTS INCLUDING ANY PERMIT EXPIRATION DATES
		BEGINING STA	ENDING STA						
	ESA * 1	76+85 (CR48)	17+00 (SR 16)	Right	Minor Grading of a roadway ditch and Installation of property fence		Section 106 of the National Preservation Act	107.23F	The contractor ensure that no additional construction related activities including the use of easements staging, construction, vehicular use, borrow, or waste activities take place inside the ESAs.
	ESA * 2	33+00	37+00	Right	Minor Grading of a roadway and roadway ditch and Installation of property fence		Section 106 of the National Preservation Act	107.23F	The contractor ensure that no additional construction related activities including the use of easements staging, construction, vehicular use, borrow, or waste activities take place inside the ESAs.
	ESA * 3	33+00	40+40	Left	Minor Grading of a roadway ditch		Section 106 of the National Preservation Act	107.23F	The contractor ensure that no additional construction related activities including the use of easements staging, construction, vehicular use, borrow, or waste activities take place inside the ESAs.
A-1	Stream * 1	31+60	32+60	Both	Bridge Replacement	Activities with in 100 ft of the proposed bridge are exempt	Memo from EPD date 6/8/06 re: Buffer variance issues		Roadway drainage exemption - work beyond 100 ft of the proposed bridge will require a buffer variance or written permission from EPD prior to commencement of the activity.
A-3	Wetland * 2	25+90	29+40	Right	Placement of fill and a roadway ditch and the Installation of fence.	0.26 Permanent Impact 0.06 Temporary Impact	Section 404 of the CWA - NWP 14		Any additional fill or modifications to the wetland other than what is shown on the plans will require a permit modification or a new permit prior to commencement of the activity. Permit expires << >>
A-4	Wetland * 3	31+90	32+50	Both	Clearing and placement of Rip Rap	0.01 Permanent Impact 0.07 Temporary Impact	Section 404 of the CWA - NWP 14		Any additional fill or modifications to the wetland other than what is shown on the plans will require a permit modification or a new permit prior to commencement of the activity. Permit expires << >>
A-8	Georgia Railroad	12+00	26+00	Left	None	None	Section 106 of the National Preservation Act	107.23F	The contractor ensure that no construction related activities take place inside the historic boundary of the railroad. This includes staging, construction vehicular use, borrow, or waste activities, and trailer placement.
A-7	Clayton House	39+40	41+00	Right	None	None	Section 106 of the National Preservation Act	107.23F	The contractor ensure that no construction related activities take place inside the historic boundary of the Clayton House. This includes staging, construction vehicular use, borrow, or waste activities, and trailer placement.
A-6	Wetland * 5	30+73	31+80	Right	None	None	Section 404 of the CWA - NWP 14		
A-5	Ephemeral Channel * 4	29+50	30+75	Right	Placement of fill and a driveway	0.001 Permanent Impact 0.000 Temporary Impact	Section 404 of the CWA - NWP 14		
A-2	SI BUFFER	31+66	32+60	Both	Clearing and placement of Rip Rap	None	Section 106 of the National Preservation Act	107.23F	The contractor ensure that no additional construction related activities including the use of easements staging, construction, vehicular use, borrow, or waste activities take place inside the ESAs.

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 2 DESIGN - TENNILLE

GENERAL NOTES

DRAWING No.
04-002