SUMMARY OF PAVING QUANTITIES

LOCATION	GRADED AGGREGATE BASE COURSE, INCL. MAT'L	RECYCLED ASPHALTIC CONC. LEVELING INCL. BITUM. MAT'L & H. LIME	RECYCLED ASPHALTIC CONC. 25 mm SUPERPAVE, GP 1 OR 2 INCL. BITUM. MAT'L & H. LIME	RECYCLED ASPHALTIC CONC. 19 mm SUPERPAVE, GP 1 OR 2 INCL. BITUM. MAT'L & H. LIME	RECYCLED ASPHALTIC CONC. 12.5 mm SUPERPAVE, GP 2 ONLY, INCL. BITUM. MAT'L & H. LIME	BITUM. TACK COAT	PVMT REINF FABRIC STRIPS, TP 2, 18 IN WIDE	MILL ASPH CONC PVMT, VARIABLE DEPTH	APSHALTIC CONCRETE CURB - 4 IN	CONCRETE SIDEWALK, 8 IN	RIGHT OF WAY MARKERS
	TON	TON	TON	TON	TON	GAL	LIN FT	SQ YD	LIN FT	SQ YD	EACH
SR 1/US 27	75	90	40	10	526	322	135	733	80	9	4
SR 1/US 27 SHLDR PVMT				14	11	7					
CR 587/BICENTENNIAL TRL	616	10	340	100	74	90	520	116	109	23	5
CR 587 SHLDR PVMT				7	6	3					
AS DIRECTED BY ENGINEER	9		20	9	18	6	15	11	11	3	
TOTALS	700	100	400	140	635	428	670	860	200	35	9

GUARDRAIL

GA. STDS. 4011-A, 4012-D, 4040, 4270 & 4360

LOCATION (STATION)	'T' BEAM	TYPE 1 ANCHOR GA. STD. 4012-D	TYPE 12 ANCHOR GA. STD. 4040
	LF	EACH	EACH
SR 1/US 27			
STA 109+26.88 - STA 110+15.00 LT	87.5		1
CR 587/BICENTENNIAL TRL			
STA 204+89.08 - STA 205+84.61LT	137.5	1	
TOTAL	225	1	1

GRAVITY TYPE WALL

GA. STD, 9031L

LOCATION (STATION)	CLASS B CONCRETE
	CU YD
SR 1/US 27 @ CR 587/BICENTENNIAL TRL	
STA 205+29.56 LT - STA 109+13.19 LT	25
TOTAL	25

TRAFFIC CONTROL

CSSTP-0007-00(081)	LUMP SUM

PLAIN CONCRETE DITCH PAVING, 4 IN

CSSTP-0007-00(081)	3 SQ YD

SUMMARY OF DRIVEWAY QUANTITIES

LOCATION (STATION)	GRADED AGGREGATE BASE COURSE, 6 IN INCL. MAT'L	RECYCLED ASPHALTIC CONC. 19 mm SUPERPAVE, GP 1 OR 2 INCL. BITUM. MAT'L & H. LIME	RECYCLED ASPHALTIC CONC. 12.5 mm SUPERPAVE, GP 2 ONLY, INCL. BITUM. MAT'L & H. LIME	BITUM. TACK COAT
	TON	TON	TON	GAL
CR 587/BICENTENNIAL TRL STA 203+43 RT.	14	5	4	2
AS DIRECTED BY ENGINEER	1		1	
TOTALS	15	5	5	2

STORM DRAIN QUANTITIES

PIPES				INLETS & MISC. DRAINAGE ITEMS							
ALLOWABLE MATERIALS: SEE TABLE PER DRAWING 4-01				STORM SEWER MANHOLE, TP 1 GA STD 1011A	STORM SEWER MANHOLE, TP 1, ADDL DEPTH, CL 2	MEDIAN DROP INLET, CONC. BOX, DOUBLE WEIR, GA STD 9031S	FLARED END SECTION 18 IN. STORM DRAIN, GA STD 1120	FLARED END SECTION 24 IN. STORM DRAIN, GA STD 1120	STONE DUMPED RIP RAP, TP 3, 18 IN	PLASTIC FILTER FABRIC	
LIN. FT.											
STR. No.	LOCATION	SIDE	STORM DRAIN PIPE, H 1-10 18"	STORM DRAIN PIPE, H 1-10 24"	STORM DRAIN PIPE, H 1-10 30"		EA.	LF.	EA.	EA.	EA.	SQ. YD.	SQ. YD.	REMARKS
A1	SR 1/US 27 STA. 107+83.73	49.39' LT.		18										REMOVE HEADWALL ADD CONC. COLLAR
A2	SR 1/US 27 STA. 107+85.12	67.34' LT.		54			1	5.75						
A3	SR 1/US 27 STA. 107+57.44	114.13' LT.									1	19	19	
B1	BICENTENNIAL TRL STA. 204+74.90	29.60' LT.	93						1			8	8	
B2	BICENTENNIAL TRL STA. 204+85.54	69.11' RT.								1		11	11	
	TOTAL		93	72			1	5.75	1	1	1	38	38	
	AS DIRECTED BY ENGINEER		7	8				0.25				2	2	
	GRAND TOTAL		100	80			1	6	1	1	1	40	40	

GRADING COMPLETE

CSSTP-0007-00(081)	LUMP SUM

CONCRETE SPILLWAY, TP 3

CSSTP-0007-00(081)	2 EACH

PBS&J

REVISION DATES		
01/04/2011		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: TRAFFIC SAFETY & DESIGN

SUMMARY QUANTITIES

SR 1 @ BICENTENNIAL TRAIL

DRAWING No. 6-01