SUMMARY TRAFFIC SIGNAL ITEMS

LOCATION	INSTL. #	DIRECTIONAL BORE 3 IN (LF)	HWY SIGNS TP 2 MATL, REFL SHEET TP 9 (SF)	PRESTRESSED CONCRET STRAIN POLE, TP IV (EA)	TRAFFIC SIGNAL INSTALLATION (LUMP)	CONDUIT NONMETAL, TP 3, 2 IN (LF)	LUMINAIRE BRACKET ARM, 10 FT ARM (EA)	INTERSECTION VIDEO DETECTION SYSTEM ASSEMBLY, TYPE A (EA)	PROGRAMMING MONITOR, TYPE A (EA)
		QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
US 27/SR 1/ MARTHA BERRY HWY AT CR 587 BICENTENNIAL TRAIL	1	390	38	1	LUMP	1000	2	2	1
TOTALS		390	38	1	LUMP	1000	2	2	1

TESTING (937-8030)	
UNIT	QUANTITY
LUMP	LUMP

TRAFFIC SIGNAL LEGEND

EXISTING SIGNAL

- CONTROLLER CABINET
- STRAIN POLE
- TIMBER POLE
- DOWN GUY
- MAST ARM
- STREET LIGHT
- 3 SECTION HEAD
- 5 SECTION HEAD
- OVERHEAD SIGN
- PEDESTAL POLE
- PEDESTRIAN SIGNAL HEAD
- PULLBOX, PB-1
- PULLBOX, PB-2
- PULLBOX, PB-3
- PULLBOX, PB-4
- PULLBOX, PB-5
- D VIDEO DETECTION ZONES
- D
- L 6' X 6' SETBACK LOOP
- L 6' X 40' QUADRUPOLE LOOP
- CONDUIT
- RAILROAD CONTROLLER
- SIGN POST

PROPOSED SIGNAL

- CONTROLLER CABINET
- STRAIN POLE
- TIMBER POLE
- DOWN GUY
- MAST ARM
- STREET LIGHT/ LUMINAIRE ARM
- 3 SECTION HEAD
- 3 SECTION HEAD W/ BACKPLATE
- 5 SECTION HEAD
- 5 SECTION HEAD W/ BACKPLATE
- OVERHEAD SIGN
- PEDESTAL POLE
- PEDESTRIAN SIGNAL HEAD
- VIDEO DETECTION CAMERA
- PULLBOX, PB-1
- PULLBOX, PB-2
- PULLBOX, PB-3
- PULLBOX, PB-6
- PULLBOX, PB-7
- D VIDEO DETECTION ZONES
- D
- L 6' X 6' SETBACK LOOP
- L 6' X 40' QUADRUPOLE LOOP
- CONDUIT
- RAILROAD CONTROLLER
- SIGN POST

PBS&J

REVISION DATES		

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: TRAFFIC OPERATIONS

TRAFFIC SIGNAL SUMMARY

SR 1 @ BICENTENNIAL TRAIL

DRAWING No. 6-05