| ITEM NO. | DESCRIPTION | UNITS | QUANTITY |
|---|---|---|---|
| . | ROADWAY ITEMS | | |
| . | | | |
| 150-1000 | TRAFFIC CONTROL - CSHPP-0007-00(131) | LS | 1.00 |
| 207-0203 | FOUND BKFILL MATL, TP II | CY | 50.00 |
| 210-0100 | GRADING COMPLETE - CSHPP-0007-00(131) | LS | 1.00 |
| 310-1101 | GR AGGR BASE CRS, INCL MATL | TN | 8500.00 |
| 318-3000 | AGGR SURF CRS | TN | 690.00 |
| 402-1812 | RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME | TN | 900.00 |
| 402-3121 | RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME | TN | 2050.00 |
| 402-3130 | RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME | TN | 6620.00 |
| 402-3190 | RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME | TN | 1600.00 |
| 413-1000 | BITUM TACK COAT | GL | 10500.00 |
| 432-0206 | MILL ASPH CONC PVMT, 1 1/2 IN DEPTH | SY | 62000.00 |
| 441-0016 | DRIVEWAY CONCRETE, 6 IN TK | SY | 50.00 |
| 441-0018 | DRIVEWAY CONCRETE, 8 IN TK | SY | 700.00 |
| 441-0104 | CONC SIDEWALK, 4 IN | SY | 4190.00 |
| 441-0108 | CONC SIDEWALK, 8 IN | SY | 2000.00 |
| 441-0748 | STAMPED CONCRETE MEDIAN, 6 IN , COLORED | SY | 4200.00 |
| 441-4030 | CONC VALLEY GUTTER, 8 IN | SY | 1000.00 |
| 441-5002 | CONCRETE HEADER CURB, 6 IN, TP 2 | LF | 2000.00 |
| 441-6222 | CONC CURB & GUTTER, 8 IN X 30 IN, TP 2 | LF | 1300.00 |
| 446-1100 | PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH | LF | 6200.00 |
| 500-9999 | CLASS B CONC, BASE OR PVMT WIDENING | CY | 40.00 |
| 550-1150 | STORM DRAIN PIPE, 15 IN, H 1-10 | LF | 200.00 |
| 550-1180 | STORM DRAIN PIPE, 18 IN, H 1-10 | LF | 120.00 |
| 550-1240 | STORM DRAIN PIPE, 24 IN, H 1-10 | LF | 90.00 |
| 611-3000 | RECONSTR CATCH BASIN, GROUP 1 | EA | 128.00 |
| 611-3010 | RECONSTR DROP INLET, GROUP 1 | EA | 34.00 |
| 611-3030 | RECONSTR STORM SEW MANHOLE, TYPE 1 | EA | 13.00 |
| 611-4001 | RECONSTR MINOR DRAINAGE STR | EA | 1.00 |
| 611-8050 | ADJUST MANHOLE TO GRADE | EA | 14.00 |
| 620-0100 | TEMPORARY BARRIER, METHOD NO. 1 | LF | 1300.00 |
| 634-1200 | RIGHT OF WAY MARKERS | EA | 32.00 |
| 641-1100 | GUARDRAIL, TP T | LF | 173.00 |
| 641-1200 | GUARDRAIL, TP W | LF | 187.00 |
| 641-5001 | GUARDRAIL ANCHORAGE, TP 1 | EA | 13.00 |
| 641-5012 | GUARDRAIL ANCHORAGE, TP 12 | EA | 5.00 |
| 643-8200 | BARRIER FENCE (ORANGE), 4 FT | LF | 2400.00 |
| 668-1100 | CATCH BASIN, GP 1 | EA | 13.00 |
| 668-1110 | CATCH BASIN, GP 1, ADDL DEPTH | LF | 3.00 |
| 668-2100 | DROP INLET, GP 1 | EA | 8.00 |
| 668-4300 | STORM SEWER MANHOLE, TP 1 | EA | 3.00 |
| 668-4311 | STORM SEWER MANHOLE, TP 1, ADDL DEPTH, CL 1 | LF | 1.00 |
| 668-5000 | JUNCTION BOX | EA | 3.00 |
| . | | | |
| . | | | |
| . | | | |
| . | | | |
| . | | | |
| . | | | |
| . | | | |
| . | | | |
| . | | | |
| . | | | |
| . | | | |
| . | | | |

| ITEM NO. | DESCRIPTION | UNITS | QUANTITY |
|---|---|---|---|
| . | SIGNING & MARKING ITEMS | | |
| . | | | |
| 610-6515 | REM HIGHWAY SIGN, STD | EA | 2.00 |
| 610-6873 | REM CONCRETE STRAIN POLE | EA | 22.00 |
| 611-5360 | RESET HIGHWAY SIGN | EA | 2.00 |
| 636-1020 | HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3 | SF | 238.00 |
| 636-1033 | HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9 | SF | 960.00 |
| 636-1041 | HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 9 | SF | 55.00 |
| 636-2070 | GALV STEEL POSTS, TP 7 | LF | 2077.00 |
| 636-2080 | GALV STEEL POSTS, TP 8 | LF | 265.00 |
| 636-2090 | GALV STEEL POSTS, TP 9 | LF | 73.00 |
| 636-3010 | GROUND-MOUNTED BREAKAWAY SIGN SUPPORT | EA | 16.00 |
| 636-5100 | MILEPOST SIGNS | EA | 6.00 |
| 653-0110 | THERMOPLASTIC PVMT MARKING, ARROW, TP 1 | EA | 2.00 |
| 653-0120 | THERMOPLASTIC PVMT MARKING, ARROW, TP 2 | EA | 56.00 |
| 653-0130 | THERMOPLASTIC PVMT MARKING, ARROW, TP 3 | EA | 5.00 |
| 653-0160 | THERMOPLASTIC PVMT MARKING, ARROW, TP 6 | EA | 74.00 |
| 653-0170 | THERMOPLASTIC PVMT MARKING, ARROW, TP 7 | EA | 4.00 |
| 653-0210 | THERMOPLASTIC PVMT MARKING, WORD, TP 1 | EA | 1.00 |
| 653-1501 | THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE | LF | 40500.00 |
| 653-1502 | THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW | LF | 37000.00 |
| 653-1704 | THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE | LF | 4550.00 |
| 653-1804 | THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE | LF | 18500.00 |
| 653-3501 | THERMOPLASTIC SKIP TRAF STRIPE, 5 IN, WHITE | GLF | 15900.00 |
| 653-6004 | THERMOPLASTIC TRAF STRIPING, WHITE | SY | 1650.00 |
| 653-6006 | THERMOPLASTIC TRAF STRIPING, YELLOW | SY | 580.00 |
| 654-1001 | RAISED PVMT MARKERS TP 1 | EA | 55.00 |
| 654-1003 | RAISED PVMT MARKERS TP 3 | EA | 660.00 |
| . | | | |
| . | SIGNALIZATION & CCTV ITEMS | | |
| . | | | |
| 615-1200 | DIRECTIONAL BORE - 3 IN | LF | 3450.00 |
| 639-2002 | STEEL WIRE STRAND CABLE, 3/8 IN | LF | 3736.00 |
| 639-4003 | STRAIN POLE, TP III | EA | 22.00 |
| 639-4004 | STRAIN POLE, TP IV | EA | 24.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 1 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 2 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 4 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 5 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 6 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 7 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 8 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 9 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 10 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 11 | LS | 1.00 |
| 647-1000 | TRAFFIC SIGNAL INSTALLATION NO - 12 | LS | 1.00 |
| 647-2160 | PULL BOX, PB-6 | EA | 10.00 |
| 682-6233 | CONDUIT, NONMETL, TP 3, 2 IN | LF | 8080.00 |
| 687-1000 | TRAFFIC SIGNAL TIMING - CSHPP-0007-00(131) | LS | 1.00 |
| 935-1511 | OUTSIDE PLANT FIBER OPTIC CABLE, DROP, SINGLE MODE, 6 FIBER | LF | 2150.00 |
| 935-4010 | FIBER OPTIC SPLICE, FUSION | EA | 30.00 |
| 935-8000 | TESTING | LS | 1.00 |
| 936-1001 | CCTV SYSTEM, TYPE B | EA | 5.00 |
| 939-1191 | VIDEO ENCODER, TYPE B | EA | 5.00 |
| 939-1195 | VIDEO DECODER, TYPE A | EA | 5.00 |
| 939-2305 | FIELD SWITCH, TYPE C | EA | 5.00 |
| . | | | |

JORDAN JONES & GOULDING

REVISION DATES
6-29-09
8-13-09

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: DISTRICT 7

# DETAILED ESTIMATE

MEMORIAL DRIVE STREETSCAPE PH 3
FROM WOODCROFT BD TO GOLDSMITH RD

DRAWING No. 9-01

GPLN