DRAINAGE ITEMS

STRUCTURE NUMBER	LOCATION	HT. OF FILL LIN.FT.	18" SLOPE DRAIN PIPE LIN.FT.	10" STORM DRAIN PIPE LIN.FT.	18" STORM DRAIN PIPE LIN.FT.	24" STORM DRAIN PIPE EACH	30" STORM DRAIN PIPE EACH	CATCH BASIN, GPI, GA. STD. 1033D EACH	CATCH BASIN, GPI, GA. STD. 1034D EACH	JUNCTION BOX, GPI, GA. STD. 9031U EACH	CATCH BASIN, GPI, ADD'L DEPTH LIN.FT.	CATCH BASIN, GPI, GA. STD. 1033B LIN.FT.	DROP INLET, GPI, GA. STD. 1019A EACH	FES GA. STD. 1120 EACH	MEDIAN DROP INLET GPI, GA. STD. 9031S EACH	ADJUST STR. TO GRADE EACH	RECONSTR MINOR DRAINAGE STR EACH
B1.0	STA 107+95.00, 131.00' RT													1 (18")			
B2.0	STA 107+95.00, 34.00' RT	2.1	35		4			1									
C1.0	STA 109+00.00, 114.30' LT													1 (18")			
C2.0	STA 109+00.00, 35.00' RT	2.1	28		4			1									
D1.0	STA 111+50.00, 95.50' LT													1 (18")			
D2.0	STA 111+50.00, 35.00' LT	2.1	20		4			1									
E1.0	STA 112+27.68, 86.00' LT													1 (18")			
E2.0	STA 112+27.68, 35.00' LT	3.2	24		4												
F1.0	STA 112+10.00, 86.00' LT													1 (24")			
F2.0	STA 114+65.00, 63.00' RT	5.4				253				1							
F3.0	STA 203+20.00, 22.00' RT	6.1				87		1			2.48						
F4.0	STA 203+20.00, 22.00' LT	6.1				45		1			2.26						
F5.0	STA 116+05.00, 59.72' RT	5.6				79				1							
G1.0	STA 113+50.00, 72.00' LT													1 (18")			
G2.0	STA 113+50.00, 35.00' LT	5.5			25			1									
H1.0	STA 116+65.00, 72.00' LT													1 (18")			
H2.0	STA 116+65.00, 47.00' LT	3.6			24			1									
J1.0	STA 117+60.00, 72.00' LT													1 (18")			
J2.0	STA 117+60.00, 47.00' LT	3.6			25			1									
K1.0	STA 118+85.00, 70.00' LT													1 (30")			
K2.0	STA 118+90.00, 39.50' LT	3.5					26	1			0.21						
K3.0	STA 121+10.00, 47.00' LT						214	1			0.17						
K4.0	STA 122+50.00, 35.00' LT	3.6				137		1									
K5.0	STA 124+20.00, 35.00' LT	3.4				168		1									
K6.0	STA 125+75.00, 35.00' LT	3.1				155		1									
K7.0	STA 127+55.00, 35.00' LT	3.6			180			1									
K8.0	STA 129+20.00, 35.00' LT	3.3			165			1									
K9.0	STA 131+00.00, 35.00' LT	3.1			180			1									
K10.0	STA 132+50.00, 35.00' LT	3.1			150			1									
K11.0	STA 135+40.00, 35.00' LT	3.0			290			1									
K12.0	STA 136+90.00, 47.00' LT	3.0			151			1									
K13.0	STA 139+05.00, 35.00' LT	3.1			215			1									
L1.0	STA 122+85.00, 63.05' RT													1 (18")			
L2.0	STA 123+75.00, 57.80' RT	5.0			90										1		
L3.0	STA 124+55.00, 50.80' RT	2.0			81								1				
L4.0	STA 124+55.00, 35.00' RT	3.3			16			1									
L5.0	STA 125+75.00, 35.00' RT	3.4			120			1									
L6.0	STA 126+95.00, 47.00' RT	3.0			119												
L7.0	STA 128+20.00, 47.00' RT	2.5			105							1					
L8.0	STA 129+40.00, 35.00' RT	2.6			140							1					
L3.1	STA 125+45.00, 52.00' RT	2.3			89							1		1 (18")			
N1.0	STA 131+12.00, 48.50' RT													1 (18")			
N2.0	STA 131+35.00, 35.00' RT	4.0			27			1									
N3.0	STA 133+45.00, 35.00' RT	3.3			210			1									
N4.0	STA 136+00.00, 35.00' RT	2.9			255			1									
N5.0	STA 137+05.00, 35.00' RT	2.9			105			1									
N6.0	STA 139+50.00, 47.00' RT	3.1			245			1									
N7.0	STA 140+95.00, 35.00' RT	3.2			146			1									
N8.0	STA 142+90.00, 35.00' RT	3.1			195			1									
P1.0	STA 139+75.00, 51.40' LT													1 (18")			
P2.0	STA 123+75.00, 57.80' LT	2.4			53								1				
P3.0	STA 141+90.00, 47.00' LT	2.9			161			1									
P4.0	STA 142+90.00, 47.00' LT	2.9			100			1									
P5.0	STA 144+15.00, 41.70' LT	2.9			124									1 (18")			
O1.0	STA 116+25.00, 83.80' RT	3.0			27								1				
EXIST.	STA 116+40.00, 60.90' RT														1		
R1.0	STA 118+30.00, 88.70' RT	2.0		47									1				
S1.0	STA 119+52.30, 63.00' RT	2.8			15											1	
EXIST. STR.	STA 117+10, 49.00' RT																
EXIST.	STA 117+97.10, 59.70' RT															1	
EXIST.	STA 119+58.10, 49.10' RT																1
EXIST.	STA 120+30.10, 50.70' RT																
T1.0	STA 201+26.00, 69.00' RT													1 (18")			
T2.0	STA 200+78.00, 22.00' LT	3.3			28												
T3.0	STA 200+78.00, 24.00' LT	2.4			40												
U1.0	STA 121+38.00, 61.00' RT				29									1 (18")			
V1.0	STA 120+68.00, 77.70' LT													1 (24")			
V2.0	STA 120+52.00, 76.60' LT	2.5				11							1				
V3.0	STA 120+21.00, 74.00' LT	2.2				32							1				
V4.0	STA 120+03.00, 72.30' LT	2.9				10								1 (24")			
W1.0	STA 301+15.00, 30.00' LT		10														
FORTNER RD.	STA. 110+92						102								2 (30")		
RELOCATED FORTNER RD.	STA. 115+40						120								2 (30")		
TOTAL			107	57	3941	977	462	31	1	2	5.12	3	4	22	2	2	3

URS
400 NORTHPARK TOWN CENTER
1000 ABERNATHY RD., N.E.
SUITE 900
ATLANTA, GA. 30328
TEL: (678) 808-8800 FAX: (678) 808-8400

GRESHAM SMITH AND PARTNERS

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC OPERATIONS

QUANTITY SUMMARY SHEET

SR 23/121 FROM I-16 TO LYTELL STREET

DRAWING NO. 6-002

GPLAN