

Resource Name/Type	Location		Side	Construction Activity	Permitted Activity	Controlling Criteria	Special Provision?	Comments including any permit expiration dates
	Beginning STA	Ending STA						
Stream 33 Buffer	737+00	737+50	Rt	Culvert extension	Activities within 50 feet of the proposed culvert are exempt	Georgia Erosion and Sedimentation Control Act; 391-3-7-.05 GA DNR Rules for Erosion and Sedimentation Control		Roadway drainage exemption - work beyond 50 feet of the proposed culvert will require a buffer variance or written permission from EPD prior to commencement.
Migratory birds	737+40	737+45	both	Culvert extension	Refer to Special Provision 107.23	Migratory Bird Treaty Act	107.23G	The Office of Environmental Services shall be contacted prior to installation of exclusionary devices. Contractor shall direct questions to the Engineer, and the Engineer shall contact Environmental Services if necessary for resolution.
Wtl 34/Wetland	736+00	738+40	Rt	Culvert extension/Bank armor	0.014 acres permanent impact	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Wtl 37/Wetland	739+25	743+95	Lt	Roadway widening and culvert extension	0.002 acre temporary and 0.026 acre permanent impact	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
38	745+50	746+80	both	Culvert extension	0.007 acre permanent impact	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Historic Resource - Tillery House	813+50	813+05	Lt	None	N/A	AOE		N/A
Historic Resource - Omega Historic District	847+00	894+00	Both	Intersection improvements at Cemetery Road and Gibbs Patrick Road	N/A	AOE		NA
Pond 43 Buffer	847+00	848+50	Rt	Roadway widening	125 linear feet / 0.02 acre pond buffer impacts	Georgia Erosion and Sedimentation Control Act; 391-3-7-.05 GA DNR Rules for Erosion and Sedimentation Control		Work beyond requested buffer variance impact area will require a written permission from EPD prior to commencement.
PS44/Perennial Stream	848+70	848+80	Rt	Culvert extension/Bank armor	20.1 linear feet / 0.0018 acre stream impacts	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Stream 44 Buffer	848+40	848+90	Rt	Culvert extension	Activities within 50 feet of the proposed culvert are exempt	Georgia Erosion and Sedimentation Control Act; 391-3-7-.05 GA DNR Rules for Erosion and Sedimentation Control		Roadway drainage exemption - work beyond 50 feet of the proposed culvert will require a buffer variance or written permission from EPD prior to commencement.
Wtl 45/Wetland	847+00	850+20	Lt	Roadway widening and culvert extension	0.17 acre temporary and 0.043 acre permanent impact	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.

CWA Clean Water Act
RPI U.S. Army Corps of Engineers, Savannah District, Regional Permit 01
EPD Georgia Department of Natural Resources Environmental Protection Division
DNR Georgia Department of Natural Resources

Resource Name/Type	Location		Side	Construction Activity	Permitted Activity	Controlling Criteria	Special Provision?	Comments including any permit expiration dates
	Beginning STA	Ending STA						
PS46/Perennial Stream	848+90	849+20	Rt	Roadway widening and culvert extension	50 linear feet / 0.002 acre stream impact	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Stream 46 Buffer	848+90	849+40	Rt	Roadway widening and culvert extension	Activities within 50 feet of the proposed culvert are exempt	Georgia Erosion and Sedimentation Control Act; 391-3-7-.05 GA DNR Rules for Erosion and Sedimentation Control		Roadway drainage exemption - work beyond 50 feet of the proposed culvert will require a buffer variance or written permission from EPD prior to commencement.
Wtl 47/Wetland	850+90	854+60	Rt	Roadway widening	0.027 acre temporary and 0.038 permanent impacts	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Historic Resource - Omega Farm Historic District	909+00	939+00	Both	None	N/A	AOE		N/A
Historic Resource - Ford Farm	996+00	1005+00	Rt	Intersection improvements at Urbana Road/CR 59	N/A	AOE		N/A
Pond 49	1007+85	1010+00	Rt	Culvert extension/Bank armor	0.007 acre permanent impact	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Pond 49 Buffer	1007+40	1010+00	Rt	Roadway widening and culvert extension	Activities within 50 feet of the proposed culvert are exempt; buffer variance requested for 100 linear feet / 0.03 acre buffer impacts	Georgia Erosion and Sedimentation Control Act; 391-3-7-.05 GA DNR Rules for Erosion and Sedimentation Control		Roadway drainage exemption - work beyond 50 feet of the proposed culvert and requested buffer variance impact area will require a buffer variance or written permission from EPD prior to commencement.
PS50/Perennial Stream	1008+15	1008+25	Lt	Culvert extension	10.3 linear feet / 0.001 acre stream impacts	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Historic Resource - Bowen House	1046+00	1047+50	Rt	None	N/A	AOE		N/A
Pond 52	1049+50	1052+70	Rt	Culvert extension/Bank armor	0.002 permanent impacts	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Pond 52 Buffer	1050+75	1051+00	Rt	Culvert extension/Bank armor	Activities within 50 feet of the proposed culvert are exempt	Georgia Erosion and Sedimentation Control Act; 391-3-7-.05 GA DNR Rules for Erosion and Sedimentation Control		Roadway drainage exemption - work beyond 50 feet of the proposed culvert will require a buffer variance or written permission from EPD prior to commencement.
Wtl 53/Wetland	1048+80	1052+30	Lt	Roadway widening and culvert extension	0.01 acre temporary impact	Section 404 CWA - RPI		Permit application under review. Additional impacts other than what is shown on plans will require a permit modification or new permit prior to commencement of activity.
Historic Resource - Moore House	1051+00	1073+00	Lt	Improvements to W.R. Ponder Road/Iniss Road/CR 81 Intersection	N/A	AOE		N/A

REVISION DATES		STATE OF GEORGIA DEPARTMENT OF TRANSPORTATION OFFICE: TRAFFIC SAFETY & DESIGN GENERAL NOTES
US 319/SR 35 COLQUITT/TIFT COUNTIES		DRAWING No. 4-05



GPLN
1:29:52 PM
w:\TransDesign\plot\colorables\XeroxGREY.tbl
w:\TransDesign\plot\pentables\Xerox_FS.pen