SURFACING QUANTITIES

ITEMS	UNIT	MAINLINE	MAINLINE CROSSOVERS	RAMPS	TEMPORARY RAMP PAVEMENT	RELOC. CR 173	CR 100	DRIVEWAYS	SUB TOTAL	AS DIRECTED BY ENGINEER	TOTAL
RECYCLED ASPH CONC 12.5 mm SUPERPAVE, GP 2, INCL BITUM MATL & H LIME	TON		2900				264	321	3485	15	3500
RECYCLED ASPH CONC 25 mm SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TON		646		826				1472	8	1480
RECYCLED ASPH CONC LEVELING, INCL BITUM & H LIME	TON	1593	1595	1391					4579	421	5000
MILL ASPH CONC PVMT, 1-1/2 IN DEPTH	CU YD		10906						10925	94	11000
CLASS B CONC, BASE OR PVMT WIDENING	CU YD									30	30
BITUMINOUS TACK COAT	GAL	1664	507	443	120		102	128	2964	36	3000
INDENTATION RUMBLE STRIPS - GROUND IN PLACE (CONTINUOUS)	GLM	2	1						3	0	3
HIGH STRENGTH PAVEMENT REINFORCING FABRIC - 18 INCH WIDE	LIN FT	2300							2300	0	2300
ASPHALTIC CONCRETE CURB - 5 IN	LIN FT	975							975	125	1100
ALTERNATE *1											
PLAIN PC CONC PVMT, CL 1 CONC, 10 INCH THK	SQ YD	48390		4149		2397			54936	64	55000
RECYCLED ASPH CONC 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TON	11620	529	1329	413	395	351	402	15039	161	15200
GRADED AGGREGATE BASE COURSE	TON	30485	2592	5074	144	1113	1348	44	41800	0	40800
ALTERNATE *2											
PLAIN PC CONC PVMT, CL 1 CONC, 10 INCH THK	SQ YD	49431		4149		2397			55997	23	56000
RECYCLED ASPH CONC 19 mm SUPERPAVE, GP 1 OR 2, INCL BITUM & H LIME	TON	11791	529	1329	413	395	351	402	15210	290	15500
GRADED AGGREGATE BASE COURSE	TON	31142	2592	5074	144	1113	1348	44	41457	18	41475
MILL ASPH CONC PVMT, VARIBLE DEPTH	SY									30	30

GUARDRAIL QUANTITIES - ALT #1

LOCATION & SIDE	SIDE	"W" BEAM FT	"T" BEAM FT	ANCHORAGES TP 1	ANCHORAGES TP 12
STA 1091+50 TO STA 1093+53	LT	160	21	1	
STA 1091+63 TO STA 1093+18	RT	112	21		1
STA 1096+60 TO STA 1098+60	LT	157	21		1
STA 1096+05 TO STA 1099+00	RT	252	21	1	
STA 21+57 RAMP G TO STA 1087+00	LT	368		1	1
STA 30+75 RAMP F TO STA 1104+25	RT	518		1	1
STA 1143+63 TO STA 1146+75 I-16	RT-MED	312		1	1
STA 1148+63 TO STA 1144+05 I-16	LT-MED	456		1	1
AS REQUIRED		177			
TOTALS		2702	84	6	6

NOTE: QUANTITIES AND LOCATIONS ARE SUBJECT TO ADJUSTMENT BY THE ENGINEER TO FIT FIELD CONDITIONS.

GUARDRAIL QUANTITIES - ALT #2

LOCATION & SIDE	SIDE	"W" BEAM FT	"T" BEAM FT	ANCHORAGES TP 1	ANCHORAGES TP 12
STA 1091+50 TO STA 1093+10	LT	203	21	1	
STA 1091+63 TO STA 1092+75	RT	155	21		1
STA 109703 TO STA 11098+60	LT	200	21		1
STA 1096+45 TO STA 1098+50	RT	245	21	1	
STA 21+57 RAMP G TO STA 1087+00	LT	368		1	1
STA 30+75 RAMP F TO STA 1104+25	RT	518		1	1
STA 1143+63 TO STA 1146+75 I-16	RT-MED	312		1	1
STA 1148+63 TO STA 1144+05 I-16	LT-MED	456		1	1
AS REQUIRED		177			
TOTALS		2856	84	6	6

NOTE: QUANTITIES AND LOCATIONS ARE SUBJECT TO ADJUSTMENT BY THE ENGINEER TO FIT FIELD CONDITIONS.

DRIVEWAY QUANTITIES

* NOTE: FOR INFORMATION ONLY; SEE SURFACING QUANTITIES BLOCK.

LOCATION STATION	SIDE FEET	WIDTH FEET	12.5MM SUPERPAVE TON	19MM SUPERPAVE TON	6 IN GRADED AGGREGATE BASE COURSE TON
1068+13	LT	36	25	34	3
1071+50	LT	14	7		1
1072+32	RT	14	8		1
1082+82	LT	40	45	60	6
1082+82	RT	36/24	143	191	20
1104+79	LT	40	37	50	5
1106+20	LT	24	23	31	3
CR 100					
24+57	LT		3	5	0
TOTAL			321	402	44

TRAFFIC CONTROL

CSNHS-0007-00(251) LUMP SUM

GRADING COMPLETE

LUMP SUM CSNHS-0007-00(251)

FIELD FENCE WOVEN WIRE

AS DIRECTED BY THE ENGINEER 2700 LIN FT.

FOUNDATION BACKFILL MATERIAL, TYPE II

AS DIRECTED BY THE ENGINEER 600 CY

TEMPORARY BARRIER, METHOD 1

TOTAL 7000 LF

TRAFFIC CONTROL PORTABLE IMPACT ATTENUATOR

TOTAL 10 EACH

* TO BE USED AS DIRECTED BY THE ENGINEER.

VOID

CHANGABLE MESSAGE SIGN PORTABLE TYPE 3

AS DIRECTED BY THE ENGINEER 4 EACH

TRAFFIC CONTROL, WORKZONE LAW ENFORCEMENT

HOUR 3000

* TO BE USED AS DIRECTED BY THE ENGINEER.

FIELD ENGINEER'S OFFICE- TYPE 3

1 EACH

AGGREGATE SURFACE COURSE

TOTAL 1200 TONS

* TO BE USED AS DIRECTED BY THE ENGINEER.

ORANGE BARRIER FENCE

TOTAL 8950 LF

RIGHT OF WAY MARKERS

CSNHS-0007-00(251)	EACH	95

GEORGIA DEPARTMENT OF TRANSPORTATION

REVISION DATES

STATE OF GEORGIA
DEPARTMENT OF TRANSPORTATION
OFFICE: ROADWAY DESIGN

SUMMARY OF QUANTITIES

SR 96 @ I-16

DRAWING No. 06-001