

SUMMARY OF QUANTITIES-OVERHEAD SIGNS & STRUCTURE SUPPORTS

MILE POST I-75/SR 401 NORTHBOUND LANE (NBL)/ SOUTHBOUND LANE (SBL)	ZONING	GUARD RAIL CA. STDS. 4010 & 4011A	GUARD RAIL ANCHORAGES CA. STDS. 402C & 4050A,B,C				ILLUMINATED SIGN SYSTEM REQUIRED (LUMP)	STRUCTURAL SUPPORT (LUMP)			HIGHWAY SIGNS, ALUM EXTRUDED PANELS, REFL SHEETING TP.3 (SQUARE FEET)					HIGHWAY SIGNS, ALUMINUM PANELS - INCL BRACKETS (SQUARE FEET)				
			LINEAR FEET	TYPE (EACH)				SUPPORT NO.	TYPE	SPAN (LF)	SIGN NO.	SIGN SIZE (1A)	SIGN SIZE (1B)	SUB-TOTAL	TOTAL	SIGN NO.	SIGN SIZE	SUB-TOTAL	TOTAL	
				I	II															
60.20 NBL								C0602	III	16	SP#100	16'-0" X 18'-0"	9'-0" X 2'-6"	310.50	310.50					
60.60 NBL								C0606	EXISTING TP. I		SP#101	16'-0" X 19'-0"	9'-0" X 2'-6"	326.50	326.50					
60.80 NBL								C0608	I	90	SP#102	16'-0" X 19'-0"	9'-6" X 2'-6"	327.75						
											SP#103	16'-0" X 19'-0"	9'-0" X 2'-6"	326.50	654.25					
61.40 NBL								C0614	EXISTING TP. I		SP#104	12'-0" X 19'-0"	10'-0" X 2'-6"	253.00						
											SP#105	16'-0" X 19'-0"	9'-6" X 2'-6"	327.75	580.75					
61.20 SBL								D0612	EXISTING TP. I		SP#106	16'-0" X 19'-0"	9'-0" X 2'-6"	326.50	326.50					
61.40 SBL								D0614	EXISTING TP. I		SP#107	16'-0" X 19'-0"	9'-0" X 2'-6"	326.50	326.50					
61.80 SBL								D0618	EXISTING TP. I		SP#108	16'-0" X 19'-0"	9'-0" X 2'-6"	326.50						
											SP#109	16'-0" X 19'-0"	9'-6" X 2'-6"	327.75	654.25					
62.30 SBL								D0623	III	16	SP#110	16'-0" X 19'-0"	9'-6" X 2'-6"	327.75	327.75					
TOTALS								3			11				3507.00					

GEORGIA
DEPARTMENT
OF
TRANSPORTATION

REVISION DATES

STATE OF GEORGIA	
DEPARTMENT OF TRANSPORTATION	
OFFICE:	ROADWAY DESIGN
SUMMARY QUANTITIES	

P. I. NO. 0007273
TIFT COUNTY

DRAWING No.
6-006